

SITE DATA:

OWNER / DEVELOPER: 593 NORTH STATE RD. LLC.
PROJECT LOCATION: OSSINING, NY, 10510
EXISTING TOWN ZONING: GB, GENERAL BUSINESS
PROPOSED USE: GB, GENERAL BUSINESS
TOWN TAX MAP DATA: SECTION 90.11, BLOCK 1, LOT 36
SITE AREA: 0.697 ACRES (30,368 SF)
SEWAGE FACILITIES: PUBLIC SEWERS
WATER FACILITIES: PUBLIC WATER FACILITIES

ZONING SCHEDULE:

ZONING DISTRICT:		GB, GENERAL BUSINESS		
DIMENSIONAL REGULATIONS:	REQUIRED	PROVIDED	VARIANCE REQUIRED	
MINIMUM SIZE OF LOT:				
MINIMUM LOT AREA:	20,000 SF.	30,368 SF.	NONE	
MINIMUM LOT WIDTH:	100 FT.	201 FT.	NONE	
MINIMUM LOT DEPTH:	130 FT.	132 FT.	NONE	
MINIMUM YARD DIMENSIONS:				
PRINCIPAL BUILDING:				
FRONT YARD SETBACK:	30 FT.	55.2 FT.	NONE	
REAR YARD SETBACK:	0, 30 FT. (1)	67.8 FT.	NONE	
ONE SIDE YARD SETBACK:	0, 30 FT. (1)	22.6 FT.	NONE	
COMBINED SIDE YARD SETBACK:	---	---	NONE	
ACCESSORY BUILDINGS:				
FRONT YARD SETBACK:	30 FT.	---	NONE	
REAR YARD SETBACK:	30 FT. (1)	---	NONE	
ONE SIDE YARD SETBACK:	30 FT. (1)	---	NONE	
COMBINED SIDE YARD SETBACK:	---	---	NONE	
MAXIMUM % OF LOT TO BE OCCUPIED:				
TOTAL BUILDING COVERAGE:	30% OF LOT AREA	5.6 % OF LOT AREA	NONE	
MAXIMUM HEIGHT:				
PRINCIPAL BUILDING - FEET:	35 FT.	35 FT. MAX	NONE	
PRINCIPAL BUILDING - STORIES:	2	2	NONE	
ACCESSORY BUILDING - FEET:	35 FT.	---	NONE	
ACCESSORY BUILDING - STORIES:	2	---	NONE	

ZONING REGULATION NOTES:
1. SETBACK SHALL BE 30 FT. ALONG ANY RESIDENCE DISTRICT BOUNDARY, 0 FT. OTHERWISE.

PARKING SCHEDULE

REQUIRED PARKING:	1 SPACE PER 200 SF RETAIL FLOOR AREA 1 SPACE PER 300 SF OFFICE FLOOR AREA
COMBINATION RETAIL/ OFFICE BUILDING:	1691 S.F. @ 1 SPACES/200 S.F. = 9 SPACES 1691 S.F. @ 1 SPACES/300 S.F. = 6 SPACES TOTAL = 15 SPACES
PROVIDED PARKING:	2 GARAGE 14 STANDARD 1 HANDICAP
TOTAL PROVIDED PARKING:	15 SPACES
PARKING VARIANCE REQUIRED:	0 SPACES

- NOTES:**
- THE EXISTING TWO STORY BUILDING SHALL BE USED AS A COMBINATION OFFICE AND SHOW ROOM FOR THE PROPOSED PLUMBING BUSINESS. THE FIRST FLOOR SHALL BE USED FOR THE SHOW ROOM AND STORAGE SPACE. AND THE SECOND FLOOR SHALL BE USED AS OFFICE SPACE.
 - SITE IS TRIBUTARY TO POCANTICO RIVER
 - THERE SHALL BE NO OUTDOOR STORAGE OF ANY MATERIALS ON THE LOT.
 - THERE SHALL BE NO OUTDOOR PARKING OF ANY CONSTRUCTION EQUIPMENT ON THE LOT
 - ALL TREE PLANTINGS SHALL BE TAKEN FROM THE FOLLOWING LIST:
 - RED MAPLE (ACER RUBRUM)
 - SUGAR MAPLE (ACER SACCHARUM)
 - SHAGBARK HICKORY (CARYA OVATA)
 - TULIP TREE (LIRIODENDRON TULIPIFERA)
 - WHITE OAK (QUERCUS ALBA)
 - NORTHERN RED OAK (QUERCUS RUBRA)

NOTE:
1. THIS IS NOT A SURVEY. ALL SURVEY INFORMATION SHOWN ON THIS PLAN HAS BEEN TAKEN FROM SURVEY MAP PREPARED BY JOSEPH LINK, DATED 3/17/18. THE ENGINEER ASSUMES NO RESPONSIBILITY FOR ITS ACCURACY.

NOTE: UNAUTHORIZED ALTERATIONS OR ADDITIONS TO THIS DRAWING IS A VIOLATION OF SECTION 7209 (2) OF THE NEW YORK STATE EDUCATION LAW.

Site Design Consultants
Civil Engineers • Land Planners
251-F Underhill Avenue, Yorktown Heights, NY 10598
(914) 962-4488 - Fax: (914) 962-7386
www.sitedesignconsultants.com

JOSEPH C. KIMER, EIT
NYS Lic. No. 64431

Revisions:	No.	Date	Comments
	1	5/2/18	Plan Revisions
	2	5/25/18	Town Comments

SCALE: 1" = 10'




DRAWN BY: TK

DATE: 3/21/18

SITE PARKING PLAN


SITE PLAN PREPARED FOR
ARMSTRONG PLUMBING LLC
593 NORTH STATE ROAD
Town of Ossining
Westchester County, NY

Sheet 1 of 9



Site Design Consultants

Civil Engineers • Land Planners
251-F Underhill Avenue, Yorktown Heights, NY 10598
(914) 962-4488 - Fax: (914) 962-7386
www.sitedesignconsultants.com

[illegible]

SCALE: 1" = 10'	DRAWN BY: TK	DATE: 3/21/18
--------------------	-----------------	------------------

EXISTING CONDITIONS

SITE PLAN
PREPARED FOR
**ARMSTRONG PLUMBING
LLC**
593 NORTH STATE ROAD
Town of Ossining Westchester County, NY


Sheet
2
of
9




NOTE:
1. THIS IS NOT A SURVEY. ALL SURVEY INFORMATION SHOWN ON THIS PLAN HAS BEEN TAKEN FROM SURVEY MAP PREPARED BY JOSEPH LINK, DATED 3/17/18. THE ENGINEER ASSUMES NO RESPONSIBILITY FOR ITS ACCURACY.

NOTE: UNAUTHORIZED ALTERATIONS OR ADDITIONS TO THIS DRAWING IS A VIOLATION OF SECTION 7209 (2) OF THE NEW YORK STATE EDUCATION LAW.

Disturbed Slopes Table			
Minimum Slope	Maximum Slope	Acres	Color
15.00%	25.00%	0.04 ac.	
25.00%	35.00%	0.01 ac.	
35.00%	514306.10%	0.00 ac.	




SAFE DIG
Before You Dig, Drill or Blast!
Call 811
www.call811.com



PROJECT # 18-13

Site Design Consultants
Civil Engineers • Land Planners
251-F Underhill Avenue, Yorktown Heights, NY 10598
(914) 962-4488 - Fax: (914) 962-7386
www.sitedesignconsultants.com



Revisions:	No.	Date	Comments
	1	5/2/18	Plan Revisions
	2	5/25/18	Town Comments


SCALE: 1" = 10'	DRAWN BY: TK	DATE: 3/21/18
--------------------	-----------------	------------------

E&SC PLAN



SITE PLAN
PREPARED FOR
**ARMSTRONG PLUMBING
LLC**
593 NORTH STATE ROAD
Town of Ossining
Westchester County, NY

Sheet
3
of
9

COPYRIGHT © 2012 BY SITE DESIGN CONSULTANTS, ALL RIGHTS RESERVED



LOCATION MAP
NOT TO SCALE




SCALE: 1"=30'-0"

SAFE DIG
Before You Dig, Drill or Blast!
Call 811
Call 811 Toll Free: 811 or 1-800-486-7862
NY Industrial Code Rule 233 requires no less
than ten working days notice, but not more
than ten days notice.
www.digsaferenewyork.com


NOTE:
1. THIS IS NOT A SURVEY. ALL SURVEY INFORMATION SHOWN ON THIS PLAN HAS BEEN
TAKEN FROM SURVEY MAP PREPARED BY JOSEPH LINK, DATED 3/17/18. THE ENGINEER
ASSUMES NO RESPONSIBILITY FOR ITS ACCURACY.

NOTE: UNAUTHORIZED ALTERATIONS OR ADDITIONS TO THIS DRAWING IS A VIOLATION OF SECTION 7209 (2) OF THE NEW YORK STATE EDUCATION LAW.



PROJECT # 18-13

Site Design Consultants
Civil Engineers • Land Planners
251-F Underhill Avenue, Yorktown Heights, NY 10598
(914) 962-4488 - Fax: (914) 962-7386
www.sitedesignconsultants.com



JOSEPH C. KIMER, E. 1000
STATE OF NEW YORK
LICENSED PROFESSIONAL ENGINEER
NYS Lic. No. 64431






Revisions:	
No.	Date
1	5/21/18
2	5/25/18

Scale	Drawn By	Date
1" = 10'	TK	3/21/18

AREA MAP


SITE PLAN
PREPARED FOR
**ARMSTRONG PLUMBING
LLC**
593 NORTH STATE ROAD
Town of Ossining
Westchester County, NY

Sheet
4 of 9




NOTE:
1. THIS IS NOT A SURVEY. ALL SURVEY INFORMATION SHOWN ON THIS PLAN HAS BEEN TAKEN FROM SURVEY MAP PREPARED BY JOSEPH LINK, DATED 3/17/18. THE ENGINEER ASSUMES NO RESPONSIBILITY FOR ITS ACCURACY.

NOTE: UNAUTHORIZED ALTERATIONS OR ADDITIONS TO THIS DRAWING IS A VIOLATION OF SECTION 7209 (2) OF THE NEW YORK STATE EDUCATION LAW.



PROJECT # 18-13

Site Design Consultants
Civil Engineers • Land Planners
251-F Underhill Avenue, Yorktown Heights, NY 10598
(914) 962-4488 - Fax: (914) 962-7386
www.sitedesignconsultants.com



JOSEPH C. KIMER, EIT
LICENSED PROFESSIONAL ENGINEER
NYS Lic. No. 64431

Revisions:	
No.	Date
1	5/2/18
2	5/25/18

SCALE: 1" = 50'

DRAWN BY: TK

DATE: 3/21/18

SIGHT DISTANCE PLAN

SITE PLAN PREPARED FOR
ARMSTRONG PLUMBING LLC
593 NORTH STATE ROAD
Town of Ossining
Westchester County, NY

Sheet 5 of 9

CONSTRUCTION SEQUENCE

Recommended Sequence of Construction

Use of erosion and sediment control structures and practices are important for maintaining site stability under runoff and during construction activities. The Construction Sequence should be staged with erosion and sediment controls, as follows, with all controls in place and implemented prior to respective infrastructure construction. As construction proceeds, the controls should be monitored, maintained and replaced as needed. Additional controls may be required as needed to address unforeseen situations.

Refer to The Construction Drawings for all plans and details which relate to the Construction Sequence. This Sequence should be followed in conjunction with all Plans, Notes, and the Stormwater Pollution Prevention Plan. Prior to the commencement of work, the Owner and General Contractor shall read and understand the Sequence for Construction. The Sequence shall be discussed at the time of the Pre-construction Meeting.

During construction of the project, the Contractor is responsible to coordinate all required inspections with various agencies and the Project Engineer.

Construction Sequence

General Sequence: The general sequence applies to the start of all Phases of the project. The requirements in such shall be applied as appropriate in that phase and shall be assumed in place prior to the start of the work outlined in the sequence for each Phase.

- Prior to the beginning of any site work the major features of the construction must be field staked by a licensed surveyor. These include the building, limits of disturbance, utility lines, and Stormwater practices.
- Prior to the start of the project, an on-site pre-construction meeting will be held. This will be attended by the Project Owner, the Operator responsible for complying with the approved construction drawings including the Erosion and Sediment Control (E&SC) Plan and Details, the Design Engineer, the Engineer responsible for E&SC monitoring during construction, Town representatives from the Engineering Department and Code Enforcement.
- Cut and clear trees within the phase limits as necessary for the areas to be disturbed. Install tree protective measure at marked locations on E&SC Plan.
- Install all temporary erosion control measures as shown on the Erosion and Sediment Control Plan for the project's immediate disturbance areas. This shall include, but not limited to silt fence, stabilized construction entrances, diversion swales, sediment traps, construction fence, etc. This sequence must be followed to insure proper implementation of the Erosion and Sediment Control Plan (E&SC) and Stormwater Pollution Prevention Plan (SWPPP).
- Timbered trees and woodchips shall be temporarily stored in the stockpile and/or staging area if necessary before being removed off-site. Woodchips may be used for mulch to stabilize disturbed areas. Woodchip mulch shall be applied at a minimum rate of 500 lbs. per 1000 SF (2" thick minimum).
- Remove existing vegetative cover, cut and clear trees, grub, remove stumps and other surface features in the limit of construction only. Any disturbance that results from tree clearing and grubbing shall be immediately stabilized with woodchips mulch, hydro-mulch, or straw and seed. Timbered trees, wood chips, and stumps shall be removed off-site unless otherwise directed. As staked woodchips may be stockpiled for use as stabilizing ground cover. Demolish and/or remove existing features, i.e.: fence, concrete slab, asphalt etc., and dispose of or stockpile as required by the Owner. All construction debris shall be properly disposed of in accordance with all Federal, State, and Local requirements.
- Once the tree removal operation is complete strip the topsoil within the limits of disturbance and place excavated topsoil within the identified stockpile locations. Any soils so deemed by the Design or Monitoring Engineer shall be stockpiled for future use as landscaped areas topsoil. Contractor shall take every precaution feasible to reduce the amount of disturbed/exposed soils during construction.
- Begin rough grading of driveways and adjacent areas. Slopes in excess of 3H:1V shall not be left exposed and must be stabilized.
- Cut material shall first be moved to the fill locations required to complete the access drive and parking and bring the area up to final grades. Excess material to be used toward grading in Phase II shall be stockpiled. Blasted rock that is not suitable to remain on site shall be hauled away and properly disposed of.
- Begin installation of subsurface detention chambers within limits of disturbance.
- When the subsurface units are installed, the upstream drainage structure shall be blocked so as to not allow sediment laden water from reaching the subsurface chambers.
- Backfill as installation is complete and stabilize the area. If trenches are to be left open, place excavated material on the up-slope sides of the trench and protect and stabilize if it is to remain open for an extended period of seven (7) days or more.
- Upon completion of the subsurface chambers, begin installation of proposed Downstream Defender unit. Install storm sewer piping, catch basins and manholes, working downstream to upstream. During the installation of catch basins, install inlet protection as per E&SC Plan to assure that sediment laden water will not enter the storm system. Once the final grade above the system is achieved, put into place the final topsoil cover, seed mix, and erosion control blanket, or hydro-mulch.
- Once the infiltrator system has been installed, grade and install the base course for the driveways and parking areas.

Final Site Stabilization and Completion of New Construction:

- Upon completion of all Phases, the site shall be inspected by the Supervising Engineer and Town Inspector to determine completion of all work and permanent stabilization of the site.
- Any areas deemed incomplete or not properly stabilized shall be done so to the satisfaction to the Supervising Engineer and Town Inspector.
- Once the site is deemed adequately stable the temporary erosion and sediment control measures can be removed including the sediment traps. The area where the sediment trap was located shall be filled, top soiled, seeded and mulched in accordance with the specifications within this plan. At that time if deemed appropriate drainage structures upstream from the subsurface stormwater management systems shall be cleaned of sediment and debris. They can then be unblocked to allow for flow of collected surface runoff.

Contact information during and after construction:

593 North State Road LLC.
593 North State Road
Ossining, NY 10510

GENERAL EROSION CONTROL NOTES:

- Contractor shall be responsible for compliance with all sediment and erosion control practices. The sediment and erosion control practices are to be installed prior to any major soil disturbances and maintained until permanent protection is established. Road surface flows from the site should be dissipated with tracking pad or appropriate measures during adjacent road shoulder regrading. The contractor in responsible for the installation and maintenance of all soil erosion and sedimentation control devices throughout the course of construction.
- Catch basin inlet protection must be installed and operating at all times until tributary areas have been stabilized. When possible, flows should be stabilized before reaching inlet protection structure. Timely maintenance of sediment control structures is the responsibility of the contractor.
- All structures shall be maintained in good working order at all times. The sediment level in all sediment traps shall be closely monitored and sediment removed promptly when maximum levels are reached or as ordered by the engineer. All sediment control structures shall be inspected on a regular basis, and after each heavy rain to insure proper operation as designed. An inspection schedule shall be set forth prior to the start of construction.
- The locations and the installation times of the sediment capturing standards shall be as specified in these plans, as ordered by the engineer, and in accordance with the latest edition of the "New York standards and specifications for erosion and sediment control" (NYSSESC).
- All topsoil shall be placed in a stabilized stockpile for reuse on the site. All stockpile material required for final grading and stored on site shall be temporarily seeded and mulched within 7 days. Refer to soil stockpile details.
- Any disturbed areas that will be left exposed more than 7 days and not subject to construction traffic, shall immediately receive temporary seeding. Mulch shall be used if the season prevents the establishment of a temporary cover. Disturbed areas shall not be limed and fertilized prior to temporary seeding.
- All disturbed areas within 500 feet of an inhabited dwelling shall be wetted as necessary to provide dust control.
- The contractor shall keep the roadways within the project clear of soil and debris and is responsible for any street cleaning necessary during the course of the project.
- Sediment and erosion control structures shall be removed, and the area stabilized when the drainage area has been properly stabilized by permanent measures.
- All sediment and erosion control measures shall be installed in accordance with current edition of nyssec.
- All regraded areas must be stabilized appropriately prior to any rock blasting, cutting, and/or filling of soils. Special care should be taken during construction to insure stability during maintenance and integrity of control structures.
- Any slopes graded at 3:1 or greater shall be stabilized with erosion blankets to be staked into place in accordance with the manufacturers requirements. Erosion blankets may also be required at the discretion of town officials or project engineer. When stabilized blanket is utilized for channel stabilization, place all of the volume of seed mix prior to laying net, or as recommended by the manufacturer.
- To prevent heavy construction equipment and trucks from tracking soil off-site, construct a pervious crushed stone pad. Locate and construct pads as detailed in these plans.
- Contractor is responsible for controlling dust by sprinkling exposed soil areas periodically with water as required. Contractor to supply all equipment and water.
- Contractor shall be responsible for construction inspections as per NYSDEC GP-0-15-002 and Town of Ossining code.

OWNER / OPERATOR CERTIFICATION

"I certify under penalty of law that this document and all attachments were prepared under my direction or supervision in accordance with a system designed to assure that qualified personnel properly gathered and evaluated the information submitted. Based on my inquiry of the person or persons who manage the system, or those persons directly responsible for gathering the information, the information submitted is, to the best of my knowledge and belief, true, accurate, and complete. Further, I hereby certify that the SWPPP meets all Federal, State, and local erosion and sediment control requirements. I am aware that false statements made herein are punishable as a Class A misdemeanor pursuant to Section 210.45 of the Penal Law."

Name (please print): _____

Title: _____

Date: _____

Address: _____

Phone: _____

E-mail: _____

Signature: _____

MAINTENANCE OF TEMPORARY EROSION AND SEDIMENT CONTROL STRUCTURES:

NYS DEC GP-0-15-002 exposure restrictions - states that any exposed earthwork shall be stabilized in accordance with the guidelines of this plan.

- Trees and vegetation shall be protected at all times as shown on the detail drawing and as directed by the engineer.
- Care should be taken so as not to channel concentrated runoff through the areas of construction activity on the site.
- Fill and site disturbances should not be created which causes water to pond off site or on adjacent properties.
- Runoff from land disturbances shall not be discharged or have the potential to discharge off site without first being intercepted by a control structure, such as a sediment trap or silt fence. Sediment shall be removed before exceeding 50% of the retention structure's capacity.
- For finished grading, adequate grade shall be provided so that water will not pond on lawns for more than 24 hours after rainfall, except in swale flow areas which may drain for as long as 48 hours after rainfall.
- All swales and other areas of concentrated flow shall be properly stabilized with temporary control measures to prevent erosion and sediment travel. Surface flows over cut and fill areas shall be stabilized at all times.
- All sites shall be stabilized with erosion control materials within 7 days of final grading.
- Temporary sediment trapping devices shall be removed from the site within 30 days of final stabilization.

MAINTENANCE SCHEDULE:

	DAILY	WEEKLY	MONTHLY	AFTER RAINFALL	NECESSARY TO MAINTAIN FUNCTION	AFTER APPROVAL OF INSPECTOR
SILT FENCE	---	----	INSP.	INSP.	CLEAN/ REPLACE	REMOVE
WHEEL CLEANER	CLEAN	----	----	----	REPLACE	REMOVE
INLET PROTECTION	---	INSP.	INSP.	CLEAN	REPLACE	REMOVE

MAINTENANCE OF PERMANENT CONTROL STRUCTURES DURING CONSTRUCTION:

The stormwater management system and outlet structure shall be inspected on a regular basis and after every rainfall event. Sediment build up shall be removed from the inlet protection regularly to insure detention capacity and proper drainage. Outlet structure shall be free of obstructions. All piping and drain inlets shall be free of obstruction. Any sediment build up shall be removed.

MAINTENANCE OF CONTROLS AFTER CONSTRUCTION:

Controls (including respective outlet structures) should be inspected periodically for the first few months after construction and on an annual basis thereafter. They should also be inspected after major storm events.

DEBRIS AND LITTER REMOVAL:

Twice a year, inspect outlet structure and drain inlets for accumulated debris. Also, remove any accumulations during each mowing operation.

STRUCTURAL REPAIR/REPLACEMENT:

Outlet structure must be inspected twice a year for evidence of structural damage and repaired immediately.

EROSION CONTROL:

Unstable areas tributary to the basin shall immediately be stabilized with vegetation or other appropriate erosion control measures.

SEDIMENT REMOVAL:

Sediment should be removed after it has reached a maximum depth of five inches above the stormwater management system floor.

TOPSOIL:

Existing topsoil will be removed and stored in piles sufficiently as to avoid mixing with other excavation. Stockpiles shall be surrounded by erosion control as outlined on these plans. The furnishing of new topsoil shall be of a better or equal to the following criteria (SS713.01 NYSDOT):

- The pH of the material shall be 5.5 to 7.6.
- The organic content shall not be less than 2% or more than 70%.
- Gradation:

SIEVE SIZE	% PASSING BY WGT.
2 INCH	100
1 INCH	85 TO 100
1/4 INCH	65 TO 100
NO. 200 MESH	20 TO 80

PERMANENT VEGETATIVE COVER:

- Site preparation:
 - Install erosion control measures.
 - Scarify compacted soil areas.
 - Lime as required to pH 6.5.
 - Fertilize with 10-6-4 4 lbs/1,000 S.F.
 - Incorporate amendments into soil with disc harrow.
- Seed mixtures for use on swales and cut and fill areas.

MIXTURE	LBS/ACRE
ALT. A	KENTUCKY BLUE GRASS 20 CREeping RED FESCUE 28 RYE GRASS OR REDTOP 5
ALT. B	CREeping RED FESCUE 20 REDTOP 2 TALL FESCUE/SMOOTH BLOOMGRASS 20
- SEEDING:
 - Prepare seed bed by raking to remove stones, twigs, roots and other foreign material.
 - Apply soil amendments and integrate into soil.
 - Apply seed uniformly by cyclone seeder culti-packer or hydro-seeder at rate indicated.
 - Stabilize seeded areas in drainage swales.
 - Irrigate to fully saturate soil layer, but not to dislodge planting soil.
 - Seed between April 1st and May 15th or August 15th and October 15th.
 - Seeding may occur May 15th and August 15th if adequate irrigation is provided.
 - Seeding

TEMPORARY VEGETATIVE COVER:

SITE PREPARATION:

- Install erosion control measures.
- Scarify areas of compacted soil.
- Fertilize with 10-10-10 at 400/acre.
- Lime as required to pH 6.5.

SEED SPECIES:

MIXTURE	LBS/ACRE
Rapidly germinating annual ryegrass (or approved equal)	20
Perennial ryegrass	20
Cereal oats	36

SEEDING:

Same as permanent vegetative cover


CONTRACTOR CERTIFICATION STATEMENT

Certification Statement - All contractors and subcontractors as identified in a SWPPP, by the Owner or Operator, in accordance with Part III.A.5 of the SPDES General Permit for Stormwater Runoff from Construction Activity, GP-0-15-002, dated January 12, 2015, Page 10 of 40, shall sign a copy of the following Certification Statement before undertaking any construction activity at the Site identified in the SWPPP:


"I hereby certify that I understand and agree to comply with the terms and conditions of the SWPPP and agree to implement any corrective actions identified by the Qualified Inspector during a site inspection. I also understand that the Owner or Operator must comply with the terms and conditions of the New York State Pollutant Discharge Elimination System ("SPDES") General Permit for Stormwater Discharge from Construction Activities and that it is unlawful for any person to cause or contribute to a violation of water quality standards. Furthermore, I understand that certifying false, incorrect or inaccurate information is a violation of the referenced permit and the laws of the State of New York and could subject me to criminal, civil and/or administrative proceedings."

Individual Contractor: _____
Name and Title (please print): _____
Signature of Contractor: _____
Company / Contracting Firm: _____
Name of Company: _____
Address of Company: _____
Telephone Number / Cell Number: _____
Site Information: _____
Address of Site: _____


Today's Date: _____




E-1 SILT FENCE DETAIL NOT TO SCALE




E-3 TREE PROTECTION PLAN FOR GRADE CHANGE DETAIL NOT TO SCALE




E-5 INLET PROTECTION DETAIL NOT TO SCALE



E-2 STABILIZED CONSTRUCTION ENTRANCE DETAIL NOT TO SCALE



E-4 SOIL STOCKPILE DETAIL NOT TO SCALE



E-6 TREE TRUNK ARMOR / TREE PROTECTION DETAIL NOT TO SCALE

PROJECT # 18-13

Site Design Consultants

Civil Engineers • Land Planners

251-F Underhill Avenue, Yorktown Heights, NY 10598

(914) 962-4488 - Fax: (914) 962-7386

www.sitedesignconsultants.com

Engineer:

Joseph C. Rina, P.E.
NYS Lic. No. 64431

Revisions:

No.	Date	Comments
1	5/21/18	Plan Revisions
2	5/25/18	Town Comments

SCALE:

NTS

DRAWN BY:

TK

DATE:

3/21/18

E&SC DETAILS

SITE PLAN PREPARED FOR

ARMSTRONG PLUMBING

LLC

593 NORTH STATE ROAD

Ossining


Westchester County, NY

Sheet

6

of

9



TYPICAL INSTALLATION GUIDELINES			
SIGN	M.U.T.C.D. NUMBER	SIZE OF SIGN	TYPE OF MOUNT
	R1-1	18" X 18"	GR. MT.
	R7-8	12" X 18"	GR. MT.


SIGN	M.U.T.C.D. NUMBER	SIZE OF SIGN	TYPE OF MOUNT
	P1-2 (SEE NOTE 4)	12" X 18"	GR. MT.
	R7-6 (SEE NOTE 4)	12" X 18"	GR. MT.

- GENERAL NOTES:**
- All signage shall be in accordance with the latest edition of the national MUTCD and the N.Y.S Supplement (MUTCD), September 2007, including the following:
A. Letter size and series
B. Legend and background color
C. Reflectivity
D. Size of sign
 - The type of characters as specified in the standard specifications shall be as follows:
MUTCD CODE LETTER TYPE OF CHARACTER
G.I. TYPE IV
R.P.W.M. TYPE IV OR V
 - Sign locations as shown on plans are approximate. The Contractor shall relocate existing signs and install new signs in accordance with the MUTCD, latest edition. The Contractor shall contact the Town Engineer to discuss/resolve problem areas.
 - Except where otherwise specified, parking signs shall be placed facing approaching traffic at an angle of between 30 and 45 degrees with the line of traffic flow. Parking signs shall be placed at each end of a regulation (single-headed arrows) and, within the regulation (double-headed arrows), at intervals not to exceed 200 ft.
 - Where new signs are installed the Contractor shall affix a label to the back of the sign panel. This label will show the date of installation and identification numbers.
 - Placement of W3-17 sign is prescribed in the General Municipal Law.

R-1

TRAFFIC SIGN DETAIL


NOT TO SCALE



R-2

TYPICAL DRIVEWAY AND PARKING LOT SECTION


NOT TO SCALE



R-3

CONCRETE CURB DETAIL


NOT TO SCALE



S-1

TRASH ENCLOSURE DETAIL


NOT TO SCALE



R-4

TYPICAL PARKING STALL LAYOUT

NOT TO SCALE



ST-1

RETAINING WALL DETAIL

NOT TO SCALE

TABLE I

WALL HEIGHT "H"	WALL DIMENSIONS										REINFORCING			
	A	B	C	D	E	F	G	I	J		STEM		FOOTING	
											VERTICAL EACH FACE	HORIZONTAL EACH FACE	MAIN TOP & BOTTOM	LONGITUDINAL TOP & BOTTOM
1'-0"	3'-6"	1'-3"	0"	0"	2'-3"	0"	1'-0"	1'-0"	1'-0"		#6 @ 16" O.C.	#5 @ 18" O.C.	#6 @ 18" O.C.	4 - #5
2'-0"	3'-6"	1'-3"	0"	0"	2'-3"	0"	1'-0"	1'-0"	1'-0"		#6 @ 16" O.C.	#5 @ 18" O.C.	#6 @ 18" O.C.	4 - #5
3'-0"	4'-0"	1'-6"	0"	0"	2'-6"	0"	1'-0"	1'-0"	1'-0"		#6 @ 16" O.C.	#5 @ 18" O.C.	#6 @ 16" O.C.	4 - #5
4'-0"	4'-6"	1'-9"	0"	1'-0"	1'-8"	6"	1'-3"	1'-0"	1'-0"		#6 @ 16" O.C.	#5 @ 18" O.C.	#6 @ 16" O.C.	5 - #5
5'-0"	5'-0"	1'-6"	10"	1'-0"	1'-8"	6"	1'-3"	1'-0"	1'-3"		#6 @ 15" O.C.	#5 @ 15" O.C.	#6 @ 16" O.C.	6 - #5
6'-0"	6'-0"	2'-0"	8"	1'-4"	2'-0"	8"	1'-3"	1'-0"	1'-4"		#6 @ 15" O.C.	#5 @ 15" O.C.	#6 @ 16" O.C.	7 - #5

- GENERAL NOTES:**
- ALL WORK SHALL BE PERFORMED IN ACCORDANCE WITH THE TOWN CODE OF PRACTICE AND THE NEW YORK STATE BUILDING CONSTRUCTION CODE.
 - ALL CHANGES MADE TO THESE PLANS SHALL BE APPROVED BY THE ENGINEER AND ANY SUCH CHANGES SHALL BE FILED AS AMENDMENTS TO THE ORIGINAL BUILDING PERMIT.
 - ALL WRITTEN DIMENSIONS ON THE DRAWINGS SHALL TAKE PRECEDENCE OVER ANY SCALED DIMENSIONS.
 - THE CONTRACTOR SHALL SUPERVISE AND DIRECT THE WORK USING HIS BEST SKILL AND ATTENTION. HE SHALL BE SOLELY RESPONSIBLE FOR ALL CONSTRUCTION MEANS, METHODS, TECHNIQUES, SEQUENCES AND PROCEDURES.
 - THE CONTRACTOR SHALL BE RESPONSIBLE TO THE OWNER FOR THE ACTS AND OMISSIONS OF HIS EMPLOYEES, SUBCONTRACTORS, AND THEIR AGENTS AND EMPLOYEES, AND ANY OTHER PERSONS PERFORMING ANY WORK.
 - THE CONTRACTOR SHALL BE RESPONSIBLE TO PROTECT HIS WORK AND WILL BE HELD RESPONSIBLE FOR CONSEQUENTIAL DAMAGE DUE TO HIS ACTIVITIES. THE OWNER AND THE ENGINEER SHALL BE HELD HARMLESS.
 - THE CONTRACTOR SHALL SECURE & PAY FOR A BUILDERS RISK POLICY TO COVER THE PERIOD OF CONSTRUCTION. THE ENGINEER & OWNER SHALL BE NAMED AS ADDITIONAL INSURED. ALL CONTRACTORS EMPLOYED AT THE SITE SHALL BE COVERED BY WORKMAN'S COMPENSATION.
 - ENGINEER'S WHOSE SEAL APPEARS HEREON HAS NOT BEEN RETAINED FOR SUPERVISION OF CONSTRUCTION. SUBSEQUENTLY, HE IS NOT RESPONSIBLE FOR CONSTRUCTION AND THEREFORE ASSUMES NO RESPONSIBILITY FOR CONSTRUCTION PRACTICES, PROCEDURES, AND RESULTS THEREFROM.

- CONSTRUCTION NOTES:**
- ALL CONCRETE WORK SHALL BE PERFORMED IN ACCORDANCE WITH THE AMERICAN CONCRETE INSTITUTE, ACI 318, LATEST EDITION.
 - EXCAVATION IN GENERAL SHALL CONFORM TO THE LINES AND GRADES SHOWN ON THE CONTRACT DRAWINGS.
 - FILL MATERIAL SHALL BE PLACED IN LOOSE 8 INCH LIFTS. PRIOR TO COMPACTION, EACH LIFT SHALL BE MOISTENED OR AERATED AS NECESSARY TO PROVIDE OPTIMUM MOISTURE CONTENT. EACH LIFT SHALL BE COMPACTED TO A MINIMUM OF 95% OF THE MAXIMUM DRY DENSITY AS DETERMINED BY A.S.T.M. D1557 METHOD C. THE CONTRACTOR WILL BE REQUIRED TO HIRE AN INDEPENDENT CERTIFIED TESTING LAB TO PERFORM FIELD DENSITY TESTS. FIELD TESTING SHALL BE PERFORMED IN ACCORDANCE WITH A.S.T.M. D1556 OR D2922. A MINIMUM OF 6 IN-PLACE FIELD DENSITY TESTS SHALL BE PERFORMED ON ALTERNATE LIFTS. FILLING OPERATIONS MAY NOT PROCEED UNTIL IN-PLACE DENSITY TESTS HAVE BEEN PERFORMED AND THE FILL PROPERLY COMPACTED.
 - FILL SHALL CONSIST OF SOUND DURABLE PARTICLES TO THE GRADATION SHOWN IN THE TABLE BELOW. THE MATERIAL SHALL BE GRANULAR AND FREE OF ORGANIC OR OTHER DELETERIOUS MATERIAL. IN GENERAL THE SOIL SHALL BE NON-PLASTIC WITH A PLASTICITY INDEX LESS THAN 5 AND SHALL CONFORM TO THE UNIFIED SOIL CLASSIFICATION SYSTEM FOR AN "SW" SOIL OR THE REQUIREMENTS OF THE NEW YORK STATE DEPARTMENT OF TRANSPORTATION STANDARD SPECIFICATION SECTION 203-2 ITEM NO. 203.07 SELECT GRANULAR FILL, HOWEVER THE MAXIMUM SIZE SHALL BE 3 INCHES.

SIEVE SIZE	PERCENT PASSING BY WEIGHT
3"	100
No. 40	0 - 70
No. 200	0 - 15

- IF ON-SITE EXCAVATED MATERIAL IS USED IT MUST CONFORM TO THE SAME MINIMUM REQUIREMENTS SPECIFIED. IN ALL INSTANCES, THE THE CONTRACTOR MUST SUBMIT CERTIFIED LABORATORY TEST REPORTS ON ALL MATERIALS USED FOR BACKFILL. THE FOLLOWING REPORTS SHALL BE PROVIDED AND BE IN ACCORDANCE WITH THE FOLLOWING ASTM SPECIFICATIONS:
- PARTICLE SIZE ANALYSIS - A.S.T.M. D422
 - SOIL CLASSIFICATION - A.S.T.M. D2487
 - LIQUID & PLASTIC LIMITS - A.S.T.M. D424
 - MODIFIED PROCTOR MAXIMUM DENSITY - A.S.T.M. D1557 METHOD C
- EXCAVATION SHALL BE PERFORMED IN ACCORDANCE WITH THE "CONSTRUCTION SAFETY & HEALTH ACT O.S.H.A. PART 192
 - GEOTEXTILE FABRIC SHALL BE TREVIRA SPUNBOUND NON-WOVEN #1125 OR APPROVED EQUAL. THE GEOTEXTILE SHALL BE INSTALLED PER THE MANUFACTURER'S RECOMMENDATIONS AND GUIDELINES.
 - THE CONTRACTOR SHALL NOT USE LARGE OR HEAVY CONSTRUCTION EQUIPMENT WITHIN 5 FEET OF THE RETAINING WALL. SUITABLE HAND/SMALL COMPACTION EQUIPMENT SHALL BE USED WITHIN 5 FEET OF THE WALL.
 - FOOTINGS CONSTRUCTED ON VIRGIN IN-SITU SOIL SHALL HAVE A MINIMUM ALLOWABLE BEARING CAPACITY OF 3000 PSF.
 - TO INSURE A PROPER BEARING SURFACE FOR THE FOOTINGS CONSTRUCTED ON NATURAL IN-SITU SOIL, THE CONTRACTOR SHALL STRIP ALL TOP SOIL. PRIOR TO CONSTRUCTION OF THE FOOTINGS, THE AREA SHALL BE COMPACTED USING SUITABLE COMPACTION EQUIPMENT. A MINIMUM A 3 PASSES SHALL BE MADE.
 - DURING BACKFILL OPERATIONS, THE CONTRACTOR SHALL BE CAREFUL NOT TO CREATE UNBALANCED LOADING CONDITIONS ON THE WALL. BACKFILL SHOULD BE PLACED AND COMPACTED ON BOTH SIDES OF THE WALL SIMULTANEOUSLY.
 - ALL FOOTINGS SHALL BE LOCATED A MINIMUM OF 3'-6" BELOW ANY ADJACENT FINISHED GRADE.
 - ALL CONCRETE SUPPLIED TO THE PROJECT SHALL HAVE A MINIMUM COMPRESSIVE STRENGTH "f_c = 4000 PSI" AND SHALL CONTAIN A MINIMUM 5% AIR ENTRAINING ADMIXTURE IN ACCORDANCE WITH A.S.T.M. C 260.
 - STEEL REINFORCEMENT SHALL BE OF THE SIZES SPECIFIED AND SHALL HAVE A MIN. YIELD STRENGTH f_y = 60, 000 PSI
 - THE CONTRACTOR SHALL PROVIDE EXPANSION JOINTS @ 90'-0" O.C. (MAX.) IN THE WALL.
 - FOOTINGS SHALL NOT BE CONSTRUCTED ON WET OR FROZEN GROUND. UNSUITABLE MATERIAL SHALL BE EXCAVATED AND REPLACED WITH COMPACTED GRANULAR FILL OR 3/4" CRUSHED STONE.

Site Design Consultants
Civil Engineers • Land Planners
251-F Underhill Avenue, Yorktown Heights, NY 10598
(914) 962-4488 - Fax: (914) 962-7386
www.sitedesignconsultants.com


Revisions:	No.	Date	Comments
	1	5/21/18	Plan Revisions
	2	5/25/18	Town Comments

SCALE: N.T.S.	DRAWN BY: TK	DATE: 3/21/18
---------------	--------------	---------------

SITE DETAILS

SITE PLAN PREPARED FOR
ARMSTRONG PLUMBING LLC
593 NORTH STATE ROAD
Westchester County, NY


Sheet 7 of 9



SWM-1 **STORMTECH SC-740 CHAMBER SYSTEM PLAN VIEW DETAIL**
NOT TO SCALE

NOTES:

- All design specifications for Stormtech SC-740 chambers shall be in accordance with the Stormtech design manual.
- The installation of Stormtech SC-740 chambers shall be in accordance with the latest Stormtech installation instructions.
- The contractor is advised to review and understand the installation instructions prior to beginning system installation. Call 1-888-892-2694 or visit www.stormtech.com to receive a copy of the latest Stormtech installation instructions.
- Chambers shall meet the design requirements and load factors specified in Section 12.12 of the latest edition of the AASHTO LRFD bridge design specifications



SWM-2 **STORMTECH SC-740 CHAMBER DETAIL**
NOT TO SCALE

PART #	STUB	A	B	C
SC740EP08T / SC740EP08TPC	6" (150 mm)	10.9" (277 mm)	18.5" (470 mm)	0.5" (13 mm)
SC740EP08B / SC740EP08BPC	8" (200 mm)	12.2" (310 mm)	16.5" (419 mm)	0.6" (15 mm)
SC740EP08T / SC740EP08TPC	8" (200 mm)	12.2" (310 mm)	16.5" (419 mm)	0.6" (15 mm)
SC740EP08B / SC740EP08BPC	8" (200 mm)	12.2" (310 mm)	16.5" (419 mm)	0.6" (15 mm)

SC-740 TECHNICAL SPECIFICATION

NTS

90.7" (2304 mm) ACTUAL LENGTH

85.4" (2169 mm) INSTALLED LENGTH

START END

OVERLAP NEXT CHAMBER HERE (OVER SMALL CORRUGATION)

ACCEPTS 4" (100 mm) SCH 40 PVC PIPE FOR INSPECTION PORT. FOR PIPE SIZES LARGER THAN 4" (100 mm) UP TO 10" (250 mm) USE INSERTA TEE CONNECTION CENTERED ON A CHAMBER CREST CORRUGATION

NOMINAL CHAMBER SPECIFICATIONS

SIZE (W X H X INSTALLED LENGTH)

CHAMBER STORAGE

MINIMUM INSTALLED STORAGE* WEIGHT

*ASSUMES 6" (152 mm) STONE ABOVE, BELOW, AND BETWEEN CHAMBERS


STUBS AT BOTTOM OF END CAP FOR PART NUMBERS ENDING WITH "B"

STUBS AT TOP OF END CAP FOR PART NUMBERS ENDING WITH "T"

ALL STUBS, EXCEPT FOR THE SC740EP24B ARE PLACED AT BOTTOM OF END CAP SUCH THAT THE OUTSIDE DIAMETER OF THE STUB IS FLUSH WITH THE BOTTOM OF THE END CAP. FOR ADDITIONAL INFORMATION CONTACT STORMTECH AT 1-888-892-2694.

* FOR THE SC740EP24B THE 24" (600 mm) STUB LIES BELOW THE BOTTOM OF THE END CAP APPROXIMATELY 1.75" (44 mm). BACKFILL MATERIAL SHOULD BE REMOVED FROM BELOW THE N-12 STUB SO THAT THE FITTING SITS LEVEL.

NOTE: ALL DIMENSIONS ARE NOMINAL



SWM-3 **STORMTECH SC-740 CROSS SECTION DETAIL**
NOT TO SCALE

ACCEPTABLE FILL MATERIALS: STORMTECH SC-310 CHAMBER SYSTEMS

MATERIAL LOCATION	DESCRIPTION	AASHTO MATERIAL CLASSIFICATIONS	COMPACTION / DENSITY REQUIREMENT
D	FINAL FILL: FILL MATERIAL FOR LAYER 'D' STARTS FROM THE TOP OF THE 'C' LAYER TO THE BOTTOM OF FLEXIBLE PAVEMENT OR UNPAVED FINISHED GRADE ABOVE. NOTE THAT PAVEMENT SUBBASE MAY BE PART OF THE 'D' LAYER	N/A	PREPARE PER SITE DESIGN ENGINEER'S PLANS. PAVED INSTALLATIONS MAY HAVE STRINGENT MATERIAL AND PREPARATION REQUIREMENTS.
C	INITIAL FILL: FILL MATERIAL FOR LAYER 'C' STARTS FROM THE TOP OF THE EMBEDMENT STONE ('B' LAYER) TO 18" (450 mm) ABOVE THE TOP OF THE CHAMBER. NOTE THAT PAVEMENT SUBBASE MAY BE A PART OF THE 'C' LAYER.	AASHTO M1451 A-1, A-2.4, A-3 OR AASHTO M431 3, 357, 4, 467, 5, 56, 57, 6, 67, 68, 7, 78, 8, 89, 9, 10	BEGIN COMPACTIONS AFTER 12" (300 mm) OF MATERIAL OVER THE CHAMBERS IS REACHED. COMPACT ADDITIONAL LAYERS IN 6" (150 mm) MAX LIFTS TO A MIN. 95% PROCTOR DENSITY FOR WELL GRADED MATERIAL AND 95% RELATIVE DENSITY FOR PROCESSED AGGREGATE MATERIALS. ROLLER GROSS VEHICLE WEIGHT NOT TO EXCEED 12,000 lbs (53 kN). DYNAMIC FORCE NOT TO EXCEED 20,000 lbs (89 kN).
B	EMBEDMENT STONE: FILL SURROUNDING THE CHAMBERS FROM THE FOUNDATION STONE ('A' LAYER) TO THE 'C' LAYER ABOVE.	AASHTO M431 3, 357, 4, 467, 5, 56, 57	NO COMPACTION REQUIRED.
A	FOUNDATION STONE: FILL BELOW CHAMBERS FROM THE SUBGRADE UP TO THE FOOT (BOTTOM) OF THE CHAMBER.	AASHTO M431 3, 357, 4, 467, 5, 56, 57	PLATE COMPACT OR ROLL TO ACHIEVE A FLAT SURFACE. #3

NOTES:

- THE LISTED AASHTO DESIGNATIONS ARE FOR GRADATIONS ONLY. THE STONE MUST ALSO BE CLEAN, CRUSHED, ANGULAR. FOR EXAMPLE, A SPECIFICATION FOR #4 STONE WOULD STATE: "CLEAN, CRUSHED, ANGULAR NO. 4 (AASHTO M43) STONE".
- STORMTECH COMPACTION REQUIREMENTS ARE MET FOR 'A' LOCATION MATERIALS WHEN PLACED AND COMPACTED IN 6" (150 mm) (MAX) LIFTS USING TWO FULL COVERAGES WITH A VIBRATORY COMPACTOR.
- WHERE INFILTRATION SURFACES MAY BE COMPROMISED BY COMPACTION, FOR STANDARD DESIGN LOAD CONDITIONS, A FLAT SURFACE MAY BE ACHIEVED BY RAKING OR DRAGGING WITHOUT COMPACTION EQUIPMENT. FOR SPECIAL LOAD DESIGNS, CONTACT STORMTECH FOR COMPACTION REQUIREMENTS.

ADS GEOSYNTHETICS 601T NON-WOVEN GEOTEXTILE ALL AROUND CLEAN, CRUSHED, ANGULAR STONE IN A & B LAYERS

PAVEMENT LAYER (DESIGNED BY SITE DESIGN ENGINEER)

PERIMETER STONE (SEE NOTE 6)

EXCAVATION WALL (CAN BE SLOPED OR VERTICAL)

ADS GEOSYNTHETICS 315WTK WOVEN GEOTEXTILE BETWEEN FOUNDATION STONE AND SUBGRADE

SC-740 END CAP

SUBGRADE SOILS (SEE NOTE 5)

12" (300 mm) MIN

6" (150 mm) MIN

51" (1295 mm)

18" (450 mm) MIN


8" (200 mm) MAX

30" (760 mm)

DEPTH OF STONE TO BE DETERMINED BY DESIGN ENGINEER 6" (150 mm) MIN

12" (300 mm) TYP

SWM-4 **STORMTECH SC-740 CHAMBER DETENTION ISOLATOR ROW DETAIL**
NOT TO SCALE



D-1 **TYPICAL CATCH BASIN DETAIL**
NOT TO SCALE

SC-740 ISOLATOR ROW DETAIL

NTS

COVER ENTIRE ISOLATOR ROW WITH ADS GEOSYNTHETICS 601T NON-WOVEN GEOTEXTILE 6" (24 m) MIN WIDE

STORMTECH HIGHLY RECOMMENDS FLEXSTORM PURE INSERTS IN ANY UPSTREAM STRUCTURES WITH OPEN GRATES

INSPECTION PORT

SC-740 CHAMBER

SC-740 END CAP

CATCH BASIN OR MANHOLE


BYPASS WEIR TO DIRECT FLOWS TO TREATMENT CHAMBERS

SUMP DEPTH TBD BY SITE DESIGN ENGINEER (24" (600 mm) MIN RECOMMENDED)

24" (600 mm) HDPE ACCESS PIPE REQUIRED USE FACTORY PRE-FABRICATED END CAP PART #: SC740EP24B

TWO LAYERS OF ADS GEOSYNTHETICS 315WTK WOVEN GEOTEXTILE BETWEEN FOUNDATION STONE AND CHAMBERS 5" (1.5 m) MIN WIDE CONTINUOUS FABRIC WITHOUT SEAMS

SWM-5 **STORMTECH FLUSING/INSPECTION PORT DETAIL**
NOT TO SCALE



D-2 **RIP-RAP OVERFLOW CHANNEL DETAIL**
NOT TO SCALE

INSPECTION & MAINTENANCE

STEP 1) INSPECT ISOLATOR ROW FOR SEDIMENT

A. INSPECTION PORTS (IF PRESENT)

A.1. REMOVE/OPEN LID ON NYLOPLAST INLINE DRAIN

A.2. REMOVE AND CLEAN FLEXSTORM FILTER IF INSTALLED

A.3. USING A FLASHLIGHT AND STADIA ROD, MEASURE DEPTH OF SEDIMENT AND RECORD ON MAINTENANCE LOG

A.4. LOWER A CAMERA INTO ISOLATOR ROW FOR VISUAL INSPECTION OF SEDIMENT LEVELS (OPTIONAL)

A.5. IF SEDIMENT IS AT, OR ABOVE, 3" (80 mm) PROCEED TO STEP 2. IF NOT, PROCEED TO STEP 3.

B. ALL ISOLATOR ROWS

B.1. REMOVE COVER FROM STRUCTURE AT UPSTREAM END OF ISOLATOR ROW

B.2. USING A FLASHLIGHT, INSPECT DOWN THE ISOLATOR ROW THROUGH OUTLET PIPE(S). MIRRORS ON POLES OR CAMERAS MAY BE USED TO AVOID A CONFINED SPACE ENTRY(S). FOLLOW OSHA REGULATIONS FOR CONFINED SPACE ENTRY IF ENTERING MANHOLE.

B.3. IF SEDIMENT IS AT, OR ABOVE, 3" (80 mm) PROCEED TO STEP 2. IF NOT, PROCEED TO STEP 3.

STEP 2) CLEAN OUT ISOLATOR ROW USING THE JETVAC PROCESS

A. A FIXED CULVERT CLEANING NOZZLE WITH REAR FACING SPREAD OF 45° (1.1 m) OR MORE IS PREFERRED

B. APPLY MULTIPLE PASSES OF JETVAC UNTIL BACKFLUSH WATER IS CLEAN

C. VACUUM STRUCTURE SUMP AS REQUIRED


STEP 3) REPLACE ALL COVERS, GRATES, FILTERS, AND LIDS; RECORD OBSERVATIONS AND ACTIONS.

STEP 4) INSPECT AND CLEAN BASINS AND MANHOLES UPSTREAM OF THE STORMTECH SYSTEM.

NOTES

- INSPECT EVERY 6 MONTHS DURING THE FIRST YEAR OF OPERATION. ADJUST THE INSPECTION INTERVAL BASED ON PREVIOUS OBSERVATIONS OF SEDIMENT ACCUMULATION AND HIGH WATER ELEVATIONS. J
- CONDUCT JETTING AND VACTORING ANNUALLY OR WHEN INSPECTION SHOWS THAT MAINTENANCE IS NECESSARY.

D-3 **GRASS SWALE DETAIL**
NOT TO SCALE



D-4 **STORM PIPE BEDDING DETAIL**
NOT TO SCALE

STORMTECH SC-740 6" INSPECTION PORT DETAIL

NTS

CONCRETE COLLAR

PAVEMENT

18" (450 mm) MIN WIDTH

CONCRETE COLLAR NOT REQUIRED FOR UNPAVED APPLICATIONS

12" (300 mm) NYLOPLAST INLINE DRAIN BODY W/ SOLID HINGED COVER OR GRATE PART# 2712AGGN

6" (150 mm) ADS N-12 HDPE PIPE

SC-740 CHAMBER

6" (150 mm) INSERTA TEE PART# 06N12ST74IP

INSERTA TEE TO BE CENTERED ON CORRUGATION CREST


8" (200 mm) MIN THICKNESS

FLEXSTORM CATCH IT PART# 6212NYFX WITH USE OF OPEN GRATE

CONCRETE SLAB

6" (150 mm) MIN THICKNESS

D-4 **STORM PIPE BEDDING DETAIL**
NOT TO SCALE



D-4 **STORM PIPE BEDDING DETAIL**
NOT TO SCALE

STORMWATER MANAGEMENT DETAILS

FINISH GRADE

SEE DRIVEWAY DETAIL FOR NEW INSTALLATIONS. SEE PAVEMENT REPLACEMENT DETAIL FOR INSTALLATIONS UNDER EXISTING ROADWAYS.

PAVEMENT FINISHED GRADE

SEE DRIVEWAY DETAIL FOR NEW INSTALLATIONS. SEE PAVEMENT REPLACEMENT DETAIL FOR INSTALLATIONS UNDER EXISTING ROADWAYS.

1'-0"

2'-0" MIN COVER

1'-0"

4'-2" MIN

8" MIN - IF GROUND WATER TABLE S ENCOUNTERED

CLEAN FILL BEDDING MATERIAL SEE NOTES

DIA VARIES

APPROVED SUB GRADE

NOTES:

- Pipe shall be laid and connected in the bedding which shall consist of:
A. Compacted existing subsoil when laid above ground water or;
B. 3/4" crushed stone when laid below ground water.
- If subsoil is determined to be unsuitable by the Engineer, all unsuitable material shall be removed for at least 2'-6" below the pipe invert or twice the pipe diameter, whichever is greater, and replaced with compacted bedding material.

Site Design Consultants

Civil Engineers • Land Planners

251-F Underhill Avenue, Yorktown Heights, NY 10598

(914) 962-4488 • Fax: (914) 962-7386

www.sitedesignconsultants.com

PROJECT # 18-13

STATE OF NEW YORK

JOSEPH C. RINA, P.E.

Professional Engineer

NYS Lic. No. 64431

Revisions:	No.	Date	Comments
	1	5/2/18	Plan Revisions
	2	5/25/18	Town Comments

SCALE: NTS

DRAWN BY: TK

DATE: 3/21/18

STORMWATER MANAGEMENT DETAILS

SITE PLAN PREPARED FOR



ARMSTRONG PLUMBING LLC

593 NORTH STATE ROAD

Westchester County, NY

Sheet 8 of 9

FIG. 2018.18.13.2 ARMSTRONG PLUMBING NORTH STATE ENGINEERING CAD-CD-18-13 ARMSTRONG PLUMBING NORTH STATE RD-15-13 SITE PLAN 5-25-18 DWG



Operation

Introduction

The Downstream Defender® operates on simple fluid hydraulics. It is self-activating, has no moving parts, no external power requirement and is manufactured from durable non-corrosive components. No manual procedures are required to operate the unit and maintenance is limited to monitoring accumulations of stored pollutants and periodic clean-outs. The Downstream Defender® has been designed to allow for easy and safe access for inspection/monitoring and clean-out procedures. Entry into the unit or removal of the internal components is not necessary for maintenance, thus safety concerns related to confined-space-entry are avoided.

Pollutant Capture and Retention

The internal components of the Downstream Defender® have been designed to protect the oil/floatables and sediment storage volumes so that separator performance is not reduced as pollutants accumulate between clean-outs (Fig.2). The Downstream Defender® vessel remains wet between storm events. Oil and floatables are stored on the water surface in the outer annulus separate from the sediment storage volume in the sump of the unit providing the option for separate oil disposal, and accessories such as adsorbent pads. Since the oil/floatables and sediment storage volumes are isolated from the active separation region, the potential for re-suspension and washout of stored pollutants between clean-outs is minimized.

Wet Sump

The sump of the Downstream Defender® retains a standing water




Fig.2 Pollutant storage volumes of the Downstream Defender®.

Hydro International (Stormwater), 94 Hutchins Drive, Portland ME 04102
Tel: (207) 756-6200 Fax: (207) 756-6212 Web: www.hydro-int.com

level between storm events. The water in the sump prevents stored sediment from solidifying in the base of the unit. (The clean-out procedure becomes more difficult and labor intensive if the system allows fine sediment to dry-out and consolidate. Dried sediment must be manually removed by maintenance crews. This is a labor intensive operation in a hazardous environment.)

Blockage Protection

The Downstream Defender® has large clear openings and no internal restrictions or weirs, minimizing the risk of blockage and hydraulic losses. In addition to increasing the system headloss, orifices and internal weirs can increase the risk of blockage within the unit.

Maintenance

Overview

The Downstream Defender® protects the environment by removing a wide range of pollutants from stormwater runoff. Periodic removal of these captured pollutants is essential to the continuous, long-term functioning of the Downstream Defender®. The Downstream Defender® will capture and retain sediment and oil until the sediment and oil storage volumes are full to capacity. When sediment and oil storage capacities are reached, the Downstream Defender® will no longer be able to store removed sediment and oil. Maximum pollutant storage capacities are provided in Table 1.

Hydro International recommends that maintenance crews watch the Downstream Defender® maintenance training video at www.hydro-int.com/us/products/downstream-defender. Maintenance providers are also encouraged to participate in Hydro International's Maintenance Contractor Certification Program (see page 12).



Fig.3 Watch the Downstream Defender® instructional maintenance video at www.hydro-int.com/us/products/downstream-defender.



Inspection Procedures

1. Set up any necessary safety equipment around the access port or grate of the Downstream Defender® as stipulated by local ordinances. Safety equipment should notify passing pedestrian and road traffic that work is being done.
2. Remove the lids to the manhole (Fig. 4). NOTE: The 4-ft (1.2m) Downstream Defender® will only have one lid.
3. Without entering the vessel, look down into the chamber to inspect the inside. Make note of any irregularities. See Fig.7 and 8 for typical inspection views.
4. Without entering the vessel, use the pole with the skimmer net to remove floatables and loose debris from the outer annulus of the chamber.
5. Using a sediment probe such as a Sludge Judge®, measure the depth of sediment that has collected in the sump of the vessel (Fig.5).
6. On the Maintenance Log (see page 9), record the date, unit location, estimated volume of floatables and gross debris removed, and the depth of sediment measured. Also note any apparent irregularities such as damaged components or blockages.



Fig.7 View over center shaft into sediment storage zone.

Hydro International (Stormwater), 94 Hutchins Drive, Portland ME 04102
Tel: (207) 756-6200 Fax: (207) 756-6212 Web: www.hydro-int.com

7. Securely replace the grate or lid.
8. Take down safety equipment.
9. Notify Hydro International of any irregularities noted during inspection.

Floatables and Sediment Cleanout

Floatables cleanout is typically done in conjunction with sediment removal. A commercially or municipally owned sump-vac is used to remove captured sediment and floatables (Fig.6).

Floatables and loose debris can also be netted with a skimmer and pole. The access port located at the top of the manhole provides unobstructed access for a vactor hose and skimmer pole to be lowered to the base of the sump.

Scheduling

- Floatables and sump cleanout are typically conducted once a year during any season.
- If sediment depths are greater than 75% of maximum clean-out depths stated in Table 1, sediment removal is required.
- Floatables and sump cleanout should occur as soon as possible following a spill in the contributing drainage area.



Fig.8 View of outer annulus of floatables and oil collection zone.

The Downstream Defender® allows for easy and safe inspection, monitoring and clean-out procedures. A commercially or municipally owned sump-vac is used to remove captured sediment and floatables. Access ports are located in the top of the manhole. On the 6-ft (1.8m), 8-ft (2.4m), 10-ft (3.0m) and 12-ft (3.7m) units, the floatables access port is above the outlet pipe between the concrete manhole wall and the dip plate. The sediment removal access ports for all Downstream Defender® models are located directly over the hollow center shaft.

Maintenance events may include Inspection, Oil & Floatables Removal, and Sediment Removal. Maintenance events do not require entry into the Downstream Defender®, nor do they require the internal components of the Downstream Defender® to be removed. In the case of inspection and floatables removal, a vactor truck is not required. However, a vactor truck is required if the maintenance event is to include oil removal and/or sediment removal.

Determining Your Maintenance Schedule

The frequency of cleanout is determined in the field after installation. During the first year of operation, the unit should be inspected every six months to determine the rate of sediment and floatables accumulation. A simple probe such as a Sludge Judge® can be used to determine the level of accumulated solids stored in the sump. This information can be recorded in the maintenance log (see page 9) to establish a routine maintenance schedule.

The vactor procedure, including both sediment and oil/floatables removal, for a 6-ft (1.8m) Downstream Defender® typically takes less than 30 minutes and removes a combined water/oil volume of about 500 gallons (1900 liters).

Table 1. Downstream Defender® Pollutant Storage Capacities and Max. Cleanout Depths.

Unit Diameter		Total Oil Storage		Oil Clean-out Depth		Total Sediment Storage		Sediment Clean-out Depth		Max. Liquid Volume Removed	
(ft)	(m)	(gal)	(L)	(in)	(cm)	(yd³)	(m³)	(in)	(cm)	(gal)	(L)
4	1.2	70	265	<16	<41	0.70	0.53	<18	<45	384	1,454
6	1.8	216	818	<23	<58	2.10	1.61	<24	<61	1,239	4,690
8	2.4	540	2,044	<33	<84	4.65	3.56	<30	<76	2,884	10,917
10	3.0	1,050	3,975	<42	<107	8.70	6.65	<36	<91	5,546	20,994
12	3.7	1,770	6,700	<49	<125	14.70	11.24	<42	<107	9,460	35,810

NOTES

1. Refer to Downstream Defender® Clean-out Detail (Fig.2) for measurement of depths.
2. Oil accumulation is typically less than sediment, however, removal of oil and sediment during the same service is recommended.
3. Remove floatables first, then remove sediment storage volume.
4. Sediment removal is not required unless sediment depths exceed 75% of maximum clean-out depths stated in Table 1.



Recommended Equipment

- Safety Equipment (traffic cones, etc.)

- Crow bar or other tool to remove grate or lid
- Pole with skimmer or net (if only floatables are being removed)
- Sediment probe (such as a Sludge Judge®)

- Vactor truck (6-inch/150mm diameter flexible hose recommended)

- Downstream Defender® Maintenance Log

Floatables and Sediment Clean Out Procedures

1. Set up any necessary safety equipment around the access port or grate of the Downstream Defender® as stipulated by local ordinances. Safety equipment should notify passing pedestrian and road traffic that work is being done.
2. Remove the lids to the manhole NOTE: The 4-ft (1.2m) Downstream Defender® will only have one lid.
3. Without entering the vessel, look down into the chamber to inspect the inside. Make note of any irregularities.
4. Using the Floatables Port for access, remove oil and floatables stored on the surface of the water with the vactor hose or the skimmer net (Fig.9, top).
5. Using a sediment probe such as a Sludge Judge®, measure the depth of sediment that has collected in the sump of the vessel and record it in the Maintenance Log (Pg.9).
6. Once all floatables have been removed, drop the vactor hose to the base of the sump via the Central Access Port. Vactor out the sediment and gross debris off the sump floor (Fig.6 and 9).

Maintenance at a Glance

Activity	Frequency
Inspection	- Regularly during first year of installation - Every 6 months after the first year of installation
Oil and Floatables Removal	- Once per year, with sediment removal - Following a spill in the drainage area
Sediment Removal	- Once per year or as needed - Following a spill in the drainage area

NOTE: For most cleanouts it is not necessary to remove the entire volume of liquid in the vessel. Only removing the first few inches of oils/floatables and the sediment storage volume is required.



Inspection Procedures

Inspection is a simple process that does not involve entry into the Downstream Defender®. Maintenance crews should be familiar with the Downstream Defender® and its components prior to inspection.

Scheduling

- It is important to inspect your Downstream Defender® every six months during the first year of operation to determine your site-specific rate of pollutant accumulation

- Typically, inspection may be conducted during any season of the year

- Sediment removal is not required unless sediment depths exceed 75% of maximum clean-out depths stated in Table 1

Recommended Equipment

- Safety Equipment and Personal Protective Equipment (traffic cones, work gloves, etc.)


- Crow bar or other tool to remove grate or lid

- Pole with skimmer or net


- Sediment probe (such as a Sludge Judge®)

- Trash bag for removed floatables

- Downstream Defender® Maintenance Log



Site Design Consultants
Civil Engineers • Land Planners
251-F Underhill Avenue, Yorktown Heights, NY 10598
(914) 962-4488 - Fax: (914) 962-7386
www.sitedesignconsultants.com



Revisions:	No.	Date	Comments
	1	5/2/18	Plan Revisions
	2	5/25/18	Town Comments

SCALE: NTS	DRAWN BY: TK	DATE: 3/21/18
------------	--------------	---------------

**DOWNSIDE DEFENDER
DETAILS**

**ARMSTRONG PLUMBING
LLC**
593 NORTH STATE ROAD
Town of Ossining
Westchester County, NY

Sheet 9 of 9