

LOCATION MAP
NOT TO SCALE

SITE DATA:

CONTRACT VENDEE:
DEVELOPER:


PROJECT LOCATION:

EXISTING TOWN ZONING:
PROPOSED USE:
TOWN TAX MAP DATA:
SITE AREA :
SEWAGE FACILITIES:
WATER FACILITIES:

AUDUBON MANOR LLC.
PARTH KNOLLS LLC.
500 EXECUTIVE BLVD. #203
OSSINING, NY, 10562
87 HAWKES AVE.
OSSINING, NY, 10562
MF-1, MULTIFAMILY-INN
MF-1, MULTIFAMILY-INN
SECTION 80.20, BLOCK 1, LOT 15
5.53 ACRES (240,751 SF)
PUBLIC SEWERS
PUBLIC WATER FACILITIES

DRAWING INDEX:

SHEET NUMBER	DRAWING TITLE
T-1	TITLE SHEET
T-2	TITLE SHEET 2
C-101	SITE PLAN
C-102	EXISTING CONDITIONS PLAN
C-103	EROSION AND SEDIMENT CONTROL PLAN
C-104	UTILITY PLAN
C-105	GRADING PLAN
C-106	SIGHT DISTANCE PLAN
C-107	TREE PLAN
C-108	FIRE ACCESS PLAN
C-109	ENVIRONMENTAL CONSTRAINTS MAP
C-110	OPEN SPACE AND RECREATION PLAN
C-111	LIGHTING PLAN
C-301	PROFILES
G-1	NOTES
G-2	E&SC NOTES
C-501	E&SC DETAILS
C-502	SITE DETAILS
C-503	WATERMAIN DETAILS
C-504	SANITARY SEWER DETAILS
C-505	DRAINAGE DETAILS
C-506	STORMWATER MANAGEMENT DETAILS
C-507	CRYSTAL STREAM DETAILS
C-508	CISTERN DETAILS
M-101	WETLAND BUFFER MITIGATION PLAN
M-102	BUFFER MITIGATION NOTES
L-101	LANDSCAPE PLAN
A-100	ZONING & CODE ANALYSIS
A-100A	SCHEMATIC BUILDING LAYOUT AND TABULATIONS
A-101	PROPOSED BUILDING #1 - BASEMENT FLOOR PLAN
A-102	PROPOSED BUILDING #1 - FIRST FLOOR PLAN
A-103	PROPOSED BUILDING #1 - SECOND FLOOR PLAN
A-104	PROPOSED BUILDING #1 - UPPER LEVEL FLOOR PLAN
A-105	PROPOSED BUILDING #1 - ROOF PLAN
A-106	PROPOSED BUILDING #1 - FRONT AND REAR ELEVATIONS
A-107	PROPOSED BUILDING #1 - LEFT AND RIGHT SIDE ELEVATIONS
A-201	PROPOSED BUILDING #2 - BASEMENT FLOOR PLAN
A-202	PROPOSED BUILDING #2 - FIRST FLOOR PLAN
A-203	PROPOSED BUILDING #2 - SECOND FLOOR PLAN
A-204	PROPOSED BUILDING #2 - UPPER LEVEL FLOOR PLAN
A-205	PROPOSED BUILDING #2 - ROOF PLAN
A-206	PROPOSED BUILDING #2 - FRONT AND REAR ELEVATIONS
A-207	PROPOSED BUILDING #2 - LEFT AND RIGHT SIDE ELEVATIONS





CONTRACT VENDEE:
AUDUBON MANOR, CO., LLC.
500 EXECUTIVE BLVD #203
OSSINING, NY 10562
CIVIL ENGINEER:
SITE DESIGN CONSULTANTS
251-F UNDERHILL AVENUE
YORKTOWN HEIGHTS, NY 10598
P: 914 962 4488
F: 914 962 7386
jriina@sitedesignconsultants.com

SURVEYOR:
LINK LAND SURVEYORS
21 CLARK PLACE, SUITE 1B
MAHOPAC, NY 10541
P: 845-628-5857
F: 845-621-0013
www.linklandsurveyors.com

ENVIRONMENTAL CONSULTANT:
TIM MILLER ASSOCIATES INC.
10 NORTH STREET
COLD SPRING, NY 10516
P: 845-265-4400

TRAFFIC CONSULTANT:
TIM MILLER ASSOCIATES INC.
10 NORTH STREET
COLD SPRING, NY 10516
P: 845-265-4400

ARCHITECT:
ARQ.HT, LLC.
100 EXECUTIVE BLVD #205
OSSINING, NY 10562
P: 914-944-3377



ZONING SCHEDULE:

ZONING DISTRICT: MF-I, MULTI FAMILY RESIDENTIAL			
DIMENSIONAL REGULATIONS:	REQUIRED	PROVIDED	VARIANCE REQUIRED
MINIMUM SIZE OF LOT:			
MINIMUM LOT AREA:	40,000 SF.	240,751 SF.	NONE
MINIMUM LOT WIDTH:	150 FT.	522 FT.	NONE
MINIMUM LOT DEPTH:	150 FT.	414 FT.	NONE
MINIMUM YARD DIMENSIONS:			
PRINCIPAL BUILDING:			
FRONT YARD SETBACK:	50 FT.	82 FT.	NONE
REAR YARD SETBACK:	40 FT.	257 FT.	NONE
ONE SIDE YARD SETBACK:	50 FT.	50 FT.	NONE
COMBINED SIDE YARD SETBACK:	100 FT.	100 FT.	NONE
MAXIMUM % OF LOT TO BE OCCUPIED:			
LOT COVERAGE:	66% x 240,751 SF = 158,895 SF	71,456 SF	NONE
BUILDING COVERAGE:	20% x 240,751 SF = 48,151 SF	32,001 SF	NONE
MAXIMUM HEIGHT:			
PRINCIPAL BUILDING - FEET:	35 FEET	30 FEET	NONE
PRINCIPAL BUILDING - STORIES:	2 1/2	2 1/2	NONE

ZONING REGULATION NOTES:

1. AT LEAST 1/3 OF THE NET SITE AREA SHALL BE DEVOTED TO PERMANENT OPEN SPACE AND/OR FOR SITES SUITABLE FOR RECREATION AS REQUIRED BY NOTE 2. UNDEVELOPED PERMANENT OPEN SPACE SHALL BE PROVIDED AND GUARANTEED AT THE RATE OF 1,500 SQUARE FEET PER BEDROOM.
2. THERE SHALL BE PROVIDED ON THE SAME LOT A SUITABLY EQUIPPED AND LANDSCAPED CHILDREN'S PLAY AREA WITH A MINIMUM OF 400 SQUARE FEET FOR EACH DWELLING UNIT.
3. BUILDING COVERAGE SHALL BE NO MORE THAN 20% OF LOT AREA. 20% x 240,751 SF = 48,151 SF

PARKING SCHEDULE

PARKING REQUIRED: Two (2) spaces per dwelling unit pursuant to Zoning Section 200-29, Dwelling, Multifamily

Proposed Dwelling units. 53 apartments time (2) equals 106 spaces

Indoor Parking	Breakdown	Total Parking
Building No. 1	Standard 25	26
	Handicap 1	
	Total 26	
Building No. 2	Standard 30	31
	Handicap 1	
	Total 31	
Outdoor Parking	Breakdown	
	Standard 48	51
	Handicap 3	
	Total 51	
Total Parking Provided		108
Bank Parking for future use, if required [spaces #59,60,61 & 62]	Standard	4
Total Potential Parking Available		112

Article VI.

Section 200.33 Affordable Housing (BMR)

Section 200.34 Required 10% of the number of Dwelling units

More than 5, but fewer than 10 acres 30%

Maximum permitted Density Bonus

Calculation Dwelling 41 Apartm 41

1/2 of the units received must be BMR

Density Bonus (x) 30%

Number of Dwelling units 12.3

Rounded Number of Dwelling units 12

Total number of units with density Bonus 53

1/2 of the Bonus Units received must be BMR 6

BMR units will be broken down as follows: 1 2 bedroom unit

5 1 bedroom units

General Description of Project

Number of Multifamily Units	Non-BMR	BMR Units	Total Units	Bedrooms	Unit Ratio
Type					
One (1) B/R	31	10	41	41	77%
Two (2) B/R	10	3	13	26	25%
Total Dwelling Units	41	12	53	66	100%

Section 200.28	9	40	40	75%
Parking & loading				
2 for each dwelling unit plus 0.5 for each bedroom more than 2 bedrooms	Regular Apts	BMR Apts	Total Parking	
Dwelling Units	41	12		
Parking per Dwelling Unit	(x) 2	(x) 2		
Total Parking spaces required	82	24	106	

Building Height Max

Stories 2 1/2

Feet 35'

Design Colonial

DISTANCE BETWEEN BLDGS. (#200-16C(1) (B))

BUILDING HEIGHT X 2 = 30 X2= 60" PROVIDED 60'

BULK REGULATIONS (#200-22)

THE TOTAL NUMBER OF APARTMENTS ALLOWED PER SECTION 200-22:

BULK REGULATIONS

1. REQUIRED SQ FT PER DWELLING UNIT. 4,000 SF PLUS 1,500 SQ FT PER BEDROOM.

ONE (1) BEDROOM APARTMENTS 5,500

TWO (2) BEDROOM APARTMENTS 7,000

CALCULATION:

ONE (1) BEDROOM APARTMENTS

5,500SF X 31 = 170,500 SF 31

TWO (2) BEDROOM APARTMENTS

7,000 SF X 10= 70,000 SF

TOTAL APARTMENTS 41

TOTAL SF AREA REQUIRED 240,000 SF

TOTAL PROVIDED-SITE SF AREA: 240,751 SF

Article VI. Affordable Housing

See Sheet T for Calculation of the BMR Units and Compliance with this Section

Section 200-33 Required below -market-rate-unit component

No fewer than 10% of the total number of Units Shall be BMR Units

Number of BMR Units Provided 6

Number of BMR Units Required 5.3

Section 200-34 Residential Density bonus; Multifamily

More than 5 acres, but fewer than 10 30% Bonus

Section 200-35

Sub-Section A The BMR units shall be no less than 80% of the size of said market rate units and shall be reasonably distributed. Further, the BMR units shall provide a mix of unit types in the same proportion

Number of BMR Units Provided 6

See Sheet "T"

The Breakdown of the BMR Units are:

for calculation of One (1) Bedroom Units 3 Simplex & 2 Duplex Units 5

of Bonus Units Two (2) Bedroom Units 1 Simplex Unit 1


and break-down Total BMR Units See location in schedule below 6

Parth Knolls Apartment Tabulation


Building No.	Floor No.	Apartment No.	Livable Sq Ft Area	One B/R Simplex	One B/R Duplex	Two B/R Simplex	BMR Unit	Simp 1 B/R	Dupl 1 B/R	Simp 2 B/R
One	1st fl.	101	1,013	1,013				1		
One	1st fl.	102	1,032	1,032				1		
One	1st fl.	103	1,095	1,095				1		
One	1st fl.	104	1,095	1,095				1		
One	1st fl.	105	1,099	1,099				1		
One	1st fl.	106	1,375			1,375				1
One	1st fl.	107	1,081	1,081				1		
One	1st fl.	108	1,007	1,007			BMR	1		
One	1st fl.	109	1,054	1,054				1		
One	1st fl.	110	1,218			1,218			8	2
Two	1st fl.	111	1,263			1,263				1
Two	1st fl.	112	933	933				1		
Two	1st fl.	113	1,015	1,015				1		
Two	1st fl.	114	1,053			1,053	BMR			1
Two	1st fl.	115	1,459			1,459				1
Two	1st fl.	116	1,015	1,015				1		
Two	1st fl.	117	1,034	1,034				1		
Two	1st fl.	118	1,216			1,216				1
Two	1st fl.	119	1,200			1,200				1
Two	1st fl.	120	927	927				1		
Two	1st fl.	121	1,121	1,121				1		
Two	1st fl.	122	941	941				1		
Two	1st fl.	123	846	846			BMR			
One	2nd fl	201	1,119		1,119				16	0
One	2nd fl	202	1,119		1,119		BMR			7
One	2nd fl	203	1,145			1,145				1
Page 1, Bal. forward page 2			28,475	16,308	2,238	9,929		16	2	8
Building No.	Floor No.	Apartment No.	Livable Sq Ft Area	One B/R Simplex	One B/R Duplex	Two B/R Simplex	BMR Unit	Simp 1 B/R	Dupl 1 B/R	Simp 2 B/R
Balances forward from page 1			28,475	16,308	2,238	9,929		16	2	8
One	2nd fl	204	1,087	1,087				1		
One	2nd fl	205	1,276			1,276				1
One	2nd fl	206	1,264			1,264				1
One	2nd fl	207	1,087	1,087				1		
One	2nd fl	208	849	849			BMR			
One	2nd fl	209	1,109			1,109				1
One	2nd fl	210	1,081	1,081				1		
One	2nd fl	211	1,109			1,109				1
One	2nd fl	212	1,193	1,193				1		
One	2nd fl	213	1,043			1,043				1
One	2nd fl	214	1,110	1,110				1		
Two	2nd fl	215	1,264			1,264			22	7
Two	2nd fl	216	1,204			1,204				8
Two	2nd fl	217	1,209			1,209	BMR			
Two	2nd fl	218	950	950				1		
Two	2nd fl	219	1,255			1,255				1
Two	2nd fl	220	1,038	1,038				1		
Two	2nd fl	221	1,202			1,202				1
Two	2nd fl	222	1,184			1,184				1
Two	2nd fl	223	1,038	1,038				1		
Two	2nd fl	224	1,185			1,185				1
Two	2nd fl	225	1,102			1,102				1
Two	2nd fl	226	1,375			1,375				1
Two	2nd fl	227	1,250			1,250				1
Two	2nd fl	228	1,250	1,250				1		
Two	2nd fl	229	1,196			1,196				1
Two	2nd fl	230	1,138			1,138				1
Total Square Foot Areas			59,523	26,991	16,469	16,063		28	14	13
Break down of Apartment Type				26 Apts	14 Apts	13 Apts				
Average Sq ft size by Apartment Type				1,038 sf	1,176 sf	1,236 sf				
Section 200.35.A										
BMR Units must be no less than 80% of size of said market rate units				830 sf	941 sf	989 sf				
Section 200.35.B										
Minimum gross Floor Area				675 sf	675 sf	750 sf				
Section 200-22										
Minimum requirements. 700 sf per for 1 or more bedrooms				700 sf	700 sf	700 sf				
Provided BMR Units										
Bldg. # 1	1st Fl	Apt No.108		1,007 sf			Break-down of BMR Units:			
Bldg. # 1	2nd Fl	Apt No.202			1,119 sf		1 B/R Simplex			
Bldg. # 1	2nd Fl	Apt No. 208		849 sf			1 B/R Duplex			
Bldg. # 2	1st Fl	Apt No.123		846 sf			1 B/R Simplex			
Bldg. # 2	1st Fl	Apt No.114				1,053 sf	2 B/R Simplex			
Bldg. # 2	2nd Fl	Apt No. 227			1,209 sf		1 B/R Duplex			

87.Parth Knolls BMR Units-Rev.1.2.29.16

Page 2



NOTE:
1. THIS IS NOT A SURVEY. ALL SURVEY INFORMATION SHOWN ON THIS PLAN HAS BEEN TAKEN FROM SURVEY MAP PREPARED BY JOSEPH R. LINK, DATED 03/07/15, LAST REVISED 06/08/15. THE ENGINEER ASSUMES NO RESPONSIBILITY FOR ITS ACCURACY.



Civil Engineers • Land Planners
251-F Underhill Avenue, Yorktown Heights, NY 10598
(914) 962-4488 - Fax: (914) 962-7386
www.sitedesignconsultants.com

Engineer:

Joseph C. Riina, P.E.

SCALE:
1" = 30'

DRAWN BY:
TK

DATE:
9/25/15

SITE PLAN

PARTH KNOLLS LLC.

87 HAWKES AVENUE


Town of Ossining
Westchester County, NY

heet

C-101



NOTE:
1. THIS IS NOT A SURVEY. ALL SURVEY INFORMATION SHOWN ON THIS PLAN HAS BEEN TAKEN FROM SURVEY MAP PREPARED BY JOSEPH R. LINK, DATED 03/07/15, LAST REVISED 06/08/15. THE ENGINEER ASSUMES NO RESPONSIBILITY FOR ITS ACCURACY.



PROJECT # 1518

Site Design Consultants
Civil Engineers • Land Planners
251-F Underhill Avenue, Yorktown Heights, NY 10598
(914) 962-4488 - Fax: (914) 962-7386
www.sitedesignconsultants.com

Engineer:
Joseph C. Rinna, P.E.
NYS Lic. No. 64431

Revisions:	
No.	Date
1	11/9/15
2	12/7/15
3	1/25/16
4	3/7/16

SCALE:
1" = 30'

DRAWN BY:
TK


DATE:
9/25/15

**EXISTING
CONDITIONS**

**SITE PLAN
PREPARED FOR**
PARTH KNOLLS LLC.
87 HAWKES AVENUE
Town of Ossining
Westchester County, NY

Sheet
C-102

COPYRIGHT © 2012 BY SITE DESIGN CONSULTANTS, ALL RIGHTS RESERVED



- PROPOSED TREE TO BE PROTECTED (TYP)
- PROPOSED EROSION BLANKET (TYP)
- PROPOSED SILT FENCE (TYP)
- PROPOSED INLET PROTECTION (TYP)
- PRPOSED SOIL STOCKPILE (TYP)
- PROPOSED CONSTRUCTION DUMPSTER LOCATION
- PROPOSED TREE TO BE RMEOVED (TYP)
- PRPOSED LIMIT OF DISTURBANCE (TYP)

PROPOSED BUILDING #1
F.F. ELEVATION = 315.0
PARKING ELEVATION = 305.0

PROPOSED BUILDING #2
F.F. ELEVATION = 317.2
PARKING ELEVATION = 307.2

PHASE I
PHASE II

TREE #1659 BLEW DOWN
DURING STORM ON 8/24/16

100' BUFFER AS PER
OSSINING CODE (105.16)

PROPOSED CONSTRUCTION ENTRANCE (TYP)


TW: 313.5
BW: 311.0
TW: 316.0
BW: 314.5
TW: 313.5
BW: 313.0

TW: 309.0
BW: 306.5
TW: 308.0
BW: 305.5
TW: 316.0
BW: 313.5
TW: 309.0
BW: 306.5

POOL ELEVATION = 305.5


LEGEND

- 222 EXISTING GRADING
- X 222.8 EXISTING SPOT GRADE
- 200 PROPOSED GRADING
- PROPERTY LINE / RIGHT OF WAY
- EDGE OF WETLAND
- 100' WETLAND BUFFER
- PROPOSED FIRE HYDRANT
- PROPOSED DRAINAGE LINE
- PROPOSED CATCH BASIN
- PROPOSED DRAINAGE MANHOLE
- PROPOSED CRYSTAL STREAM STRUCTURE
- PROPOSED HEADWALL WITH RIP RAP
- PROPOSED SEWER SERVICE CONNECTION
- PROPOSED WATER MAIN
- PROPOSED WATER SERVICE CONNECTION
- PROPOSED SANITARY MANHOLE AND LINE
- PROPOSED BUILDING AND DRIVE
- PROPOSED SOIL STOCKPILES
- PROPOSED SILT FENCE
- PROPOSED CRUSHED STONE INLET PROTECTION
- PROPOSED STABILIZED CONSTRUCTION ENTRANCE
- PROPOSED LIMIT OF DISTURBANCE
- EXISTING TREE TO BE PROTECTED
- EXISTING TREE TO BE REMOVED



SAFE DIG
Before You Dig, Drill or Blast!
Call 811
www.call811.com

NOTE:
1. THIS IS NOT A SURVEY. ALL SURVEY INFORMATION SHOWN ON THIS PLAN HAS BEEN TAKEN FROM SURVEY MAP PREPARED BY JOSEPH R. LINK, DATED 03/07/15, LAST REVISED 06/08/15. THE ENGINEER ASSUMES NO RESPONSIBILITY FOR ITS ACCURACY.



PROJECT # 1518

Site Design Consultants
Civil Engineers • Land Planners
251-F Underhill Avenue, Yorktown Heights, NY 10598
(914) 962-4488 - Fax: (914) 962-7386
www.sitedesignconsultants.com

Engineer:
Joseph C. Riina, P.E.
NYS Lic. No. 64431

Revisions:	
No.	Comments
1	11/9/15 Town Comments
2	12/7/15 Town Comments
3	1/25/16 Town Comments
4	3/7/16 Town Comments

SCALE: 1" = 30'

DRAWN BY: TK

DATE: 9/25/15


E&S PLAN

SITE PLAN
PREPARED FOR
PARTH KNOLLS LLC.
87 HAWKES AVENUE
Town of Ossining
Westchester County, NY

Sheet
C-103

STORMWATER RIMS & INV.									
Pipe	Upstream Structure	Rim	Downstream Structure	Rim	Length (ft)	Section Size (in)	Upstream Inv. Elev. (ft)	Downstream Inv. Elev. (ft)	Slope (%)
CB-1 TO CB-2	CB-1	317.33	CB-2	314.95	49.12	12	314.28	311.79	5.07
CB-2 TO CB-3	CB-2	314.95	CB-3	314.01	43.06	12	311.54	311.01	1.23
CB-3 TO CB-4	CB-3	314.01	CB-4	311.14	71.09	12	310.76	308.14	3.69
CB-4 TO CB-5	CB-4	311.14	CB-5	311.40	23.81	12	307.90	307.78	0.50
CB-5 TO CB-6	CB-5	311.40	CB-6	311.88	69.32	18	307.53	307.18	0.50
CB-6 TO CB-9	CB-6	310.22	CB-9	313.49	60.30	18	306.93	306.63	0.50
CB-7 TO CB-8	CB-7	313.49	CB-8	313.50	20.45	12	310.49	310.39	0.50
CB-8 TO CB-9	CB-8	313.50	CB-9	311.88	137.44	12	310.14	306.70	2.50
CB-9 TO CST #1	CB-9	311.88	CST #1	311.73	20.24	18	306.38	306.28	0.50
CST #1 TO BYPASS 1	CST #1	311.73	BYPASS 1	311.66	17.24	15	306.18	306.09	0.52
BYPASS 1 TO SC-310 CHAMBERS	BYPASS 1	311.66	SC-310 CHAMBERS	306.94	9.56	12	305.05	305.00	0.50
BYPASS 1 TO Outlet 1	BYPASS 1	311.66	Outlet 1	---	50.23	15	305.84	305.59	0.50
CB-10 TO CB-11	CB-10	306.22	CB-11	306.22	23.03	12	303.22	303.1	0.50
CB-11 TO BYPASS 2	CB-11	306.22	BYPASS 2	306.92	18.99	12	302.85	302.76	0.47
BYPASS 2 TO CISTERN	BYPASS 2	306.92	CISTERN	303.14	9.58	12	301.25	301.2	0.50
BYPASS 2 TO DMH-1	BYPASS 2	306.92	DMH-1	304.57	70.89	12	302.45	301.57	1.24
DMH-1 TO Outlet 2	DMH-1	304.57	Outlet 2	---	84.74	12	301.22	300.8	0.50

SANITARY SEWER RIMS & INV.									
Pipe	Upstream Structure	Rim	Downstream Structure	Rim	Length (ft)	Section Size (in)	Upstream Inv. Elev. (ft)	Downstream Inv. Elev. (ft)	Slope (%)
SMH-1 TO SMH-2	SMH-1	307.90	SMH-2	307.00	83.37	6	305.40	304.50	1.08
SMH-2 TO SMH-3	SMH-2	307.00	SMH-3	310.00	157.44	6	304.50	302.75	1.11
SMH-3 TO PUMPSTATION	SMH-3	310.00	PUMPSTATION	309.20	5.50	6	302.75	302.50	4.55



NOTE:
1. THIS IS NOT A SURVEY. ALL SURVEY INFORMATION SHOWN ON THIS PLAN HAS BEEN TAKEN FROM SURVEY MAP PREPARED BY JOSEPH R. LINK, DATED 03/07/15, LAST REVISED 06/08/15. THE ENGINEER ASSUMES NO RESPONSIBILITY FOR ITS ACCURACY.

PROJECT # 15-18

Site Design Consultants
Civil Engineers • Land Planners
251-F Underhill Avenue, Yorktown Heights, NY 10598
(914) 962-4488 - Fax: (914) 962-7386
www.sitedesignconsultants.com

Engineer:
Joseph C. Rinna, P.E.
NYS Lic. No. 64431

Revisions:	No.	Date	Comments
	1	11/9/15	Town Comments
	2	12/7/15	Town Comments
	3	1/25/16	Town Comments
	4	3/7/16	Town Comments

SCALE: 1"=30'-0"

DRAWN BY: TK

DATE: 9/25/15

UTILITY PLAN


SITE PLAN
PREPARED FOR
PARTH KNOLLS LLC.
87 HAWKES AVENUE
Town of Ossining
Westchester County, NY


Sheet
C-104

F:\2015\15-18 BELDOTT MANAGEMENT CORP\15-18 SITE PLAN\2-22-16.DWG

NOTE:
1. THIS IS NOT A SURVEY. ALL SURVEY INFORMATION SHOWN ON THIS PLAN HAS BEEN TAKEN FROM SURVEY MAP PREPARED BY JOSEPH R. LINK, DATED 03/07/15, LAST REVISED 06/08/15. THE ENGINEER ASSUMES NO RESPONSIBILITY FOR ITS ACCURACY.

Copyright © 2015 by Parth Knolls LLC. All rights reserved. No part of this publication may be reproduced, stored in a retrieval system, or transmitted, in any form or by any means, electronic, mechanical, photocopying, recording, or by any information storage or retrieval system, without prior written permission from Parth Knolls LLC.





PROJECT # 1518

Site Design Consultants

Civil Engineers • Land Planners

251-F Underhill Avenue, Yorktown Heights, NY 10598

(914) 962-4488 - Fax: (914) 962-7386

www.sitedesignconsultants.com

Engineer:

Joseph C. Rinna, P.E.

NYS Lic. No. 64431

Revisions:	No.	Date	Comments
	1	11/9/15	Town Comments
	2	12/7/15	Town Comments
	3	1/25/16	Town Comments
	4	3/7/16	Town Comments

SCALE:

1" = 30'

DRAWN BY:

TK

DATE:

9/25/15

GRADING PLAN

SITE PLAN
PREPARED FOR

PARTH KNOLLS LLC.


87 HAWKES AVENUE

Town of Ossining

Westchester County, NY





Sheet

C-105





NOTE:

1. THE 85TH PERCENTILE SPEEDS ARE 46 MPH FOR THE SOUTHBOUND LANE AND 44 MPH FOR THE NORTHBOUND LANE.
2. MAXIMUM SIGHT DISTANCE FOR THE NORTHERN ENTRANCE EXTENDS BEYOND THE LIMITS OF THE SURVEY INFORMATION. IT EXCEEDS 522' IN THE SOUTHBOUND LANE AND 600' IN THE NORTHBOUND LANE. THESE VALUES ARE WELL ABOVE THE REQUIRED MINIMUM SIGHT DISTANCES FOR THE NORTHERN ENTRANCE.
3. ASHTO(AMERICAN ASSOCIATION OF STATE HIGHWAY AND TRANSPORTATION OFFICIALS) REQUIREMENTS BASED ON CALCULATED VALUES




EXISTING GRADING
 EXISTING SPOT GRADE
 PROPOSED GRADING
 PROPERTY LINE / RIGHT OF WAY
 PROPOSED ROAD CENTERLINE
 PROPOSED CURB
 EDGE OF WETLAND
 100' WETLAND BUFFER
 PROPOSED HOUSE AND DRIVE










SAFE DIG
Before You Dig, Drill or Blast!
 CALL US TOLL FREE 811 or 1-800-962-7962
 NY Industrial Code Rule 753 requires no less
 than two working days notice, but not more
 than ten days notice.
www.digsafelynewyork.com


NOTE:
1. THIS IS NOT A SURVEY. ALL SURVEY INFORMATION SHOWN ON THIS PLAN HAS BEEN TAKEN FROM SURVEY MAP PREPARED BY JOSEPH R. LINK, DATED 03/07/15, LAST REVISED 06/08/15. THE ENGINEER ASSUMES NO RESPONSIBILITY FOR ITS ACCURACY.


<p>Sheet</p> <h1 style="text-align: center; margin: 0;">C-106</h1>	<p style="text-align: center;">SITE PLAN PREPARED FOR:</p> <h2 style="text-align: center; margin: 0;">PARTH KNOLLS LLC.</h2> <p style="text-align: center;">87 HAWKES AVENUE Town of Ossining Westchester County, NY</p>	<p style="text-align: center;">SIGHT DISTANCE PLAN</p>																																							
<p>SCALE: 1" = 40'</p>	<p>DRAWN BY: TK</p>	<p>DATE: 9/25/15</p>																																							
<table border="1" style="width: 100%; border-collapse: collapse;"> <thead> <tr> <th style="width: 10%;">Revisions:</th> <th style="width: 10%;">Date</th> <th style="width: 80%;">Comments</th> </tr> </thead> <tbody> <tr> <td>No. 1</td> <td>1/29/15</td> <td>Town Comments</td> </tr> <tr> <td>No. 2</td> <td>12/7/15</td> <td>Town Comments</td> </tr> <tr> <td>No. 3</td> <td>1/25/16</td> <td>Town Comments</td> </tr> <tr> <td>No. 4</td> <td>3/7/16</td> <td>Town Comments</td> </tr> <tr><td> </td><td> </td><td> </td></tr> <tr><td> </td><td> </td><td> </td></tr> <tr><td> </td><td> </td><td> </td></tr> <tr><td> </td><td> </td><td> </td></tr> <tr><td> </td><td> </td><td> </td></tr> <tr><td> </td><td> </td><td> </td></tr> <tr><td> </td><td> </td><td> </td></tr> <tr><td> </td><td> </td><td> </td></tr> </tbody> </table>			Revisions:	Date	Comments	No. 1	1/29/15	Town Comments	No. 2	12/7/15	Town Comments	No. 3	1/25/16	Town Comments	No. 4	3/7/16	Town Comments																								
Revisions:	Date	Comments																																							
No. 1	1/29/15	Town Comments																																							
No. 2	12/7/15	Town Comments																																							
No. 3	1/25/16	Town Comments																																							
No. 4	3/7/16	Town Comments																																							
<p>Engineer:</p> <div style="float: right; text-align: right;"> Joseph C. Riina, P.E. NYS Lic. No. 64431 </div>																																									
<div style="display: flex; justify-content: space-between;"> <div style="width: 30%;"> <p>Site Design Consultants</p> <p>Civil Engineers • Land Planners</p> <p>251-F Underhill Avenue, Yorktown Heights, NY 10598 (914) 962-4488 • Fax: (914) 962-7386 www.sitedesignconsultants.com</p> </div> <div style="width: 30%; text-align: center;">  </div> <div style="width: 30%; text-align: right;"> <p>PROJECT # 15-18</p> </div> </div>																																									

TREES WEST OF STREAM			
Tag #	Species	DBH	Condition
1900	Tulip poplar	32	Good
1599	Red maple	19	Good
1598	Red maple	224	Good
1597	Red maple	36	Poor
1596	Red maple	13	Good
1595	Red maple	22	Poor
1594	Tulip poplar	11	Fair
1593	Red maple	21	Good
1592	Red maple	18	Good
1591	Pin Oak	30	Good but leaning
1590	Pin Oak	24	Good but leaning
1589	Beech	16	Good
1588	Red maple	42	Good/Fair Craggy
1587	Black birch	11	Fair
1586	Triple Beech	21/15/9	Good
1585	Red Oak	20	Good
1584	Pignut hickory	24	Good
1583	Beech	11	Good
1582	Sugar maple	12	Good
1581	Black birch	17	Good
1580	Red Oak	23	Fair but leaning
1579	Red Oak	11	Fair but tangled with adjacent tree
1578	Norway maple	12	Good
1577	Tulip poplar	26	Good but leaning
1576	Beech	12	Good
1575	Birch	20	Fair
1574	Norway maple	10	Good


LEGEND

      	<p>EXISTING GRADING</p> <p>EXISTING SPOT GRADE</p> <p>PROPOSED GRADING</p> <p>PROPERTY LINE / RIGHT OF WAY</p> <p>EDGE OF WETLAND</p> <p>100' WETLAND BUFFER</p> <p>PROPOSED BUILDING AND DRIVE</p> <p>EXISTING TREE TO BE PROTECTED</p> <p>EXISTING TREE TO BE REMOVED</p>
---	---



Sheet C-107	<div style="text-align: right;">SITE PLAN PREPARED FOR PARTH KNOLLS LLC. 87 HAWKES AVENUE Town of Ossining Westchester County, NY</div>	<div style="text-align: right;">SCALE: 1" = 30'</div> <div style="text-align: right;">DRAWN BY: TK</div> <div style="text-align: right;">DATE: 9/25/15</div>	<div style="text-align: right;">TREE PLAN</div>																														
<div style="text-align: right;">Revisions:</div> <table border="1" style="width: 100%; border-collapse: collapse;"><thead><tr><th>No.</th><th>Date</th><th>Comments</th></tr></thead><tbody><tr><td>1</td><td>10/1/15</td><td>Town Comments</td></tr><tr><td>2</td><td>10/1/15</td><td>Town Comments</td></tr><tr><td>3</td><td>1/25/16</td><td>Town Comments</td></tr><tr><td>4</td><td>3/7/16</td><td>Town Comments</td></tr><tr><td> </td><td> </td><td> </td></tr><tr><td> </td><td> </td><td> </td></tr><tr><td> </td><td> </td><td> </td></tr><tr><td> </td><td> </td><td> </td></tr><tr><td> </td><td> </td><td> </td></tr></tbody></table>				No.	Date	Comments	1	10/1/15	Town Comments	2	10/1/15	Town Comments	3	1/25/16	Town Comments	4	3/7/16	Town Comments															
No.	Date	Comments																															
1	10/1/15	Town Comments																															
2	10/1/15	Town Comments																															
3	1/25/16	Town Comments																															
4	3/7/16	Town Comments																															
<div style="text-align: right;">Engineer:</div> <table border="1" style="width: 100%; border-collapse: collapse;"><tr><td style="width: 50%; height: 100px;"></td><td style="width: 50%; text-align: center; vertical-align: middle;"><div style="text-align: right;">Joseph C. Riina, P.E. NYS Lic. No. 64431</div></td></tr></table>					<div style="text-align: right;">Joseph C. Riina, P.E. NYS Lic. No. 64431</div>																												
	<div style="text-align: right;">Joseph C. Riina, P.E. NYS Lic. No. 64431</div>																																
<div style="text-align: right;">Site Design Consultants Civil Engineers • Land Planners 251-F Underhill Avenue, Yorktown Heights, NY 10598 (914) 962-4488 - Fax: (914) 962-7386 www.sitedesignconsultants.com</div>																																	
<div style="text-align: right;"> PROJECT # 15-18</div>																																	


NOTE:
1. THIS IS NOT A SURVEY. ALL SURVEY INFORMATION SHOWN ON THIS PLAN HAS BEEN TAKEN FROM SURVEY MAP PREPARED BY JOSEPH R. LINK, DATED 03/07/15, LAST REVISED 06/08/15. THE ENGINEER ASSUMES NO RESPONSIBILITY FOR ITS ACCURACY.




NOTE:
1. THIS IS NOT A SURVEY. ALL SURVEY INFORMATION SHOWN ON THIS PLAN HAS BEEN TAKEN FROM SURVEY MAP PREPARED BY JOSEPH R. LINK, DATED 03/07/15, LAST REVISED 06/08/15. THE ENGINEER ASSUMES NO RESPONSIBILITY FOR ITS ACCURACY.

LEGEND

- PROPERTY LINE / RIGHT OF WAY
- PROPOSED CURB
- EDGE OF WETLAND
- 100' WETLAND BUFFER



SAFE DIG
Before You Dig, Drill or Blast!
Call 811 or 1-800-486-6868
NY Industrial Code Rule 23 requires no less than ten days notice.
www.digbeforeyoudig.com



PROJECT # 1518

Site Design Consultants
Civil Engineers • Land Planners
251-F Underhill Avenue, Yorktown Heights, NY 10598
(914) 962-4488 - Fax: (914) 962-7386
www.sitedesignconsultants.com

Engineer:
Joseph C. Rinna, P.E.
NYS Lic. No. 64431

Revisions:	No.	Date	Comments
	1	12/7/15	Town Comments
	2	12/7/15	Town Comments
	3	1/25/16	Town Comments

SCALE:
1" = 30'


DRAWN BY:
TK


DATE:
9/25/15

Fire Access Plan

PARTH KNOLLS LLC.
87 HAWKES AVENUE
Town of Ossining
Westchester County, NY

Sheet
C-108





PROJECT # 15-18

Site Design Consultants

Civil Engineers • Land Planners

251-F Underhill Avenue, Yorktown Heights, NY 10598

(914) 962-4488 • Fax: (914) 962-7386

www.sitedesignconsultants.com

Engineer:

Joseph C. Rinna, P.E.

NYS Lic. No. 64431

Revisions:	
No.	Date
1	11/9/15
2	12/7/15
3	1/25/16
4	5/7/16

SCALE: 1" = 30'

DRAWN BY: TK

DATE: 9/25/15

ENVIRONMENTAL
CONSTRAINTS MAP

SITE PLAN
PREPARED FOR

PARTH KNOLLS LLC.

87 HAWKES AVENUE

Town of Ossining

Westchester County, NY

Sheet


C-109

COPYRIGHT © 2012 BY SITE DESIGN CONSULTANTS, ALL RIGHTS RESERVED

F:\2015\15-18 BELDOTTI MANAGEMENT CORP\15-18 SITE PLAN\2-22-16.DWG

ZONING REGULATION NOTES:
1. AT LEAST 1/3 OF THE NET SITE AREA SHALL BE DEVOTED TO PERMANENT OPEN SPACE AND/OR FOR SITES SUITABLE FOR RECREATION AS REQUIRED BY NOTE 2. UNDEVELOPED PERMANENT OPEN SPACE SHALL BE PROVIDED AND GUARANTEED AT THE RATE OF 1,500 SQUARE FEET PER BEDROOM.
2. THERE SHALL BE PROVIDED ON THE SAME LOT A SUITABLY EQUIPPED AND LANDSCAPED CHILDREN'S PLAY AREA WITH A MINIMUM OF 400 SQUARE FEET FOR EACH DWELLING UNIT.

NOTE:
1. **THIS IS NOT A SURVEY.** ALL SURVEY INFORMATION SHOWN ON THIS PLAN HAS BEEN TAKEN FROM SURVEY MAP PREPARED BY JOSEPH R. LINK, DATED 03/07/15, LAST REVISED 06/08/15. THE ENGINEER ASSUMES NO RESPONSIBILITY FOR ITS ACCURACY.




RECREATION AREA REQUIREMENTS			
NUMBER OF UNITS	REQUIRED SF PER UNIT	AREA REQUIRED	AREA PROVIDED
53	400 SF	21,200 SF	23,045 SF

OPEN SPACE REQUIREMENTS			
APARTMENTS & TYPE	BEDROOMS	OPEN SPACE REQUIRED	OPEN SPACE PROVIDED
ONE BEDROOM - 40	40 x 1,500 SF	60,000 SF	
TWO BEDROOM - 13	26 x 1,500 SF	39,000 SF	
TOTALS - 53	66 BEDROOMS	99,000 SF	
REAR OF PROPERTY			99,985 SF
FRONT OF PROPERTY			32,311 SF
TOTAL PROVIDED			132,296 SF

LEGEND

- PROPERTY LINE / RIGHT OF WAY
- PROPOSED ROAD CENTERLINE
- PROPOSED CURB
- EDGE OF WETLAND
- 100' WETLAND BUFFER
- PROPOSED RECREATION AREA
- PERMANENT OPEN SPACE
- PROPOSED HOUSE AND DRIVE



SAFE DIG
Before You Dig, Drill or Blast!
Call 811
www.call811.org

PROJECT # 15-18

Site Design Consultants
Civil Engineers • Land Planners
251-F Underhill Avenue, Yorktown Heights, NY 10598
(914) 962-4488 - Fax: (914) 962-7386
www.sitedesignconsultants.com

Engineer:
Joseph C. Rinna, P.E.
NYS Lic. No. 64431

Revisions:	No.	Date	Comments
	1	11/9/15	Town Comments
	2	12/7/15	Town Comments
	3	1/25/16	Town Comments

SCALE:
1" = 30'

DRAWN BY:
TK

DATE:
9/25/15

**OPEN SPACE
AND
RECREATION
PLAN**

SITE PLAN
PREPARED FOR
PARTH KNOLLS LLC.
87 HAWKES AVENUE
Town of Ossining
Westchester County, NY

Sheet
C-110

Notes:

1. These calculations are based on the listed fixtures only. Substitution of these fixtures will void all calculations.
2. Acuity Brands Lighting reserves the right to withdraw these copyrighted plans from the public record if substitutions occur.
3. **ALL SUBSTITUTIONS REQUIRE NEW CALCULATIONS BASED ON THE FIXTURES SUPPLIED.**
4. Luminaire near Pool area for security lighting only. Illumination will not meet NYS Sanitary Code for night swimming.

Statistics						
Description	Symbol	Avg	Max	Min	Max/Min	Avg/Min
Drive Lanes and Parking	+	1.9 fc	9.0 fc	0.1 fc	90.0:1	19.0:1
Pool Security Lighting	+	0.7 fc	4.6 fc	0.1 fc	46.0:1	7.0:1
Site Tresspass	+	0.0 fc	0.5 fc	0.0 fc	N/A	N/A

Engineer:

SCALE:
1" = 30'

DRAWN BY:
TK









DATE:
9/25/15

PARTH KNOLLS LLC.

Town of Ossining
Westchester County, NY

Sheet

COPYRIGHT © 2012 BY SITE DESIGN CONSULTANTS. ALL RIGHTS RESERVED.



E:\2014\14-18 BEL DOTTI MANAGEMENT CORP\ENGINEERING\CD\14-18 BEL DOTTI MANAGEMENT CORP\14-18 DETAILS 2-14-16.DWG

GENERAL NOTES:

1. THE ENGINEER WHOSE SEAL APPEARS HEREON HAS NOT BEEN RETAINED FOR SUPERVISION OF CONSTRUCTION. SUBSEQUENTLY, HE IS NOT RESPONSIBLE FOR CONSTRUCTION AND THEREFORE ASSUMES NO RESPONSIBILITY FOR CONSTRUCTION PRACTICES, PROCEDURES, AND RESULTS THEREFROM.
2. THE ENGINEER SHALL NOT BE HELD RESPONSIBLE OR HELD ACCOUNTABLE FOR THE INTEGRITY OF ANY STRUCTURES CONSTRUCTED OR UNDER CONSTRUCTION PRIOR TO THE APPROVAL OF THE PLANS.
3. THE TOWN ENGINEER'S OFFICE AND WATER DISTRICT OFFICE IS TO BE NOTIFIED 24 HOURS BEFORE COMMENCING SITE CONSTRUCTION OR WATER MAIN CONNECTION.
4. ALL WORK IS TO BE IN ACCORDANCE WITH THE TOWN CODE OF PRACTICE AND SPECIFICATIONS.
5. ALL CONDITIONS, LOCATIONS, AND DIMENSIONS SHALL BE FIELD VERIFIED AND THE ENGINEER SHALL BE IMMEDIATELY NOTIFIED OF ANY DISCREPANCIES.
6. ALL CHANGES MADE TO THE PLANS SHALL BE APPROVED BY THE ENGINEER WHOSE SEAL APPEARS ON THESE DRAWINGS. ANY SUCH CHANGES SHALL BE FILED AS AMENDMENTS TO THE ORIGINAL BUILDING PERMIT.
7. ALL WRITTEN DIMENSIONS ON THE DRAWINGS SHALL TAKE PRECEDENCE OVER ANY SCALED DIMENSIONS.
8. IT IS THE CONTRACTOR'S RESPONSIBILITY TO CALL IN A "CODE 53" PRIOR TO CONSTRUCTION FOR UNDERGROUND UTILITY LOCATIONS. 9. SUBSTRUCTURES AND THEIR ENCROACHMENTS BELOW GRADE, IF ANY, ARE NOT SHOWN.
9. ANY PROPOSED ELECTRIC AND/OR TELEPHONE SERVICE LINES ARE TO BE PLACED UNDERGROUND.
10. THE DESIGN ENGINEER DISCLAIMS ANY LIABILITY FOR DAMAGE OR LOSS INCURRED DURING OR AFTER CONSTRUCTION.
11. ALL CONDITIONS, LOCATIONS AND DIMENSIONS SHALL BE FIELD VERIFIED BY THE CONTRACTOR AND THE OWNER/ENGINEER NOTIFIED IN WRITING OF ANY DISCREPANCIES PRIOR TO THE START OF WORK. THE OWNER/ENGINEER WILL EVALUATE THE SITUATION AND MODIFY THE PLAN AS NECESSARY.

CONTRACTOR RESPONSIBILITIES:

1. ALL WORK ON THE PROJECT SHALL BE PERFORMED IN A WORKMAN LIKE MANNER AND SHALL BE IN ACCORDANCE WITH THE STANDARDS OF THE INDUSTRY. THE OWNER WILL BE THE SOLE JUDGE OF THE ACCEPTABILITY OF THE WORK. MATERIALS AND WORK DEEMED UNACCEPTABLE WILL BE REMOVED AND REDONE AT THE SOLE COST AND RESPONSIBILITY OF THE CONTRACTOR.
2. THE CONTRACTOR SHALL BE RESPONSIBLE TO PROTECT HIS WORK AND WILL BE HELD RESPONSIBLE FOR CONSEQUENTIAL DAMAGES DUE TO HIS ACTIVITIES. THE CONTRACTOR SHALL BE RESPONSIBLE TO THE OWNER FOR THE ACTS AND OMISSIONS OF HIS EMPLOYEES AND THEIR AGENTS AND EMPLOYEES, AND ANY OTHER PERSONS PERFORMING ANY THE WORK UNDER A SEPARATE CONTRACT WITH THE CONTRACTOR.
3. IT IS THE CONTRACTOR'S RESPONSIBILITY TO PROPERLY SHORE EXISTING UTILITIES IF REQUIRED BY CONSTRUCTION.
4. IT SHALL BE THE CONTRACTOR'S RESPONSIBILITY TO NOTIFY THE THE BUILDING INSPECTOR IN ADVANCE OF HIS WORK OR AS THE INSPECTOR DEEMS APPROPRIATE.
5. ALL CONDITIONS, LOCATIONS AND DIMENSIONS SHALL BE FIELD VERIFIED BY THE CONTRACTOR AND THE OWNER/ENGINEER NOTIFIED IN WRITING OF ANY DISCREPANCIES PRIOR TO THE START OF WORK. THE OWNER/ENGINEER WILL EVALUATE THE SITUATION AND MODIFY THE PLAN AS NECESSARY.
6. ALL CHANGES MADE TO THIS PLAN SHALL BE APPROVED BY THE ENGINEER WHOSE SEAL APPEARS ON THESE DRAWINGS. ANY UNAUTHORIZED ALTERATION OR ADDITIONS TO THIS DRAWING IS A VIOLATION OF SECTION 7209 (2) OF THE NEW YORK STATE EDUCATION LAW.
7. THE CONTRACTOR SHALL SUPERVISE AND DIRECT THE WORK USING HIS BEST SKILL AND ATTENTION. HE SHALL BE SOLELY RESPONSIBLE FOR ALL CONSTRUCTION MEANS, METHODS, TECHNIQUES, SEQUENCES, AND PROCEDURES AND FOR COORDINATING ALL PORTIONS OF THIS WORK UNDER THIS CONTRACT.
8. THE CONTRACTOR SHALL BE RESPONSIBLE TO THE OWNER FOR THE ACTS AND OMISSIONS OF HIS EMPLOYEES, SUBCONTRACTORS, AND THEIR AGENTS AND EMPLOYEES, AND ANY OTHER PERSONS PERFORMING ANY OF THE WORK UNDER A CONTRACT WITH THE CONTRACTOR.
9. THE CONTRACTOR SHALL VERIFY ALL SUBSTRUCTURES ENCOUNTERED DURING CONSTRUCTION.
10. THE CONTRACTOR SHALL SECURE & PAY FOR A BUILDERS RISK POLICY TO COVER THE PERIOD OF CONSTRUCTION. THE ENGINEER & OWNER SHALL BE NAMED AS ADDITIONAL INSURED. ALL CONTRACTORS EMPLOYED AT THE SITE SHALL BE COVERED BY WORKMAN'S COMPENSATION.

GENERAL CONSTRUCTION NOTES:

1. BENCH MARKS USING U.S.G.S. DATUM SHALL BE OF SUCH ELEVATION THAT THE GROUND WILL SLOPE AWAY FROM IT IN ALL DIRECTIONS.
2. CONSTRUCTION ACTIVITY SHALL BE LIMITED FROM 8:00 A.M. TO 6 P.M., AND NO CONSTRUCTION ACTIVITY SHALL OCCUR ON SUNDAYS OR LEGAL NEW YORK STATE HOLIDAYS. WHERE BLASTING IS NECESSARY, IT SHALL OCCUR FROM MONDAY THROUGH FRIDAY BETWEEN THE HOURS OF 8:00 A.M. AND 6:00 P.M. NO BLASTING SHALL OCCUR ON HOLIDAYS, SATURDAY OR SUNDAY. ALL BLASTING SHALL ALSO BE COMPLETED IN ACCORDANCE WITH THE TOWN OF OSSINING AND NEW YORK STATE BLASTING ORDINANCES.
3. ANY SOIL THAT IS UNSUITABLE FOR DEVELOPMENT OF BUILDINGS OR ROADWAYS SHALL BE REMOVED FROM THE AREA AND SHALL BE DISPOSED OF WITHIN THE SITE IN NEW EMBANKMENTS WHERE STRUCTURAL LOADING, I.E. A BUILDING OR ROADWAY, WILL NOT TAKE PLACE. WHEN CONSTRUCTION IS PROPOSED TO OCCUR IN SPECIFIC AREAS WHERE SOILS ARE OF QUESTIONABLE SUITABILITY, THE APPLICANT SHALL PROVIDE SOILS ENGINEERING REPORTS AS REQUIRED BY THE PLANNING BOARD ENGINEER, PRIOR TO THE CONSTRUCTION OF ROADWAYS AND, AS REQUIRED BY THE BUILDING INSPECTOR, PRIOR TO THE ISSUANCE OF A BUILDING PERMIT.
4. NO TOPSOIL SHALL BE REMOVED FROM THE SITE.
5. ROCK CUT STABILITY IS TO BE FIELD VERIFIED BY GEOTECHNICAL ENGINEER AND SHALL BE MOIDIFIED IF REQUIRED.
6. NO CRUSHING/PROCESSING IS PERMITTED ON THE SITE WITHOUT PRIOR APPROVAL BY THE TOWN OF OSSINING PLANNING BOARD.

GENERAL STORM DRAINAGE & UTILITY NOTES

1. ALL UTILITIES, INCLUDING ELECTRIC LINES, TELEPHONE, WATER, SANITARY SEWER LINES, AND STORM SEWER LINES SHALL BE LOCATED UNDERGROUND AND SHALL BE INSTALLED IN ACCORDANCE WITH THE REQUIREMENTS OF THE TOWN OF OSSINING AND THE UTILITY COMPANIES HAVING JURISDICTION.
2. LOCATION OF GAS AND WATER VALVES, ELECTRIC AND TELEPHONE POLES ARE TO BE DETERMINED BY PROPER AUTHORITIES AND APPROVED, AS TO LOCATION, BY THE TOWN ENGINEER.
3. EACH BUILDING CONSTRUCTED HEREON SHALL BE OF SUCH AN ELEVATION THAT THE GROUND WILL SLOPE AWAY FROM IT IN ALL DIRECTIONS. IN THE EVENT THAT THIS IS NOT FEASIBLE, THE CONTRACTOR SHALL INSTALL TYPICAL YARD DRAINS AS REQUIRED AND CONNECT THEM TO THE STORM DRAINAGE SYSTEM OR AS DIRECTED BY THE PROJECT ENGINEER.
4. ROOF LEADERS AND FOOTING DRAINS SHALL EMPTY INTO THE STORM DRAINAGE SYSTEM OR DISCHARGE DIRECTLY TO STORMWATER MANAGEMENT SYSTEMS IF GRADES PERMIT, AND CONNECTION TO THE STORM SYSTEM IS NOT FEASIBLE. FOOTING DRAINS ONLY MAY DISCHARGE TO DAYLIGHT AT THE REAR OF BUILDINGS. FOOTING DRAINS SHALL EXTEND A MINIMUM OF 30 FT. FROM THE REAR FACE OF THE BUILDING WHEN POSSIBLE. UNDER NO CIRCUMSTANCES SHALL THE DISCHARGE OF GROUND WATER OR STORM WATER, EITHER BY GRAVITY OR BY PUMPING, BE DISCHARGED TO ANY SANITARY SEWER SYSTEM.
5. ANY REVISIONS AND/OR ADDITIONS TO THE ROAD STORM DRAINAGE SYSTEMS CURRENTLY SHOWN ON THE PLANS WHICH ARE DEEMED NECESSARY DURING CONSTRUCTION MUST BE MADE BY THE CONTRACTOR AS REQUIRED BY THE TOWN AND SHALL BE SHOWN ON THE AS-BUILT DRAWINGS.
6. STORM DRAIN PIPING TO BE HIGH DENSITY POLYETHYLENE AS SHOWN ON THE CONSTRUCTION DRAWINGS. MINIMUM COVER TO BE 2' UNLESS OTHERWISE NOTED.
7. INTERCEPTOR DRAINS ARE TO BE INSTALLED WHERE REQUIRED BY THE TOWN OR PROJECT ENGINEER DURING ROAD CONSTRUCTION.
8. ALL EXISTING UNDERGROUND DRAINS ENCOUNTERED DURING CONSTRUCTION OF PROPOSED ROADS ARE TO BE CONNECTED TO PROPOSED DRAINAGE IMPROVEMENTS. CONNECTIONS TO BE APPROVED BY THE TOWN ENGINEER.
9. PRIOR TO FINAL APPROVAL AND OPERATION OF DRAINAGE SYSTEM, CONTRACTOR SHALL CLEAR ALL ACCUMULATED SEDIMENT AND/OR DEBRIS FROM DRAINAGE STRUCTURES, MANHOLES, CULVERTS, OUTLETS AND DRAIN INLETS. ENGINEER SHALL BE NOTIFIED FOR FINAL INSPECTION.
10. ALL STRUCTURES SHALL BE SET ONE INCH BELOW PAVEMENT.
11. STREET OPENING PERMIT FROM THE TOWN OF OSSINING D.P.W. MAY BE REQUIRED FOR INSTALLATIONS IN PUBLIC ROADS.

WALL NOTES:

1. EXCAVATION IN GENERAL SHALL CONFORM TO THE LINES AND GRADES SHOWN ON THE CONTRACT DRAWINGS.
2. THE ENGINEER SHALL BE NOTIFIED OF UNSUITABLE SUB-GRADE SOILS PRIOR TO PLACEMENT OF WALL.
3. WALLS TO BE CONSTRUCTED ON VIRGIN IN-SITU SOIL SHALL HAVE A MINIMUM ALLOWABLE BEARING CAPACITY OF 2 TSF. ALL OTHER CONDITIONS SHALL BE APPROVED BY THE GEOTECHNICAL ENGINEER.
4. TO INSURE A PROPER BEARING SURFACE, THE WALL SHALL BE CONSTRUCTED ON NATURAL IN-SITU SOIL. THE CONTRACTOR SHALL STRIP ALL TOP SOIL. THE AREA SHALL THEN BE COMPACTED USING SUITABLE COMPACTION EQUIPMENT. A MINIMUM OF 3 PASSES SHALL BE MADE.
5. WALLS SHALL NOT BE CONSTRUCTED ON WET OR FROZEN GROUND.
6. SOILS USED AS BACKFILL SHALL CONSIST OF CLEAN DRY SOIL. THE MATERIAL SHALL BE GRANULAR AND FREE OF ORGANIC OR OTHER DELETERIOUS MATERIAL. IN GENERAL THE SOIL SHALL BE NON-PLASTIC WITH A PLASTICITY INDEX LESS THAN 5 AND SHALL CONFORM TO THE AASHTO SOIL CLASSIFICATION SYSTEM FOR AN "A-1-A" SOIL. HOWEVER THE MAXIMUM SIZE SHALL BE 6". IN GENERAL ALL FILL SHALL BE APPROVED BY THE ENGINEER PRIOR TO ITS USE. WET MATERIAL OR UNSUITABLE MATERIAL SHOULD NOT BE USED.
7. BACKFILL SHALL BE PLACED AND COMPACTED IN A MAXIMUM 12" LIFTS.
8. ALL BOULDER RETAINING WALLS SHALL HAVE A GEOTEXTILE FABRIC BACKING FOR THE FULL HIEGHT OF THE WALL AS MANUFACTURED BY MIRAFI OR APPROVED EQUAL.
9. IF GROUNDWATER IS ENCOUNTERED, THE ENGINEER SHALL BE NOTIFIED IMMEDIATELY TO DETERMINE IF THE ADDITION OF AN UNDERDRAIN MAY BE REQUIRED.
10. THE CONTRACTOR SHALL NOT USE LARGE OR HEAVY CONSTRUCTION EQUIPMENT WITHIN 5' OF THE RETAINING WALLS OR NEW FOUNDATION WALLS. HAND OPERATED COMPACTING EQUIPMENT SHALL BE USED WITHIN 5' OF THE WALL FACE.
11. ALTERNATE WALL DESIGNS MUST BE SEALED BY A NEW YORK STATE LICENSED PROFESSIONAL ENGINEER THE MINIMUM FACTORS OF SAFETY FOR SLIDING AND OVERTURNING SHALL BE 2.0.
12. ALTERNATE WALL DESIGNS MUST BE SEALED BY A NEW YORK STATE LICENSED PROFESSIONAL ENGINEER THE MINIMUM FACTORS OF SAFETY FOR SLIDING AND OVERTURNING SHALL BE 2.0.

WATERMAIN NOTES

I. DISTRIBUTION SYSTEM - WATERMAIN

A. GENERAL

THE CONTRACTOR SHALL PERFORM THE NECESSARY EXCAVATION, BACKFILLING, CLEARING, GRUBBING, SHEETING, SHORING, DO ALL SHAPING OF TRENCHES, PUMPING AND BAILING, LAYING AND JOINING OF ALL PIPES, PROTECT AND SUPPORT EXISTING STRUCTURES AND REPAIR THEM, IF DAMAGED, AND ALL ELSE NECESSARY TO COMPLETE THE WORK.

THE CONTRACTOR SHALL FURNISH ALL MATERIALS, EQUIPMENT, LABOR, AND TOOLS NECESSARY TO COMPLETE THE WORK IN A SAFE, NEAT, AND WORKMANLIKE MANNER.

B. SITE AND ACCESS CLEARING (WITHIN EASEMENTS)

THE CONTRACTOR SHALL CONFINE ALL CLEARING OPERATIONS TO WITHIN THE IMMEDIATE AREAS THAT ARE ESSENTIAL FOR CONSTRUCTION OF THE WORK.

C. STOCKPILING OF SUITABLE BACKFILL MATERIAL

THE CONTRACTOR SHALL BE PREPARED WHEN EXCAVATING THE TRENCH TO SEPARATE SUITABLE BACKFILL MATERIAL FROM UNSUITABLE MATERIAL FOR USE AS BACKFILL ADJACENT TO THE PIPE.

D. PROTECTION OF EXISTING STRUCTURES AND UTILITIES

SPECIAL PRECAUTIONS SHALL BE TAKEN BY THE CONTRACTOR TO PROTECT OVERHEAD POWER LINES, WATERMAINS, GAS MAINS, ELECTRIC AND TELEPHONE CONDUITS, STORM AND SANITARY SEWERS, CULVERTS, BUILDINGS AND OTHER EXISTING STRUCTURES IN AND NEAR THE EXCAVATION. IN ALL CASES, WHETHER UNDERGROUND STRUCTURES HAVE OR HAVE NOT BEEN DELINEATED, THE TOWN ENGINEER, WATER SUPERINTENDENT, OR AUTHORIZED REPRESENTATIVE ACCEPTS NO RESPONSIBILITY FOR THEIR LOCATION. "UNDERGROUND UTILITIES" LOCATES EXISTING UNDERGROUND UTILITIES FREE OF CHARGE. THE PHONE NUMBER IS 1-800-245-2828.

GUTTERS, SEWERS, DRAINS AND DITCHES SHALL BE KEPT OPEN AT ALL TIMES FOR SURFACE DRAINAGE. NO DAMMING OR PONDING OF WATER IN GUTTERS OR OTHER WATERWAYS WILL BE PERMITTED EXCEPT WHERE STREAM CROSSINGS ARE NECESSARY AND THEN ONLY TO AN EXTENT WHICH THE TOWN ENGINEER, WATER SUPERINTENDENT, OR AUTHORIZED REPRESENTATIVE SHALL CONSIDER NECESSARY. THE CONTRACTOR SHALL NOT DIRECT ANY FLOW OF WATER ACROSS OR OVER PAVEMENTS EXCEPT THROUGH APPROVED PIPES OR PROPERLY CONSTRUCTED TROUGHS OF SUCH SIZES AND LENGTHS AS MAY BE REQUIRED, AND PLACE THE SAME AS DIRECTED. THE GRADING IN THE VICINITY OF TRENCHES SHALL BE CONTROLLED SO THAT THE GROUND SURFACE IS PROPERLY PITCHED TO PREVENT WATER RUNNING IN THE TRENCHING. THE CONTRACTOR SHALL NOT COMMENCE OPERATIONS INVOLVING ANY PUBLIC UTILITY BEFORE HAVING GIVEN WRITTEN NOTICE TO THE COMPANY OR OWNER, OR ITS AGENTS, AND SHALL COOPERATE WITH THE COMPANY'S OR OWNER'S FORCES IN PROTECTING AND PREVENTING DAMAGE TO THE PROPERTY.

THE CONTRACTOR WILL, AT HIS OWN EXPENSE, BE RESPONSIBLE FOR DIRECT OR INDIRECT DAMAGE THAT MAY BE DONE TO ANY UTILITY OR STRUCTURE IN THE PROSECUTION OF HIS WORK. THE LIABILITY OF THE CONTRACTOR IS ABSOLUTE AND IS NOT DEPENDENT UPON ANY QUESTIONS OF NEGLIGENCE ON HIS PART OR ON THE PART OF HIS AGENT, OR EMPLOYEES, AND THE NEGLECT OF THE TOWN ENGINEER, WATER SUPERINTENDENT, OR AUTHORIZED REPRESENTATIVE TO DIRECT THE CONTRACTOR TO TAKE ANY PARTICULAR PRECAUTION OR TO REFRAIN FROM DOING SUCH DAMAGE.

SHOULD THE POSITION OF ANY PIPE, CONDUIT, POLE OR OTHER STRUCTURES, ABOVE OR BELOW THE GROUND, BE SUCH AS TO REQUIRE ITS REMOVAL, REALIGNMENT, OR CHANGE DUE TO WORK TO BE DONE, REALIGNMENT OR CHANGE WILL BE DONE BY OR UNDER SUPERVISION OF THE OWNER OF THE OBSTRUCTIONS. THE CONTRACTOR SHALL UNCOVER AND SUSTAIN THE STRUCTURES, AFTER SUCH REALIGNMENT OR CHANGE.

THE CONTACTOR SHALL NOT INTERFERE WITH ANY PERSONS, OR WITH THE OWNER IN PROTECTING, REMOVING, CHANGING OR REPLACING THEIR PIPES, CONDUITS, POLES OR OTHER STRUCTURES; BUT HE SHALL SUFFER SAID PERSONS OR THE OWNER TO TAKE ALL SUCH MEASURES AS THEY MAY DEEM NECESSARY OR ADVISABLE FOR THE PURPOSE AFORESAID, AND THE CONTRACTOR SHALL THEREBY BE IN NO WAY RELIEVED OF ANY OF HIS RESPONSIBILITIES.

THE CONTRACTOR SHALL MAKE ALL NECESSARY ARRANGEMENTS WITH THE OWNER OF THE RESPECTIVE UTILITY PRIOR TO RELOCATION OR INTERRUPTION OF SERVICE. ALL WORK NECESSARY FOR THE RELOCATION SHALL BE PERFORMED BY THE CONTRACTOR, OR BY THE OWNER AT THE OWNER'S OPTION, AND TO THE SATISFACTION OF THE OWNER. WHERE SERVICE IS INTERRUPTED, THE CONTRACTOR SHALL COOPERATE IN RESTORING SERVICE PROMPTLY. ALL CHARGES FOR DAMAGES DONE TO UTILITIES SHALL BE PAID BY THE CONTRACTOR.

E. CONSTRUCTION OF ROAD RIGHT-OF-WAY

CONSTRUCTION IN THE ROAD RIGHT-OF-WAY SHALL AT ALL TIMES BE PERFORMED WITH MINIMUM DISTURBANCE TO TRAFFIC WITH SUFFICIENT BARRICADES AND DIRECTION. DETOURS CAN BE INSTITUTED WITH APPROVAL OF THE TOWN ENGINEER, WATER SUPERINTENDENT OR AUTHORIZED REPRESENTATIVE OR STATE, COUNTY, OR LOCAL AUTHORITIES. PAVEMENT SHALL BE CUT PRIOR TO REMOVAL. HOLES AND SETTLEMENTS IN THE TRENCHES SHALL BE IMMEDIATELY FILLED TO THE ORIGINAL GRADE ELEVATION WITH THE SPECIFIED MATERIALS.

F. EXCAVATION AND PREPARATION OF TRENCH

THE CONTRACTOR SHALL PROCEED WITH CAUTION IN THE EXCAVATION AND PREPARATION OF THE TRENCH SO THAT THE EXACT LOCATION OF UNDERGROUND STRUCTURES, BOTH KNOWN AND UNKNOWN, MAY BE DETERMINED. THE TRENCH SHALL BE EXCAVATED SO THAT THE PIPE CAN BE LAID TO THE ALIGNMENT AND DEPTH REQUIRED. MINIMUM DEPTH OF COVER FROM SURFACE OF GROUND TO TOP OF PIPE BARREL SHALL BE FOUR FEET (4'). NO TRENCH SHALL BE EXCAVATED MORE THAN FIVE HUNDRED LINEAL FEET (600 LF) IN ADVANCE OF PIPE LAYING, UNLESS AUTHORIZED BY THE TOWN ENGINEER, WATER SUPERINTENDENT, OR AUTHORIZED REPRESENTATIVE. THE TRENCH SHALL BE SO BRACED AND DRAINED THAT THE WORKMEN MAY WORK THEREIN SAFELY AND EFFICIENTLY. IT IS ESSENTIAL THAT THE DISCHARGE OF THE TRENCH DEWATERING PUMPS BE CONDUCTED TO NATURAL DRAINAGE CHANNELS OR DRAINS, AS IN ACCORDANCE WITH OSHA REQUIREMENTS.

THE WIDTH OF THE TRENCH SHALL BE OF ADEQUATE SIZE TO PERMIT THE PIPE TO BE LAID AND JOINTED PROPERLY, BUT SHALL NOT EXCEED THE SUM OF TWENTY-FOUR INCHES(24") PLUS THE PIPE OUTSIDE DIAMETER, AND THE BACKFILL TO BE PLACED AND COMPACTED AS SPECIFIED.

LEDGE ROCK, BOULDERS AND LARGE STONES SHALL BE REMOVED TO PROVIDE A CLEARANCE OF AT LEAST SIX INCHES (6") BELOW AND ON EACH SIDE OF ALL PIPES AND FITTINGS.

THE TRENCH SHALL BE EXCAVATED TO THE DEPTH REQUIRED SO AS TO PROVIDE A UNIFORM AND CONTINUOUS BEARING AND SUPPORT FOR THE PIPE ON SOLID AND UNDISTURBED GROUND AT EVERY POINT. WHERE THE BOTTOM OF THE TRENCH AT A SUBGRADE IS FOUND TO BE UNSTABLE, OR TO INCLUDE ASHES, CINDERS, ALL TYPES OF REFUSE, VEGETABLE OR OTHER ORGANIC MATERIAL OR LARGE PICES OF FRAGMENTS OR INORGANIC MATERIAL WHICH IN THE JUDGEMENT OF THE TOWN ENGINEER, WATER SUPERINTENDENT, OR AUTHORIZED REPRESENTATIVE SHOULD BE REMOVED, THE CONTRACTOR SHALL EXCAVATE AND REMOVE SUCH UNSUITABLE MATERIAL TO THE WIDTH AND DEPTH ORDERED BY THE TOWN ENGINEER, WATER SUPERINTENDENT, OR AUTHORIZED REPRESENTATIVE.

ANY PART OF THE BOTTOM OF THE TRENCH EXCAVATED BELOW THE SPECIFIED GRADE SHALL BE CORRECTED WITH APPROVED BEDDING MATERIAL, SUCH AS THOROUGHLY COMPACTED CRUSHED STONE, GRAVEL, OR CONCRETE AS DIRECTED BY THE TOWN ENGINEER, WATER SUPERINTENDENT, OR AUTHORIZED REPRESENTATIVE. THE FINISHED SUBGRADE SHALL BE PREPARED ACCURATELY BY MEANS OF HAND TOOLS.

GENERAL WATER MAIN NOTES:

1. ALL PROPOSED WATERMAIN MATERIALS, CONSTRUCTION AND INSTALLATION SHALL CONFORM TO ALL APPLICABLE RULES AND REGULATIONS OF THE TOWN OF OSSINING WATER DEPARTMENT AND THE WESTCHESTER COUNTY HEALTH DEPARTMENT STANDARDS AND SPECIFICATIONS.
2. THE RECORDS OF THE TOWN OF OSSINING INDICATE THAT THERE IS ADEQUATE WATER PRESSURE AND CAPACITY AS REQUIRED TO SERVE THIS PROJECT.
3. ALL BACKFLOW PREVENTION DEVICES ASSOCIATED WITH THE FIRE AND DOMESTIC SERVICES FOR EACH OF THE PROPOSED OFFICE SPACES IN THE TYPE "B" UNITS SHALL BE LOCATED INTERNAL TO THE BUILDING AND SHALL REQUIRE SEPARATE APPROVAL BY THE WESTCHESTER COUNTY DEPARTMENT OF HEALTH.
4. ALL FIRE AND DOMESTIC SERVICE CONNECTIONS FROM THE PROPOSED WATER MAIN SHALL BE INSTALLED WITH WET TAPS AFTER THE CONTRACTOR HAS INSTALLED THE MAIN AND IT HAS BEEN APPROVED BY THE TOWN OF OSSINING WATER DEPARTMENT AND THE WESTCHESTER COUNTY DEPARTMENT OF HEALTH.
5. THE CONTRACTOR IS ADVISED THAT BEFORE HE CONNECTS TO THE EXISTING WATER SYSTEM, HE MUST ADVISE AND COORDINATE HIS OPERATIONS WITH THE TOWN OF OSSINING WATER DEPARTMENT'S SUPERINTENDENT. MEANS AND METHODS USED TO CONNECT TO THE EXISTING SERVICE SHALL BE APPROVED BY THE TOWN AND SHALL INCLUDE BUT NOT BE LIMITED TO WET TAPS OR OTHERWISE.
6. THE CONTRACTOR IS TO MAINTAIN CONSTANT FLOW AND PRESSURE IN ALL WATER MAINS AT ALL TIMES. IF THE NEED SHOULD ARISE THAT WATER SERVICE IS TO BE INTERRUPTED FOR A SHORT PERIOD, IT MUST BE COORDINATED WITH AND APPROVED BY THE ENGINEER AND THE TOWN OF OSSINING SUPERINTENDENT OF WATER.
7. WATER MAINS CROSSING HOUSE SEWERS, STORM SEWERS OR SANITARY SEWERS SHALL BE LAID TO PROVIDE A VERTICAL SEPARATION OF A MINIMUM OF 18" BETWEEN THE BOTTOM OF WATER MAIN AND TOP OF SEWER.
8. WATER MAINS PASSING UNDER HOUSE SEWERS, IN ADDITION, SHALL BE PROTECTED BY PROVIDING A VERTICAL SEPARATION OF 18" MINIMUM FROM THE BOTTOM OF THE SEWER TO THE TOP OF THE WATER MAIN AND ADEQUATE STRUCTURAL SUPPORT FOR THE SEWER TO PREVENT EXCESSIVE DEFLECTION OF THE JOINTS AND THE SEWER SETTling AND BREAKING THE WATER MAIN. IN ADDITION THE LENGTH OF WATER PIPE IS TO BE CENTERED AT THE POINT OF CROSSING SO THAT THE JOINTS WILL BE EQUIDISTANT AND AS FAR AS POSSIBLE FROM THE SEWER. NO WATER MAIN SHALL PASS THROUGH OR COME IN CONTACT WITH ANY PART OF A SEWER OR SEWER MANHOLE.
9. THE COVER OVER THE TOP OF THE WATER MAIN SHALL BE A MINIMUM OF 4 FEET TO A MAXIMUM OF 5.5 FT.
10. WATER MAINS SHALL BE CLASS 54 DUCTILE IRON PIPES (DIP) TYTON JOINT TYPE AND FITTINGS SHALL BE FACTORY CEMENT LINED CLASS 54. ALL FITTINGS SHALL HAVE MECHANICAL JOINTS AND SHALL BE PRESSURE RATED AT 250 PSI. ALL NECESSARY JOINT MATERIALS SHALL BE FURNISHED. WATER MAINS SHALL BE INSTALLED IN ACCORDANCE WITH AWWA STANDARDS, LATEST REVISION.
11. ALL GATE VALVES SHALL BE MUELLER RESILIENT WEDGE (TURN LEFT OPEN) TYPE AND SHALL MEET AWWA STANDARDS, LATEST REVISION.
12. ALL SERVICE CONNECTIONS AND SMALL DIAMETER EXTENSIONS SHALL CONFORM TO AWWA C-151.
13. RETAINER GLANDS AND CONCRETE THRUST BLOCKS OR RODS SHALL BE USED AT ALL LOCATIONS WHERE RESTRAINTS EXIST.
14. INSTALLATION AND TESTING OF THE WATER MAIN SHALL BE INSPECTED BY THE WESTCHESTER COUNTY DEPARTMENT OF HEALTH. THE CONTRACTOR SHALL PROVIDE THE HEALTH DEPARTMENT A MINIMUM 48 HOURS NOTICE PRIOR TO ANY PRESSURE/LEAKAGE TESTS AND/OR DISINFECTION AND BACTERIOLOGICAL TESTS PERFORMED ON THE PROPOSED WATER MAIN. THE RESULTS OF THE ABOVE TESTS MUST BE ACCEPTED BY THE WCHD PRIOR TO USE OF THE MAIN.
15. ASBUILT DRAWINGS SHALL SHOW DIMENSIONS BETWEEN ALL VALVE TURNING NUTS AND FINISH GRADE.
16. INSTALLATION, DISINFECTION AND TESTING TO BE WITNESSED AND CERTIFIED BY A LICENSED PROFESSIONAL ENGINEER OR TOWN OF OSSINING ENGINEER.
17. ALL HYDRANTS AND VALVES SHALL BE AS MANUFACTURED BY THE MUELLER COMPANY.
18. THE FINAL LOCATIONS OF FIRE HYDRANTS AND SIAMESE CONNECTIONS SHALL BE DETERMINED BY AND COORDINATED WITH THE TOWN OF OSSINING FIRE DEPARTMENT.
19. IF, DURING CONSTRUCTION, IT IS FOUND THAT THE REQUIRED SEPARATION OF WATER MAINS, SANITARY SEWERS, STORM SEWERS, AND BUILDING SEWERS CANNOT BE MET, THE DEVELOPER OR HIS AUTHORIZED REPRESENTATIVE SHALL CONTACT THE WESTCHESTER COUNTY DEPARTMENT OF HEALTH. APPROVAL BY THE WCHD IS REQUIRED PRIOR TO ANY FIELD CHANGES THAT WILL AFFECT MINIMUM WATER/SEWER SEPARATION DISTANCES.
20. ALL TYPES OF INSTALLED PIPE SHALL BE PRESSURE TESTED AND LEAKAGE TESTED IN ACCORDANCE WITH THE LATEST EDITION OF AWWA STANDARD C-600.
21. ALL NEW, CLEANED OR REPAIRED WATER MAINS SHALL BE DISINFECTED AND BACTERIOLOGICAL TESTING PERFORMED IN ACCORDANCE WITH THE LATEST EDITION OF AWWA STANDARD C-651-05 (EXCEPT FOR SECTION 4.4.2 WHICH IS NOT APPROVABLE), THE SPECIFICATIONS INCLUDE DETAILED PROCEDURES FOR THE ADEQUATE FLUSHING, DISINFECTION, AND MICRO- BIOLOGICAL TESTING OF ALL WATER MAINS.
22. ROAD OPENINGS SHALL BE DONE IN ACCORDANCE WITH CONDITIONS OF PERMIT, AND COORDINATED WITH THE TOWN OF OSSINING.



PROJECT # 15-18

Site Design Consultants

Civil Engineers • Land Planners
251-F Underhill Avenue, Yorktown Heights, NY 10598
(914) 962-4488 - Fax: (914) 962-7386
www.sitedesignconsultants.com

Engineer:

Joseph C. Rina, P.E.
NYS Lic. No. 64431

Revisions:		No.	Date	Comments
1	11/9/15	Town Comments		
2	12/7/15	Town Comments		
3	1/25/16	Town Comments		
4	5/7/16	Town Comments		

SCALE: NTS	DRAWN BY: TK	DATE: 9/25/15
---------------	-----------------	------------------

NOTES

SITE PLAN
PREPARED FOR

PARTH KNOLLS LLC.

87 HAWKES AVENUE

Town of Ossining

Westchester County, NY

Sheet

G-1

Construction Sequence

Recommended Sequence of Construction

Use of erosion and sediment control structures and practices are important for maintaining site stability under runoff and during daily construction activities. The Construction Sequence should be staged with erosion and sediment controls, as follows, with all controls in place and implemented prior to respective infrastructure construction. As construction proceeds, the controls should be monitored, maintained and replaced as needed. Additional controls may be required as needed to address unforeseen situations.

Refer to The Construction Drawings for all plans and details which relate to the Construction Sequence. This Sequence should be followed in conjunction with all Plans, Notes, and the Stormwater Pollution Prevention Plan. Prior to the commencement of work, the Owner and General Contractor shall read and understand the Sequence for Construction. The Sequence shall be discussed at the time of the Pre-construction Meeting.

During construction of the project, the Contractor is responsible to coordinate all required inspections with various agencies and the Project Engineer.

Construction Sequence

General Sequence: The general sequence applies to the start of all Phases of the project. The requirements in such shall be applied as appropriate in that phase and shall be assumed in place prior to the start of the work outlined in the sequence for each Phase.

- Prior to the beginning of any site work the major features of the construction must be field staked by a licensed surveyor. These include the building, limits of disturbance, utility lines, and Stormwater practices.
- Prior to the start of the project, an on-site pre-construction meeting will be held. This will be attended by the Project Owner, the Operator responsible for complying with the approved construction drawings including the Erosion and Sediment Control (E&SC) Plan and Details, the Design Engineer, the Engineer responsible for E&SC monitoring during construction, Town representatives from the Engineering Department and Code Enforcement.
- Cut and clear trees within the phase limits as necessary for the areas to be disturbed. Install tree protective measure at marked locations on E&SC Plan.
- Install all temporary erosion control measures as shown on the Erosion and Sediment Control Plan for the project's immediate disturbance areas. This shall include, but not limited to silt fence, stabilized construction entrances, diversion swales, sediment traps, construction fence, etc. This sequence must be followed to insure proper implementation of the Erosion and Sediment Control Plan (E&SC) and Stormwater Pollution Prevention Plan (SWPPP).
- Timbered trees and woodchips shall be temporarily stored in the stockpile and/or staging area if necessary before being removed off-site. Woodchips may be used for mulch to stabilize disturbed areas. Woodchip mulch shall be applied at a minimum rate of 500 lbs. per 1000 SF (2" thick minimum).
- Remove existing vegetative cover, cut and clear trees, grub, remove stumps and other surface features in the limit of construction only. Any disturbance that results from tree clearing and grubbing shall be immediately stabilized with woodchips mulch, hydro-mulch, or straw and seed. Timbered trees, wood chips, and stumps shall be removed off-site unless otherwise directed. As stated woodchips may be stockpiled for use as stabilized ground cover. Demolish and/or remove existing features, i.e.: fence, concrete slab, asphalt etc., and dispose of or stockpile as required by the Owner. All construction debris shall be properly disposed of in accordance with all Federal, State, and Local requirements.

Standard Sequence Notes for Phases I & II

- Begin rough grading the building pads for the Buildings. Begin moving the fill towards the location designated for each phase. Cut and fill of a certain phase shall meet the next phase boundary at a maximum slope of 2V:1H. For previous phases where grading is complete match to finish grade elevations. All compaction requirements shall be met within the fill sections. (This work shall include the commencement of the retaining walls around the proposed building construction.) Upon completion of the grading, temporary seed or hydro-mulch the embankment and install erosion control blankets as shown on the Plans along the northern perimeter of the fill section. During building and site construction, maintain and re-establish as required, erosion control and stabilization measures as required by the Site Plan and Details. Areas which are to remain undisturbed for more than seven (7) days shall be stabilized with temporary seeding or mulch.
- A licensed surveyor must define the building locations.
- Install or check condition of all temporary Erosion Control Measures as shown on the Erosion and Sediment Control Plan.
- Begin preparation of the building site and excavation of the building foundation as well as construction of all retaining walls. Areas in which final grade is achieved shall be immediately stabilized with permanent vegetative cover. Permanent slopes of 3:1 or greater shall receive erosion blankets.
- Begin construction of the foundation. Upon completion and after proper curing time is achieved, backfill the foundation and bring site to rough grade. Areas which are to remain undisturbed for more than seven (7) days shall be stabilized with temporary seeding or mulch.

The following phases are the general order for construction of the project and may be modified after approved by the supervising Engineer. The phasing is meant to minimize the amount of open disturbance. Under no circumstances shall multiple phases amounting to five (5) acres or greater be disturbed during the same period of time. In the event greater disturbance is necessary outside of the Phase limits shown on the Erosion and Sediment Control Plan, the Contractor shall coordinate with the Engineer of Record, and Municipality for an on-site meeting to discuss the alternative approach to the construction.

Phase I: Construction of Building 1 - The intent of this Phase is to complete the construction of Building 1, the driveways for the parking area in front of the building, the parking garage, the parking area in the rear of the building, and the landscape and hardscape included in the Phase limits shown on the Erosion and Sediment Control Plan. Additionally, any proposed drainage measures shown within the phase limits shall be put in place, but not connected until the final stabilization of Phase 2.

- The Surveyor shall stake-out the proposed driveway centerlines, limits of cut and fill and the location of the temporary sediment traps.
- Implement the General Sequence Notes 1 through 6 where applicable prior to continuing this Phase.
- Once the tree removal operation is complete strip the topsoil within the Phase I boundary and place excavated topsoil within the identified stockpile locations. Any soils so deemed by the Design or Monitoring Engineer shall be stockpiled for future use as landscaped area topsoil. Contractor shall take every precaution feasible to reduce the amount of disturbed/exposed soils during construction.
- Construct and install temporary sediment traps along the proposed access drive and rear parking area. Install the temporary filtered outlet pipe. Any disturbed area that will not be further disturbed within seven (7) days shall be immediately stabilized with woodchips, hydro-mulch, or straw and seed.
- Prior to starting the work install all erosion and sediment controls including the installation of the stabilized construction entrance and sediment trap.
- Begin the removal of the existing driveway. Material shall be properly disposed of.
- Begin rough grading of driveways within phase limits and adjacent areas. Slops in excess of 3H:1V shall not be left exposed and must be stabilized.
- Begin excavation of the building foundation for the Building and adjacent areas.

Refer to Notes 7 through 12 under the General Sequence.

- Cut material shall first be moved to the fill locations required to complete the access drive and staging area and bring the area up to final grades. Excess material to be used toward infilling in Phase II shall be stockpiled. Blasted rock that is not suitable to remain on site shall be hauled away and properly disposed of. An area has been provided for the stockpiling of removed soil and rock which is to be removed from the site as well as a cuing area for trucks awaiting loading.
- Proceed with the construction of Building 1. This includes the building structure itself, retaining walls, and rough grades. At any point during this begin installation of the utilities including the water and sewer connections, drainage and power utilities.
- Stake-out the location of utilities and utility structures within this Phase. Temporarily relocate the staging area at the western end of the site. Begin installation of subsurface infiltration and detention chambers within Phase I limits.
- When the subsurface units are installed, the upstream drainage structure shall be blocked so as to not allow sediment laden water from reaching the subsurface chambers.
- Backfill as installation is complete and stabilize the area. If trenches are to be left open, place excavated material on the up-slope sides of the trench and protect and stabilize if it is to remain open for an extended period of seven (7) days or more.
- Upon completion of the subsurface chambers, begin installation of proposed bypass and outlet structures. Install storm sewer piping, catch basins and manholes, working downstream to upstream. During the installation of catch basins, install inlet protection and water bar as per E&SC Plan to assure that sediment laden water will not enter the storm system. Once the final grade above the system is achieved, put into place the final topsoil cover, seed mix, and erosion control blanket, or hydro-mulch. Refer to the Landscape Plan for the seed mix requirements.
- Once the infiltrator system has been installed, grade and install the base course for the driveways and parking areas. Re-establish the staging area for the construction site trailer and parking.

Note: No stormwater is permitted to enter the infiltration system from the upstream conveyance system and shall be blocked until the completion and stabilization of all Phases tributary to the basin. An area shall be considered to have achieved final stabilization when it has a minimum uniform 80% perennial vegetative cover or other permanent non-vegetative cover with a density sufficient to resist accelerated surface erosion and subsurface characteristics sufficient to resist sliding and other movements.

- Complete construction of the building and remaining retaining walls within Phase limits.
- Stake out and install curbing as per Plan. Once curbing is completed around catch basins, re-install inlet protection within catch basins. As curbing is complete, backfill with topsoil. Areas that are filled with topsoil are to be raked, seeded, and hay mulched.
- Upon completion of the majority of the infrastructure in that phase, install pavement binder course to the thickness and elevation as per the Construction Plans.
- As each Phase is at the completion stage install final asphalt surface.
- Install hardscape such as patios, walks steps etc., and final vegetation including sod and landscaping. Refer to Landscape Plans for location and identification of ground cover and plantings. Clear site of debris and all unwanted materials. Disposal shall be in accordance with all Federal, State, and Local requirements.
- During the Final Phase of building construction, finish grade, topsoil, rake, and seed all areas as required. Where required or recommended, hydro-mulch or install erosion control blankets.
- Upon completion of this Phase, the Contractor shall be required to stabilize disturbed soils in the event the disturbed area will remain not worked for greater than seven (7) days, at the direction of the Engineer of Record or permitting entity Inspector, and when significant precipitation is in the immediate forecast. All disturbed areas shall be temporarily stabilized with hydro-mulch or where appropriate woodchips. It is recommended that any grading that is at the finish stage will receive no further disturbance and that permanent stabilization such as topsoil, seed, mulching or blankets as per the Plan be installed. **The next Phase cannot commence until these steps have been completed.**

Phase II: Construction of Building 2 - The intent of this Phase is to complete the construction of Building 2, the main access driveway and parking for the building, the pool and recreation area located behind the building and the landscape and hardscape included in the Phase limits shown on the Erosion and Sediment Control Plan. Additionally, the any proposed drainage measures shown within the phase limits shall be put in place, but not connected until the final stabilization of Phase II.

- The Surveyor shall stake-out the proposed building, drive and parking access, pool and recreation area, limits of cut and fill, and the location of the temporary sediment traps.
- Strip topsoil within the Phase II boundary and place excavated topsoil within the identified stockpile locations. Any soils so deemed by the Design or Monitoring Engineer shall be stockpiled for future use as landscaped area topsoil. Contractor shall take every precaution feasible to reduce the amount of disturbed/exposed soils during construction.
- Begin excavation for the building foundation for the building and adjacent areas. **Refer to Notes 7 through 12 under the General Sequence.**
- Begin rough grading main access driveway and parking area for building 2. Connections to building 1 driveway shall be made at subgrade elevations.
- Cut material shall first be moved to the fill locations required to complete and bring the areas up to final grades. Excess material to be removed from the site.
- Stake-out the location of utilities and utility structures within this Phase. Install storm sewer piping, catch basins and manholes, working downstream to upstream. During the installation of catch basins, install inlet protection and water bar as per E&SC Plan to assure that sediment-laden water will not enter the storm system. Make connections to other phase utilities as necessary.
- Complete construction of the building and remaining retaining walls within Phase limits. Utilities must be installed and completed before the construction of the retaining walls.
- Stake out and install curbing as per Plan. Once curbing is completed around catch basins, re-install inlet protection within catch basins. As curbing is complete, backfill with topsoil. Areas that are filled with topsoil are to be raked, seeded, and hay mulched.
- Upon completion of the majority of the infrastructure in that phase, install pavement binder course to the thickness and elevation as per the Construction Plans.
- As the Phase is at the completion stage install final asphalt surface.
- Install hardscape such as patios, walks steps etc., and final vegetation including sod and landscaping. Refer to Landscape Plans for location and identification of ground cover and plantings. Clear site of debris and all unwanted materials. Disposal shall be in accordance with all Federal, State, and Local requirements.
- During the Final Phase of building construction, once final grade is achieved, place final topsoil cover, begin placement of seed mix and erosion control blanket, or hydro-mulch. Refer to the Landscape Plan for the seed mix requirements.

Final Site Stabilization and Completion of New Construction:

- Upon completion of all Phases, the site shall be inspected by the Supervising Engineer and Town Inspector to determine completion of all work and permanent stabilization of the site.
- Any areas deemed incomplete or not properly stabilized shall be done so to the satisfaction to the Supervising Engineer and Town Inspector.
- Once the site is deemed adequately stable the temporary erosion and sediment control measures can be removed including the sediment traps. The area where the sediment trap was located shall be filled, top soiled, seeded and mulched in accordance with the specifications within this plan. At that time if deemed appropriate drainage structures upstream from the subsurface stormwater management systems shall be cleaned of sediment and debris. They can then be unblocked to allow for flow of collected surface runoff.

Contact information during and after construction:

Anthony Beldotti
APB Management
500 Executive Blvd. #203
Ossining, NY 10562
914-762-7898

GENERAL EROSION CONTROL NOTES:

- CONTRACTOR SHALL BE RESPONSIBLE FOR COMPLIANCE WITH ALL SEDIMENT AND EROSION CONTROL PRACTICES. THE SEDIMENT AND EROSION CONTROL PRACTICES ARE TO BE INSTALLED PRIOR TO ANY MAJOR SOIL DISTURBANCES, AND MAINTAINED UNTIL PERMANENT PROTECTION IS ESTABLISHED. ROAD SURFACE FLOWS FROM THE SITE SHOULD BE DISSIPATED WITH TRACKING PAD OR APPROPRIATE MEASURES DURING ADJACENT ROAD SHOULDER REGRADING. CONTRACTOR IS RESPONSIBLE FOR THE INSTALLATION AND MAINTENANCE OF ALL SOIL EROSION AND SEDIMENTATION CONTROL DEVICES THROUGHOUT THE COURSE OF CONSTRUCTION.
- CATCH BASIN INLET PROTECTION MUST BE INSTALLED AND OPERATING AT ALL TIMES UNTIL TRIBUTARY AREAS HAVE BEEN STABILIZED. WHEN POSSIBLE FLOWS SHOULD BE STABILIZED BEFORE REACHING INLET PROTECTION STRUCTURE. TIMELY MAINTENANCE OF SEDIMENT CONTROL STRUCTURES IS THE RESPONSIBILITY OF THE CONTRACTOR.
- ALL STRUCTURES SHALL BE MAINTAINED IN GOOD WORKING ORDER AT ALL TIMES. THE SEDIMENT LEVEL IN ALL SEDIMENT TRAPS SHALL BE CLOSELY MONITORED AND SEDIMENT REMOVED PROMPTLY WHEN MAXIMUM LEVELS ARE REACHED OR AS ORDERED BY THE ENGINEER. ALL SEDIMENT CONTROL STRUCTURES SHALL BE INSPECTED ON A REGULAR BASIS, AND AFTER EACH HEAVY RAIN TO INSURE PROPER OPERATION AS DESIGNED. AN INSPECTION SCHEDULE SHALL BE SET FORTH PRIOR TO THE START OF CONSTRUCTION.
- THE LOCATIONS AND THE INSTALLATION TIMES OF THE SEDIMENT CAPTURING STANDARDS SHALL BE AS SPECIFIED IN THESE PLANS, AS ORDERED BY THE ENGINEER, AND IN ACCORDANCE WITH THE LATEST EDITION OF THE "NEW YORK STANDARDS AND SPECIFICATIONS FOR EROSION AND SEDIMENT CONTROL" (NYSSESC).
- ALL TOPSOIL SHALL BE PLACED IN A STABILIZED STOCKPILE FOR REUSE ON THE SITE. ALL STOCKPILE MATERIAL REQUIRED FOR FINAL GRADING AND STORED ON SITE SHALL BE TEMPORARILY SEEDED AND MULCHED WITHIN 7 DAYS. REFER TO SOIL STOCKPILE DETAILS.
- ANY DISTURBED AREAS THAT WILL BE LEFT EXPOSED MORE THAN 7 DAYS AND NOT SUBJECT TO CONSTRUCTION TRAFFIC, SHALL IMMEDIATELY RECEIVE TEMPORARY SEEDING. MULCH SHALL BE USED IF THE SEASON PREVENTS THE ESTABLISHMENT OF A TEMPORARY COVER. DISTURBED AREAS SHALL NOT BE LIMED AND FERTILIZED PRIOR TO TEMPORARY SEEDING.
- ALL DISTURBED AREAS WITHIN 500 FEET OF AN INHABITED DWELLING SHALL BE WETTED AS NECESSARY TO PROVIDE DUST CONTROL.
- THE CONTRACTOR SHALL KEEP THE ROADWAYS WITHIN THE PROJECT CLEAR OF SOIL AND DEBRIS AND IS RESPONSIBLE FOR ANY STREET CLEANING NECESSARY DURING THE COURSE OF THE PROJECT.
- SEDIMENT AND EROSION CONTROL STRUCTURES SHALL BE REMOVED AND THE AREA STABILIZED WHEN THE DRAINAGE AREA HAS BEEN PROPERLY STABILIZED BY PERMANENT MEASURES.
- ALL SEDIMENT AND EROSION CONTROL MEASURES SHALL BE INSTALLED IN ACCORDANCE WITH CURRENT EDITION OF NYSSESC.
- ALL REGRADED AREAS MUST BE STABILIZED APPROPRIATELY PRIOR TO ANY ROCK BLASTING, CUTTING, AND/OR FILLING OF SOILS. SPECIAL CARE SHOULD BE TAKEN DURING CONSTRUCTION TO INSURE STABILITY DURING MAINTENANCE AND INTEGRITY OF CONTROL STRUCTURES.
- ANY SLOPES GRADED AT 3:1 OR GREATER SHALL BE STABILIZED WITH EROSION BLANKETS TO BE STAKED INTO PLACE IN ACCORDANCE WITH THE MANUFACTURES REQUIREMENTS. EROSION BLANKETS MAY ALSO BE REQUIRED AT THE DISCRETION OF TOWN OFFICIALS OR PROJECT ENGINEER. WHEN STABILIZED BLANKET IS UTILIZED FOR CHANNEL STABILIZATION, PLACE ALL OF THE VOLUME OF SEED MIX PRIOR TO LAYING NET, OR AS RECOMMENDED BY THE MANUFACTURER.
- TO PREVENT HEAVY CONSTRUCTION EQUIPMENT AND TRUCKS FROM TRACKING SOIL OFF-SITE, CONSTRUCT A PERVIOUS CRUSHED STONE PAD. LOCATE AND CONSTRUCT PADS AS DETAILED IN THESE PLANS.
- CONTRACTOR IS RESPONSIBLE FOR CONTROLLING DUST BY SPRINKLING EXPOSED SOIL AREAS PERIODICALLY WITH WATER AS REQUIRED. CONTRACTOR TO SUPPLY ALL EQUIPMENT AND WATER.
- CONTRACTOR SHALL BE RESPONSIBLE FOR CONSTRUCTION INSPECTIONS AS PER NYSDEC GP-0-15-002 AND TOWN OF OSSINING CODE.

MAINTENANCE OF TEMPORARY EROSION AND SEDIMENT CONTROL STRUCTURES:

N.Y.S.D.E.C. GP-0-15-002 EXPOSURE RESTRICTIONS - STATES THAT ANY EXPOSED EARTHWORK SHALL BE STABILIZED IN ACCORDANCE WITH THE GUIDELINES OF THIS PLAN.

- TREES AND VEGETATION SHALL BE PROTECTED AT ALL TIMES AS SHOWN ON THE DETAIL DRAWING AND AS DIRECTED BY THE ENGINEER.
- CARE SHOULD BE TAKEN SO AS NOT TO CHANNEL CONCENTRATED RUNOFF THROUGH THE AREAS OF CONSTRUCTION ACTIVITY ON THE SITE.
- FILL AND SITE DISTURBANCES SHOULD NOT BE CREATED WHICH CAUSES WATER TO POND OFF SITE OR ON ADJACENT PROPERTIES.
- RUNOFF FROM LAND DISTURBANCES SHALL NOT BE DISCHARGED OR HAVE THE POTENTIAL TO DISCHARGE OFF SITE WITHOUT FIRST BEING INTERCEPTED BY A CONTROL STRUCTURE, SUCH AS A SEDIMENT TRAP OR SILT FENCE. SEDIMENT SHALL BE REMOVED BEFORE EXCEEDING 50% OF THE RETENTION STRUCTURE'S CAPACITY.
- FOR FINISHED GRADING, ADEQUATE GRADE SHALL BE PROVIDED SO THAT WATER WILL NOT POND ON LAWNS FOR MORE THAN 24 HOURS AFTER RAINFALL, EXCEPT IN SWALE FLOW AREAS WHICH MAY DRAIN FOR AS LONG AS 48 HOURS AFTER RAINFALL.
- ALL SWALES AND OTHER AREAS OF CONCENTRATED FLOW SHALL BE PROPERLY STABILIZED WITH TEMPORARY CONTROL MEASURES TO PREVENT EROSION AND SEDIMENT TRAVEL. SURFACE FLOWS OVER CUT AND FILL AREAS SHALL BE STABILIZED AT ALL TIMES.
- ALL SITES SHALL BE STABILIZED WITH EROSION CONTROL MATERIALS WITHIN 7 DAYS OF FINAL GRADING.
- TEMPORARY SEDIMENT TRAPPING DEVICES SHALL BE REMOVED FROM THE SITE WITHIN 30 DAYS OF FINAL STABILIZATION.

MAINTENANCE SCHEDULE:

	DAILY	WEEKLY	MONTHLY	AFTER RAINFALL	NECESSARY TO MAINTAIN FUNCTION	AFTER APPROVAL OF INSPECTOR
SILT FENCE	----	-----	INSP.	INSP.	CLEAN/ REPLACE	REMOVE
WHEEL CLEANER	CLEAN	-----	-----	-----	REPLACE	REMOVE
INLET PROTECTION	----	INSP.	INSP.	CLEAN	REPLACE	REMOVE

MAINTENANCE OF PERMANENT CONTROL STRUCTURES DURING CONSTRUCTION:

The stormwater management system and outlet structure shall be inspected on a regular basis and after every rainfall event. Sediment build up shall be removed from the inlet protection regularly to insure detention capacity and proper drainage. Outlet structure shall be free of obstructions. All piping and drain inlets shall be free of obstruction. Any sediment build up shall be removed.

MAINTENANCE OF CONTROLS AFTER CONSTRUCTION:

Controls (including respective outlet structures) should be inspected periodically for the first few months after construction and on an annual basis thereafter. They should also be inspected after major storm events.

DEBRIS AND LITTER REMOVAL:

Twice a year, inspect outlet structure and drain inlets for accumulated debris. Also, remove any accumulations during each mowing operation.

STRUCTURAL REPAIR/REPLACEMENT:

Outlet structure must be inspected twice a year for evidence of structural damage and repaired immediately.

EROSION CONTROL:

Unstable areas tributary to the basin shall immediately be stabilized with vegetation or other appropriate erosion control measures.

SEDIMENT REMOVAL:

Sediment should be removed after it has reached a maximum depth of five inches above the stormwater management system floor.

TOPSOIL:

Existing topsoil will be removed and stored in piles sufficiently as to avoid mixing with other excavation. Stockpiles shall be surrounded by erosion control as outlined on these plans. The furnishing of new topsoil shall be of a better or equal to the following criteria (SS713.01 NYSDOT):

- The pH of the material shall be 5.5 to 7.6.
- The organic content shall not be less than 2% or more than 70%.

Gradation:	SIEVE SIZE	% PASSING BY WGT.
	2 INCH	100
	1 INCH	85 TO 100
	1/4 INCH	65 TO 100
	NO. 200 MESH	20 TO 80

PERMANENT VEGETATIVE COVER:

- Site preparation:
 - Install erosion control measures.
 - Scarify compacted soil areas.
 - Lime as required to ph 6.5.
 - Fertilize with 10-6-4 4 lbs/1,000 S.F.
 - Incorporate amendments into soil with disc harrow.
- Seed mixtures for use on swales and cut and fill areas.

MIXTURE		LBS./ACRE
ALT. A	KENTUCKY BLUE GRASS	20
	CREeping RED FESCUE	28
	RYE GRASS OR REDTOP	5
ALT. B	CREeping RED FESCUE	20
	REDTOP	2
	TALL FESCUE/SMOOTH BLOOMGRASS	20

- SEEDING
 - Prepare seed bed by raking to remove stones, twigs, roots and other foreign material.
 - Apply soil amendments and integrate into soil.
 - Apply seed uniformly by cyclone seeder culti-packer or hydro-seeder at rate indicated.
 - Stabilize seeded areas in drainage swales.
 - Irrigate to fully saturate soil layer, but not to dislodge planting soil.
 - Seed between April 1st and May 15th or August 15th and October 15th.
 - Seeding may occur May 15th and August 15th if adequate irrigation is provided.

TEMPORARY VEGETATIVE COVER:

SITE PREPARATION:

- Install erosion control measures.
- Scarify areas of compacted soil.
- Fertilize with 10-10-10 at 400/acre.
- Lime as required to ph 6.5.

SEED SPECIES:

MIXTURE	LBS./ACRE
Rapidly germinating annual ryegrass (or approved equal)	20
Perennial ryegrass	20
Cereal oats	36

SEEDING:

Same as permanent vegetative cover

OWNER / OPERATOR CERTIFICATION

"I certify under penalty of law that this document and all attachments were prepared under my direction or supervision in accordance with a system designed to assure that qualified personnel properly gathered and evaluated the information submitted. Based on my inquiry of the person or persons who manage the system, or those persons directly responsible for gathering the information, the information submitted is, to the best of my knowledge and belief, true, accurate, and complete. Further, I hereby certify that the SWPPP meets all Federal, State, and local erosion and sediment control requirements. I am aware that false statements made herein are punishable as a Class A misdemeanor pursuant to Section 210.45 of the Penal Law."

Name (please print): _____

Title: _____

Date: _____

Address: _____

Phone: _____

E-mail: _____

Signature: _____

CONTRACTOR CERTIFICATION STATEMENT

Certification Statement - All contractors and subcontractors as identified in a SWPPP, by the Owner or Operator, in accordance with Part III.A.5 of the SPDES General Permit for Stormwater Runoff from Construction Activity, GP-0-15-002, dated January 12, 2015, Page 10 of 40, shall sign a copy of the following Certification Statement before undertaking any construction activity at the Site identified in the SWPPP:

"I hereby certify that I understand and agree to comply with the terms and conditions of the SWPPP and agree to implement any corrective actions identified by the Qualified Inspector during a site inspection. I also understand that the Owner or Operator must comply with the terms and conditions of the New York State Pollutant Discharge Elimination System ("SPDES") General Permit for Stormwater Discharge from Construction Activities and that it is unlawful for any person to cause or contribute to a violation of water quality standards. Furthermore, I understand that certifying false, incorrect or inaccurate information is a violation of the referenced permit and the laws of the State of New York and could subject me to criminal, civil and/or administrative proceedings."

Individual Contractor: _____

Name and Title (please print): _____

Signature of Contractor: _____

Company / Contracting Firm: _____

Name of Company: _____


Address of Company: _____

Telephone Number / Cell Number: _____

Site Information: _____

Address of Site: _____

Today's Date: _____



Site Design Consultants

Civil Engineers • Land Planners

251-F Underhill Avenue, Yorktown Heights, NY 10598

(914) 962-4488 - Fax: (914) 962-7386

www.sitedesignconsultants.com

Engineer:
Joseph C. Rina, P.E.
NYS Lic. No. 64431




Revisions:	No.	Date	Comments
	1	11/9/15	Town Comments
	2	12/7/15	Town Comments
	3	1/25/16	Town Comments
	4	5/7/16	Town Comments

SCALE: N.T.S.	DRAWN BY: TK	DATE: 9/25/15
------------------	-----------------	------------------

E&SC NOTES

SITE PLAN
PREPARED FOR
PARTH KNOLLS LLC.
87 HAWKES AVENUE
Town Of Ossining
Westchester County, NY

Sheet
G-2






SLOPE INSTALLATION EARTH ANCHOR (EA) DETAIL

- Prepare soil before installing high-performance turf reinforcement mats (HP-TRMs), including any necessary application of lime, fertilizer, and seed.
- Begin at the top of the slope by anchoring the HP-TRMs in a 12" (30 cm) deep x 12" (30cm) wide trench with approximately 30" (76.2 cm) of HP-TRMs extended beyond the up-slope portion of the trench. Backfill and compact the trench after stapling. Fold remaining 30" (76.2 cm) portion of HP-TRMs back over compacted soil. Secure HP-TRMs with an alternating row of staples and anchors approximately 30" (76.2 cm) apart in the bottom of the trench.
- Roll the HP-TRMs (A) down or (B) horizontally across the slope. HP-TRMs will unroll with appropriate side against the soil surface. All HP-TRMs must be securely fastened to soil surface by placing staples/anchors in appropriate locations as shown in the staple pattern guide.
- The edges of parallel HP-TRMs must be stapled between earth anchors with approximately 4" (10 cm) overlap depending on the HP-TRM type. For curved sections, adjust the overlap edges of parallel HP-TRMs accordingly with a minimum of 4" (10 cm) overlap to accommodate transitional segments.

NOTE: In loose soil conditions, the use of staple or stake lengths greater than 6"(15cm) may be necessary to properly secure the HP-TRMs.

Site Design Consultants
Civil Engineers • Land Planners
251-F Underhill Avenue, Yorktown Heights, NY 10598
(914) 962-4488 - Fax: (914) 962-7386
www.sitedesignconsultants.com

PROJECT # 15-18



SLOPE INSTALLATION EARTH ANCHOR (EA) DETAIL

- Prepare soil before installing high-performance turf reinforcement mats (HP-TRMs), including any necessary application of lime, fertilizer, and seed.
- Begin at the top of the slope by anchoring the HP-TRMs in a 6" (15 cm) deep x 6" (15cm) wide trench with approximately 12" (30 cm) of HP-TRMs extended beyond the up-slope portion of the trench. Backfill and compact the trench after stapling. Apply seed to compacted soil and fold remaining 12" (30 cm) portion of HP-TRMs back over seed and compacted soil. Secure HP-TRMs with a row of staples/stakes spaced approximately 12" (30 cm) apart across the width of the HP-TRMs.
- Roll the HP-TRMs (A) down or (B) horizontally across the slope. HP-TRMs will unroll with appropriate side against the soil surface. All HP-TRMs must be securely fastened to soil surface by placing staples/stakes in appropriate locations as shown in the staple pattern guide.
- The edges of parallel HP-TRMs must be stapled with approximately 2" - 5" (5-12.5cm) overlap depending on the HP-TRM type.
- Consecutive HP-TRMs spliced down the slope must be end over end (Shingle style) with an approximate 3"(7.5cm) overlap. Staple through overlapped area, approximately 12"(30cm) apart across entire HP-TRM width.




NOTE: In loose soil conditions, the use of staple or stake lengths greater than 6"(15cm) may be necessary to properly secure the HP-TRMs.

Revisions:

No.	Date	Comments
1	11/9/15	Town Comments
2	12/7/15	Town Comments
3	1/25/16	Town Comments
4	5/7/16	Town Comments

SCALE: NTS
DRAWN BY: TK
DATE: 9/25/15

Engineer: Joseph C. Rina, P.E., NYS Lic. No. 64431



SLOPE INSTALLATION EARTH ANCHOR (EA) DETAIL

- Prepare soil before installing high-performance turf reinforcement mats (HP-TRMs), including any necessary application of lime, fertilizer, and seed.
- Begin at the top of the slope by anchoring the HP-TRMs in a 6" (15 cm) deep x 6" (15cm) wide trench with approximately 12" (30 cm) of HP-TRMs extended beyond the up-slope portion of the trench. Backfill and compact the trench after stapling. Apply seed to compacted soil and fold remaining 12" (30 cm) portion of HP-TRMs back over seed and compacted soil. Secure HP-TRMs with a row of staples/stakes spaced approximately 12" (30 cm) apart across the width of the HP-TRMs.
- Roll the HP-TRMs (A) down or (B) horizontally across the slope. HP-TRMs will unroll with appropriate side against the soil surface. All HP-TRMs must be securely fastened to soil surface by placing staples/stakes in appropriate locations as shown in the staple pattern guide.
- The edges of parallel HP-TRMs must be stapled with approximately 2" - 5" (5-12.5cm) overlap depending on the HP-TRM type.
- Consecutive HP-TRMs spliced down the slope must be end over end (Shingle style) with an approximate 3"(7.5cm) overlap. Staple through overlapped area, approximately 12"(30cm) apart across entire HP-TRM width.




NOTE: In loose soil conditions, the use of staple or stake lengths greater than 6"(15cm) may be necessary to properly secure the HP-TRMs.

Revisions:

No.	Date	Comments
1	11/9/15	Town Comments
2	12/7/15	Town Comments
3	1/25/16	Town Comments
4	5/7/16	Town Comments

SCALE: NTS
DRAWN BY: TK
DATE: 9/25/15

Engineer: Joseph C. Rina, P.E., NYS Lic. No. 64431



SLOPE INSTALLATION EARTH ANCHOR (EA) DETAIL

- Prepare soil before installing high-performance turf reinforcement mats (HP-TRMs), including any necessary application of lime, fertilizer, and seed.
- Begin at the top of the slope by anchoring the HP-TRMs in a 6" (15 cm) deep x 6" (15cm) wide trench with approximately 12" (30 cm) of HP-TRMs extended beyond the up-slope portion of the trench. Backfill and compact the trench after stapling. Apply seed to compacted soil and fold remaining 12" (30 cm) portion of HP-TRMs back over seed and compacted soil. Secure HP-TRMs with a row of staples/stakes spaced approximately 12" (30 cm) apart across the width of the HP-TRMs.
- Roll the HP-TRMs (A) down or (B) horizontally across the slope. HP-TRMs will unroll with appropriate side against the soil surface. All HP-TRMs must be securely fastened to soil surface by placing staples/stakes in appropriate locations as shown in the staple pattern guide.
- The edges of parallel HP-TRMs must be stapled with approximately 2" - 5" (5-12.5cm) overlap depending on the HP-TRM type.
- Consecutive HP-TRMs spliced down the slope must be end over end (Shingle style) with an approximate 3"(7.5cm) overlap. Staple through overlapped area, approximately 12"(30cm) apart across entire HP-TRM width.


NOTE: In loose soil conditions, the use of staple or stake lengths greater than 6"(15cm) may be necessary to properly secure the HP-TRMs.

Revisions:

No.	Date	Comments
1	11/9/15	Town Comments
2	12/7/15	Town Comments
3	1/25/16	Town Comments
4	5/7/16	Town Comments




SCALE: NTS
DRAWN BY: TK
DATE: 9/25/15

Engineer: Joseph C. Rina, P.E., NYS Lic. No. 64431



GENERAL NOTES:




- All signage shall be in accordance with the latest edition of the national MUTCD and the N.Y.S Supplement (MUTCD), September 2007, including the following:
 - A. Letter size and series
 - B. Legend and background color
 - C. Reflectivity
 - D. Size of sign
- The type of characters as specified in the standard specifications shall be as follows:
 - MUTCD CODE LETTER
 - G.I.
 - R.P.W.M.
 - TYPE IV OR V
- Sign locations as shown on plans are approximate. The Contractor shall relocate existing signs and install new signs in accordance with the MUTCD, latest edition. The Contractor shall contact the Town Engineer to discuss/resolve problem areas.
- Except where otherwise specified, parking signs shall be placed facing approaching traffic at an angle of between 30 and 45 degrees with the line of traffic flow. Parking signs shall be placed at each end of a regulation (single-headed arrows) and, within the regulation (double-headed arrows), at intervals not to exceed 200 ft.
- Where new signs are installed the Contractor shall affix a label to the back of the sign panel. This label will show the date of installation and identification numbers.
- Placement of W3-17 sign is prescribed in the General Municipal Law.



R-4

CONCRETE CURB DETAIL




NOT TO SCALE



S-1

TRASH ENCLOSURE DETAIL

NOT TO SCALE



R-8

TIMBER GUARDRAIL DETAIL

NOT TO SCALE

Site Design Consultants
Civil Engineers • Land Planners
251-F Underhill Avenue, Yorktown Heights, NY 10598
(914) 962-4488 - Fax: (914) 962-7386
www.sitedesignconsultants.com

Engineer:

Revisions:	No.	Date	Comments
1	1/9/15		Town Comments
2	12/7/15		Town Comments
3	1/25/16		Town Comments
4	3/7/16		Town Comments

SCALE: N.T.S.

DRAWN BY: TK

DATE: 9/25/15

DETAILS

SITE PLAN PREPARED FOR

PARTH KNOLLS LLC.

87 HAWKES AVENUE

Town of Ossining

Westchester County, NY


Sheet

C-502

E:\2015\15-48 BELDOTT MANAGEMENT CORP\ENGINEERING\CAD\CD-15418 BELDOTT MANAGEMENT CORP\15-48 DETAILS 3-1-15.DWG


S-1

PRECAST CONCRETE SEWER MANHOLE DETAIL
NOT TO SCALE



S-2

GRAVITY SEWER LATERAL CLEAN-OUT DETAIL
NOT TO SCALE



Sheet

C-504

SITE PLAN
PREPARED FOR
PARTH KNOLLS LLC.
87 HAWKES AVENUE
Town of Ossining
Westchester County, NY

**SANITARY
SEWER
DETAILS**

SCALE:
NTS

DRAWN BY:
TK

DATE:
9/25/15

Revisions:		Date	Comments
No.			
1		11/9/15	Town Comments
2		12/7/15	Town Comments
3		1/25/16	Town Comments
4		3/7/16	Town Comments

Engineer:

Joseph C. Rina, P.E.
NYS Lic. No. 64431


Site Design Consultants

Civil Engineers • Land Planners
251-F Underhill Avenue, Yorktown Heights, NY 10598
(914) 962-4488 - Fax: (914) 962-7386
www.sitedesignconsultants.com



PROJECT # 15-18

COPYRIGHT © 2012 BY SITE DESIGN CONSULTANTS. ALL RIGHTS RESERVED




NOTES:

- All design specifications for Stormtech SC-310 chambers shall be in accordance with the Stormtech design manual.
- The installation of Stormtech SC-310 chambers shall be in accordance with the latest Stormtech installation instructions.
- The contractor is advised to review and understand the installation instructions prior to beginning system installation. Call 1-888-892-2694 or visit www.stormtech.com to receive a copy of the latest Stormtech installation instructions.
- Chambers shall meet the design requirements and load factors specified in Section 12.12 of the latest edition of the AASHTO LRFD bridge design specifications


SWM-1 STORMTECH SC-310 CHAMBER SYSTEM PLAN VIEW DETAIL

NOT TO SCALE



SWM-2 STORMTECH SC-310 CHAMBER DETAIL

NOT TO SCALE




SWM-3 STORMTECH SC-310 CROSS SECTION DETAIL

NOT TO SCALE



SWM-4 STORMTECH SC-310 CHAMBER DETENTION ISOLATOR ROW DETAIL

NOT TO SCALE



SWM-5 STORMTECH FLUSING/INSPECTION PORT DETAIL

NOT TO SCALE

SWM-6 RAIN GARDEN DETAIL

NOT TO SCALE

SWM-7 RAIN GARDEN DETAIL

NOT TO SCALE

SWM-8 RAIN GARDEN DETAIL

NOT TO SCALE

SWM-9 RAIN GARDEN DETAIL

NOT TO SCALE

SWM-10 RAIN GARDEN DETAIL

NOT TO SCALE

SWM-11 RAIN GARDEN DETAIL

NOT TO SCALE

SWM-12 RAIN GARDEN DETAIL

NOT TO SCALE

SWM-13 RAIN GARDEN DETAIL

NOT TO SCALE

SWM-14 RAIN GARDEN DETAIL

NOT TO SCALE

SWM-15 RAIN GARDEN DETAIL

NOT TO SCALE

SWM-16 RAIN GARDEN DETAIL

NOT TO SCALE

SWM-17 RAIN GARDEN DETAIL

NOT TO SCALE

SWM-18 RAIN GARDEN DETAIL

NOT TO SCALE

SWM-19 RAIN GARDEN DETAIL

NOT TO SCALE

SWM-20 RAIN GARDEN DETAIL

NOT TO SCALE

SWM-21 RAIN GARDEN DETAIL

NOT TO SCALE

SWM-22 RAIN GARDEN DETAIL

NOT TO SCALE

SWM-23 RAIN GARDEN DETAIL

NOT TO SCALE

SWM-24 RAIN GARDEN DETAIL

NOT TO SCALE

SWM-25 RAIN GARDEN DETAIL

NOT TO SCALE

SWM-26 RAIN GARDEN DETAIL

NOT TO SCALE

SWM-27 RAIN GARDEN DETAIL

NOT TO SCALE

SWM-28 RAIN GARDEN DETAIL

NOT TO SCALE

SWM-29 RAIN GARDEN DETAIL

NOT TO SCALE

SWM-30 RAIN GARDEN DETAIL

NOT TO SCALE

SWM-31 RAIN GARDEN DETAIL

NOT TO SCALE

SWM-32 RAIN GARDEN DETAIL

NOT TO SCALE

SWM-33 RAIN GARDEN DETAIL

NOT TO SCALE

SWM-34 RAIN GARDEN DETAIL

NOT TO SCALE

SWM-35 RAIN GARDEN DETAIL

NOT TO SCALE

SWM-36 RAIN GARDEN DETAIL

NOT TO SCALE

SWM-37 RAIN GARDEN DETAIL

NOT TO SCALE

SWM-38 RAIN GARDEN DETAIL

NOT TO SCALE

SWM-39 RAIN GARDEN DETAIL

NOT TO SCALE

SWM-40 RAIN GARDEN DETAIL

NOT TO SCALE

SWM-41 RAIN GARDEN DETAIL

NOT TO SCALE

SWM-42 RAIN GARDEN DETAIL

NOT TO SCALE

SWM-43 RAIN GARDEN DETAIL


NOT TO SCALE

SWM-44 RAIN GARDEN DETAIL

NOT TO SCALE

SWM-45 RAIN GARDEN DETAIL

NOT TO SCALE



Protected by U.S. Patent Nos. 6,797,161; 6,836,163; 6,839,461; 6,951,607; 6,984,782; 7,011,743; 7,037,436

CrystalStream Technologies

Best Management Practice (BMP) is a term used to describe the most effective and efficient way to manage stormwater runoff. BMPs are designed to prevent or reduce the amount of stormwater runoff that enters the water body. BMPs are designed to prevent or reduce the amount of stormwater runoff that enters the water body. BMPs are designed to prevent or reduce the amount of stormwater runoff that enters the water body.

Job Name: Parth Knolls LLC - SC-310 Pretreatment Device No.: CST-IIP NYO-001-010515 DESIGN FIRM: Site Design Consultants

SPECIFICATIONS:
1. TOTAL FLOW CAPACITY SHALL BE 6 CFS.
2. WATER QUALITY FLOW OF 0.06 CFS MUST BE MAINTAINED.
3. SPILL PROTECTION CAPACITY SHALL BE 434 GALLONS BEFORE OVERFLOW.
4. ANY CHANGES OR SUBSTITUTIONS MUST BE APPROVED BY THE ENGINEER AND THE REVIEWING AUTHORITY.

3.1 INSPECTION OVERVIEW

THE UNIT IS DESIGNED AND SPECIFIED IN MOST APPLICATIONS TO COMPLY WITH THE NON-POINT SOURCE MANDATES OF THE CLEAN WATER ACT AND THE NPDES REGULATIONS. THESE REGULATIONS STATE THAT ANY BMP (BEST MANAGEMENT PRACTICE) NEEDS TO BE INSPECTED EVERY 90 DAYS AND CLEANED AND MAINTAINED AS NEEDED. MANY LOCAL REGULATIONS HAVE SIMILAR REQUIREMENTS AND ALL FEDERAL, STATE AND LOCAL REQUIREMENTS MUST BE MET. CRYSTALSTREAM TECHNOLOGIES RECOMMENDS VISUAL INSPECTION ON A 30-DAY CYCLE AS WELL AS SEDIMENT DEPTH INSPECTION, DURING THE CONSTRUCTION PHASE. THE UNIT INSPECTION IS DONE TO DETERMINE THE OPERATIONAL STATUS OF THE UNIT AND DETERMINE IF A CLEANING CYCLE IS NECESSARY AS WELL AS TO MEET ANY JURISDICTIONAL ORDINANCE REQUIREMENTS. ALL INSPECTIONS MUST BE DOCUMENTED (APPENDIX 2). WHEN CONSTRUCTION HAS BEEN COMPLETED AND THE SITE HAS STABILIZED, THE CST UNIT SHOULD BE INSPECTED EVERY 90 DAYS FOR THE FIRST YEAR AND CLEANED WHEN SEDIMENT REACHES THE MAXIMUM STORAGE CAPACITY.

3.2 INSPECTION PROCEDURES

AS PER THE FOLLOWING:

- 3.2.1 THE UNIT SHOULD BE VISUALLY INSPECTED FROM THE SURFACE TO DETERMINE THE INTEGRITY OF ACCESS POINTS. LOOK FOR BROKEN HINGES OR BROKEN OR MISSING HANDLES. A QUALIFIED WELDER SHOULD REPAIR ANY BROKEN HINGES IMMEDIATELY. INSPECT BOLTS ON LID ANGLE IRON AND LOOK FOR LOOSE RED HEADS ON ANGLE IRON. REPLACE RED HEADS AS NEEDED. RE-PAINT THE LID, WITH A RUST RESISTANT PAINT AS NECESSARY.
- 3.2.2 THE ACCESS SHOULD BE OPENED AND SECURED PROPERLY.
- 3.2.3 A VISUAL INSPECTION SHOULD BE MADE OF THE TRASH BASKET AT THE FRONT OF THE UNIT TO DETERMINE CAPACITY AND TYPE OF MATERIAL TRAPPED.
- 3.2.4 A VISUAL INSPECTION SHOULD BE MADE OF THE WATER SURFACE IN THE FRONT OF THE UNIT TO DETERMINE OIL SHEEN OR BLANKET.
- 3.2.5 A VISUAL INSPECTION SHOULD BE MADE OF THE OIL AND HYDROCARBON RESERVOIR TO DETERMINE AMOUNT OF OIL/WATER TRAPPED AND THE HISTORICAL HIGH-WATER LEVEL IN THE UNIT.
- 3.2.6 A VISUAL INSPECTION OF THE WATER SURFACE IN THE REAR OF THE UNIT SHOULD BE MADE AND ANY POLLUTANTS NOTED.
- 3.2.7 INSPECT THE ALUMINUM MESH IN THE TRASH BASKET. REPLACE AS NEEDED.
- 3.2.8 INSPECT THE BASKET FRAME FOR CRACKS OR DAMAGE. REPAIR AS NEEDED.
A VISUAL INSPECTION SHOULD BE MADE OF THE PIPE CONNECTIONS TO THE UNIT AND ANY MATERIAL DECAY OR IMPROPER INSTALLATION NOTED. PIPES SHOULD BE CUT FLUSH WITH THE INTERIOR WALL OF THE UNIT AND PROPERLY MUDDED IN. IF UPON INSPECTION IT IS NOTED THAT THE PIPES ARE NOT CUT FLUSH, OR ARE NOT MUDDED IN, CONTACT THE CONTRACTOR AND REQUIRE THAT HE CORRECT THIS IMMEDIATELY.
- 3.2.9 INSPECT BAFFLES TO ENSURE THAT THEY ARE PROPERLY SEATED INTO THE BRACKETS. ALSO NOTE IF THERE IS ANY DAMAGE TO BAFFLES (BOWING). RESEAT BAFFLES IF NECESSARY.
- 3.2.10 INSPECT OIL RESERVOIR FOR CRACKS OR DAMAGE. CHECK THE WELDS AROUND THE OIL RESERVOIR FOR WEAR OR DAMAGE AND NOTE ANY REPAIR WORK NECESSARY. A QUALIFIED WELDER MUST PERFORM ALL REPAIR WORK TO THE WELDS ON THE OIL RESERVOIR DURING THE ROUTINE CLEANING.
- 3.2.11 INSPECT THE RISER FOR CRACKS IN THE CONCRETE WALLS. REPAIR AS REQUIRED DURING THE ROUTINE CLEANING.
- 3.2.12 A SILT GAUGE SHOULD BE USED TO DETERMINE SEDIMENT DEPTH AS SHOWN IN APPENDIX 1. CHECK THE SILT/SEDIMENT LEVEL BEHIND THE TRASH BASKET AND IN FRONT OF THE OIL RESERVOIR
- 3.2.13 THE ACCESS FOR CLEANING SHOULD BE EVALUATED AND DOCUMENTED. THE TRUCK CLEANING THESE UNITS REQUIRES A STABLE ROADWAY CAPABLE OF WITHSTANDING 15,000 POUNDS.
- 3.2.14 ANY CHANGES IN THE AREA TRIBUTARY THAT ARE EVIDENT SHOULD BE NOTED.
- 3.2.15 REPLACE THE ACCESS POINT COVERS CAREFULLY.
- 3.2.16 NOTE THE CONDITION OF THE AREA SURROUNDING THE UNIT ON THE INSPECTION REPORT. (EXAMPLE: GRASS, DIRT, ROCKS, SINK HOLES) REPORT ANY HAZARDOUS CONDITIONS TO THE APPROPRIATE SUPERVISOR.
- 3.2.17 AN INSPECTION REPORT SHOULD BE COMPLETED, WITH A COPY STAYING ON SITE AND A COPY BEING SENT TO THE LOCAL JURISDICTION.

THE INSPECTION PROCEDURES FOR THE TRAFFIC UNITS ARE SIMILAR TO THOSE FOR THE NON- TRAFFIC UNITS WITH THE EXCEPTION OF THE SEDIMENT DEPTH EVALUATIONS AS SHOWN IN APPENDIX 1 AND AN INSPECTION OF THE GRATE AND FRAME AND RING AND COVER. ALSO PROPER PRECAUTIONS SHOULD BE TAKEN IN TRAFFIC SITUATIONS AS SPECIFIED IN THE SAFETY SECTION OF THIS MANUAL.

NOTE: WHEN THERE HAS BEEN AN OBVIOUS GASOLINE SPILL OR OTHER FLAMMABLE/HAZARDOUS MATERIAL IN THE UNIT, IMMEDIATE NOTIFICATION SHOULD BE GIVEN TO THE OWNER AND JURISDICTIONAL AUTHORITIES. THIS MANUAL IS FOR ROUTINE CLEANING OF STORM WATER DEBRIS AND ANY UNUSUAL OCCURRENCES SHOULD BE LEFT TO PROPERLY TRAINED AND EQUIPPED INDIVIDUALS.

4.1 CLEANING OVERVIEW

THE CLEANING OF THE UNIT IS THE ESSENTIAL ELEMENT TO THE OPERATIONAL SUCCESS OF THE CRYSTALSTREAM DEVICE. THE POLLUTANT REMOVAL CAPACITY OF THE DEVICE WILL EVENTUALLY CAUSE THE EQUIPMENT TO FAIL WITHOUT PROPER MAINTENANCE AND ADDITIONALLY NOT ACHIEVE THE GOALS OF THE INSTALLATION. THE CLEANING CYCLE IS DEPENDANT ON A NUMBER OF FACTORS INCLUDING POLLUTANT LOAD, RAINFALL, TIME OF YEAR, BASIN CHANGES, UPSTREAM MITIGATION TACTICS AND INSTALLATION. BASED ON THE VARIETY OF FACTORS, A CLEANING SCHEDULE CAN BE CONSISTENT OR VARY WIDELY ON THE SAME DEVICE. THIS HIGHLIGHTS THE IMPORTANCE OF THE INSPECTION PROCESS IN THE OVERALL MAINTENANCE AND INTEGRITY OF THE UNIT. THE CLEANING IS GENERALLY DONE WITH A TWO-PERSON CREW AND A VACUUM PUMP SYSTEM. THE DURATION OF THE MAINTENANCE WILL DEPEND ON A NUMBER OF FACTORS BUT CAN TYPICALLY BE DONE IN ABOUT 2.5 HOURS WITH PROPERLY TRAINED INDIVIDUALS.

4.2 OPTION 1: CLEANING PROCEDURES - SURFACE CLEANING

IF THE CLEANING OF THE UNIT IS TO BE PREFORMED FROM THE SURFACE, THE OPERATOR SHOULD EXPECT A LONGER CLEANING TIME AND THE POTENTIAL FOR ADDITIONAL DISPOSAL CHARGES. THE FRONT CHAMBER OF THE UNIT WILL CONTAIN THE TRASH AND DEBRIS IN THE TRASH BASKET, ANY FLOATING HYDROCARBONS THAT HAVE NOT BEEN SKIMMED INTO THE OIL/HYDROCARBON RESERVOIR AND ACCUMULATED SEDIMENT ON THE BOTTOM OF THE UNIT.

CLEANING PROCEDURES ARE AS PER THE FOLLOWING:

- 4.2.1 THE UNIT SHOULD BE VISUALLY INSPECTED FROM THE SURFACE TO DETERMINE THE INTEGRITY OF THE TREAD PLATE LID, ALUMINUM HATCH OR OTHER ACCESS.
- 4.2.2 A VISUAL INSPECTION OF THE UNIT SHOULD BE DONE TO EVALUATE STRUCTURAL INTEGRITY AND DETERMINE IF ANY IMPACTED MATERIAL IS PRESENT IN THE DEVICE. IF THERE HAS BEEN A HAZARDOUS SPILL SEE SECTION 4.6

NOTE: WHEN THERE HAS BEEN AN OBVIOUS GASOLINE SPILL OR OTHER FLAMMABLE/HAZARDOUS MATERIAL IN THE UNIT, IMMEDIATE NOTIFICATION SHOULD BE GIVEN TO THE OWNER AND JURISDICTIONAL AUTHORITIES. THIS MANUAL IS FOR ROUTINE CLEANING OF STORM WATER DEBRIS AND ANY UNUSUAL OCCURRENCES SHOULD BE LEFT TO PROPERLY TRAINED AND EQUIPPED INDIVIDUALS.

- 4.2.3 THE TRASH BASKET SHOULD BE CLEANED BY EITHER USING A TRASH NETTING SYSTEM OR VACUUM TRUCK. IF CLEANING USING A NETTING SYSTEM, THIS MATERIAL CAN BE DISPOSED OF IN TRASH BAGS IN THE NORMAL MANNER.
- 4.2.4 THE SURFACE OIL/HYDROCARBON SEPARATION ZONE IN THE FRONT CHAMBER SHOULD BE REMOVED EITHER WITH SORBANTS OR WITH A VACUUM TRUCK.
- 4.2.5 THE STORMWATER CONTAINED IN THE AREA BETWEEN THE SURFACE WATER AND THE SEDIMENT ACCUMULATION CAN BE DECANTED TO MINIMIZE THE AMOUNT OF DISPOSAL REQUIRED. ANY DOWNSTREAM DISCHARGE NEEDS TO BE AFTER THE SURFACE CLEANING AND ONLY DOWN TO THE LEVEL OF THE BOTTOM OF THE OIL/HYDROCARBON RESERVOIR OR THE TOP OF THE SEDIMENT ACCUMULATION. ANY POLLUTANTS DISCHARGED DOWNSTREAM ARE THE RESPONSIBILITY OF THE CLEANING OPERATOR.
- 4.2.6 THE OIL/HYDROCARBON RESERVOIR NEEDS TO BE EVACUATED BY THE VACUUM EQUIPMENT.
- 4.2.7 THE SEDIMENT ACCUMULATED IN THE FRONT AND REAR CHAMBER CAN BE REMOVED BY THE VACUUM EQUIPMENT.
- 4.2.8 THE UNIT SHOULD BE PRESSURE WASHED DOWN TO REMOVE ANY POLLUTION ATTACHED TO THE BAFFLES, WALLS OR HYDROCARBON RESERVOIR.
- 4.2.9 ALL PARTS SHOULD BE INSPECTED FOR WEAR AND TEAR AND DOCUMENTED.

- 4.2.10 A MAINTENANCE REPORT (APPENDIX 3) SHOULD BE COMPLETED, WITH A COPY STAYING ON SITE AND A COPY BEING SENT TO THE LOCAL JURISDICTION.
- 4.3 OPTION 2: CLEANING PROCEDURES - CONFINED SPACE ENTRY

THE CLEANING PROCEDURES ARE SIMILAR FOR CONFINED SPACE ENTRIES EXCEPT THAT THE OSHA GUIDELINE APPLY AND NEED TO BE FOLLOWED. THE CONFINED SPACE ENTRY ALLOWS THE CREW TO DO A BETTER JOB OF CLEANING THE UNIT AND ALLOWS FOR THE TIME NEEDED AND DISPOSAL COST TO BE REDUCED.

CAUTION! ANY INSPECTION DONE IN A TRAFFIC AREA MUST MEET THE DOT GUIDELINES FOR ROADWAY WORK AND ADDITIONAL SAFETY PROCEDURE WILL BE NECESSARY.

CAUTION! ALL OSHA CONFINED SPACE REQUIREMENTS SHOULD BE MET WHILE CLEANING THIS UNIT. AS PER THE FOLLOWING:

- 4.3.1 THE UNIT SHOULD BE VISUALLY INSPECTED FROM THE SURFACE TO DETERMINE THE INTEGRITY OF THE TREAD PLATE LID.
 - 4.3.2 A VISUAL INSPECTION OF THE UNIT SHOULD BE DONE TO EVALUATE STRUCTURAL INTEGRITY AND DETERMINE IF ANY IMPACTED MATERIAL IS PRESENT IN THE DEVICE. IF THERE HAS BEEN A HAZARDOUS SPILL SEE SECTION 4.6
- NOTE: WHEN THERE HAS BEEN AN OBVIOUS GASOLINE SPILL OR OTHER FLAMMABLE/HAZARDOUS MATERIAL IN THE UNIT, IMMEDIATE NOTIFICATION SHOULD BE GIVEN TO THE OWNER AND JURISDICTIONAL AUTHORITIES. THIS MANUAL IS FOR ROUTINE CLEANING OF STORM WATER DEBRIS AND ANY UNUSUAL OCCURRENCES SHOULD BE LEFT TO PROPERLY TRAINED AND EQUIPPED INDIVIDUALS.

- 4.3.3 A LADDER SHOULD BE INSERTED ON THE FRONT SIDE OF THE UNIT BETWEEN THE BAFFLES AND A SORBANT BLANKET LAID ON THE SURFACE OF THE WATER TO COLLECT ANY FREE OIL FLOATING ON THE SURFACE.
- 4.3.4 IN MOST UNITS, THE TRASH BASKET AND BAFFLES CAN BE REMOVED TO ALLOW EASIER ACCESS TO THE BOTTOM OF THE UNIT.
- 4.3.5 INSPECT THE ALUMINUM MESH IN THE TRASH BASKET. REPLACE AS NEEDED.
- 4.3.6 THE TRASH BASKET SHOULD BE CLEANED AND DIRECTLY DISPOSED OF IN GARBAGE BAGS.
- 4.3.7 THE STORMWATER CONTAINED IN THE AREA BETWEEN THE SURFACE WATER AND THE SEDIMENT ACCUMULATION CAN BE DECANTED TO MINIMIZE THE AMOUNT OF DISPOSAL REQUIRED. ANY DOWNSTREAM DISCHARGE NEEDS TO BE AFTER THE SURFACE CLEANING AND ONLY DOWN TO THE LEVEL OF THE BOTTOM OF THE OIL/HYDROCARBON RESERVOIR OR THE TOP OF THE SEDIMENT ACCUMULATION. ANY POLLUTANTS DISCHARGED DOWNSTREAM ARE THE RESPONSIBILITY OF THE CLEANING OPERATOR.
- 4.3.8 THE UNIT SHOULD BE PRESSURE WASHED DOWN TO REMOVE ANY POLLUTION ATTACHED TO THE BAFFLES, WALLS OR HYDROCARBON RESERVOIR.
- 4.3.9 THE LADDER CAN BE USED TO GET ON TO THE UNIT FLOOR AND REMOVE THE REST OF THE WATER AND SEDIMENT FROM THE BOTTOM OF THE UNIT.
- 4.3.10 THE WALLS SHOULD BE WIPED DOWN IN THE FRONT WITH A SORBANT BLANKET
- 4.3.11 THE FRESH COCONUT FIBER MESH SHOULD BE REPLACED IN THE FRAME AND THE FRAME ASSEMBLY RETURNED TO THE UNIT.
- 4.3.12 ALL PARTS SHOULD BE INSPECTED FOR WEAR AND TEAR AND DOCUMENTED.
- 4.3.13 REMOVE ALL EQUIPMENT FROM THE UNIT. REPLACE THE MANHOLE COVER AND THE GRATE IN THE CONCRETE LID.
- 4.3.14 A MAINTENANCE REPORT (APPENDIX 3) SHOULD BE COMPLETED, WITH A COPY STAYING ON SITE AND A COPY BEING SENT TO THE LOCAL JURISDICTION.

CLEANING EQUIPMENT

THE EQUIPMENT NEEDED TO CLEAN THE CRYSTALSTREAM UNIT IS:

- VACUUM TRUCK 750 GALLON
- PRESSURE WASHER
- SUBMERSIBLE PUMP
- GENERATOR
- SORBANT PADS (MYCELTTM)
- 16-25 FT. LADDER
- GLOVES
- COCONUT FIBER MESH (ROLANKA INDUSTRIES)
- TRASH BAGS
- CRYSTALSTREAM LID HOOKS
- SEDIMENT/SILT GAUGE
- RUBBER BOOTS
- TESTING EQUIPMENT TO MEET OSHA CONFINED SPACE ENTRY REQUIREMENTS
- CONES
- BARRICADES
- CAUTION TAPE
- HARDHAT
- WATERPROOF SILICON CAULK
- ALUMINUM MESH (FOR TRASH BASKET)
- FLAT SHOVEL
- 20' ELECTRICAL CORD
- 5 GALLON BUCKET W/ROPE
- FIRST AID KIT CONTAINING EYE WASH
- TRIPOD SAFETY HARNESS RECOVERY APPARATUS

CALL CRYSTALSTREAM AT 1-800-748-6945 IF YOU NEED SUPPLIES OR PARTS.

DOCUMENTATION AND DISPOSAL

THE CLEANING OF THE UNIT SHOULD BE DOCUMENTED AND THE CONTENTS OF THE UNIT ESTIMATED AND RECORDED IN A LOG FOR INSPECTIONS. THIS DOCUMENTATION SHOULD MEET FEDERAL, STATE AND LOCAL GUIDELINES.


THE DISPOSAL OF THE TRASH, DEBRIS, WATER AND SEDIMENT SHOULD BE DONE AT AN APPROVED FACILITY AND THE PROPER PERMITS SHOULD BE OBTAINED TO TRANSPORT THE MATERIAL. SEDIMENT AND WATER SHOULD BE DISPOSED OF IN ACCORDANCE WITH ALL APPLICABLE STATE AND LOCAL REGULATIONS. SEDIMENT SHOULD BE REMOVED TO A LANDFILL AND LIQUIDS TO A DECANTING FACILITY.

HAZARDOUS WASTE PROCEDURE

THE PRESENCE OF ANY HAZARDOUS MATERIAL INSIDE THE UNIT SHOULD PROMPT AN IMMEDIATE CALL TO THE JURISDICTION AND AN APPROPRIATE HAZARDOUS RESPONSE TEAM. THIS MATERIAL IS NOT PART OF THE STANDARD CLEANING OF THE DEVICE AND SHOULD BE TREATED WITH THE PROPER CARE AFFORDED SUCH SPILLS AS PER FEDERAL, STATE AND LOCAL GUIDELINES.

5.1 MAINTENANCE OVERVIEW

ALL OF THE COMPONENTS IN THE UNIT SHOULD BE INSPECTED AT EVERY CLEANING TO DETERMINE WEAR OR DAMAGE. IF ANY COMPONENTS ARE DAMAGED, PLEASE CONTACT CRYSTALSTREAM TECHNOLOGIES FOR AN EVALUATION OF THE DAMAGE AND A MAINTENANCE ESTIMATE.



Site Design Consultants

Civil Engineers • Land Planners
251-F Underhill Avenue, Yorktown Heights, NY 10598
(914) 962-4488 - Fax: (914) 962-7386
www.sitedesignconsultants.com

Engineer:

Joseph C. Rina, P.E.
NYS Lic. No. 64431

Revisions:		No.	Date	Comments
1	11/9/15	1	11/9/15	Town Comments
2	12/7/15	2	12/7/15	Town Comments
3	1/25/16	3	1/25/16	Town Comments
4	3/7/16	4	3/7/16	Town Comments

SCALE: NTS	DRAWN BY: TK	DATE: 9/25/15
---------------	-----------------	------------------

CRYSTAL
STREAM
DETAILS


SITE PLAN
PREPARED FOR
PARTH KNOLLS LLC.

87 HAWKES AVENUE


Westchester County, NY

Sheet

C-507



BILL OF MATERIALS					
ITEM #	QTY	UNIT	DESCRIPTION	MATERIAL	REMARKS
1	1	3653ANC_1	36" TRIPLE MANIFOLD TEE W/24" RISER, W/8" CLEANOUT		See Detail
2	1	3651AN	36" SINGLE MANIFOLD TEE		See Detail
3	1	3658AN	36" X 90 DEGREE MANIFOLD BEND		See Detail
4	1	3658AN	36" X 90 DEGREE MANIFOLD BEND W/24" RISER		See Detail
5	1	3658ANC_1	36" X 90 DEGREE MANIFOLD BEND W/24" RISER		See Detail
6	1	3658ANC_2	36" X 90 DEGREE MANIFOLD BEND W/12" STUB		See Detail
7	6	36580020IB	36" PIPE STICK : SOIL TIGHT (FIELD CUT)		See Detail
8	1	3658ANC_3	36" X 90 DEGREE MANIFOLD BEND W/12" STUB		See Detail
9	1	3658ANC_2	36" X 90 DEGREE MANIFOLD BEND W/12" STUB		See Detail
10	1	3658ANC_3	36" X 90 DEGREE MANIFOLD BEND W/12" STUB		See Detail
11	1	3658ANC_4	36" X 90 DEGREE MANIFOLD BEND W/12" STUB		See Detail




NOMINAL DIAMETER	NOMINAL O.D.	TYPICAL SPACING "C"	TYPICAL SIDE WALL "X"	MIN. H (NON-TRAFFIC)	MIN. H (TRAFFIC)	MAX. H*
36" (900 MM)	42" (1067 MM)	63" (1600 MM)	18" (457 MM)	12" (292 MM)	12" (292 MM)	8' (2.4 M)

* MAXIMUM FILL HEIGHTS OVER MANIFOLD FITTINGS. CONTACT MANUFACTURER'S REPRESENTATIVE FOR INSTALLATION CONSIDERATIONS WHEN COVER EXCEEDS 8-FT.
** 60" SYSTEMS REQUIRE CLASS I BACKFILL AROUND ALL FITTINGS.

NOTES:

- ALL REFERENCES TO CLASS I OR II MATERIAL ARE PER ASTM D2321 "STANDARD PRACTICE FOR UNDERGROUND INSTALLATION OF THERMOPLASTIC PIPE FOR SEWERS AND OTHER GRAVITY FLOW APPLICATIONS", LATEST EDITION.
- ALL RETENTION AND DETENTION SYSTEMS SHALL BE INSTALLED IN ACCORDANCE WITH ASTM D2321, LATEST EDITION AND THE MANUFACTURER'S PUBLISHED INSTALLATION GUIDELINES.
- MEASURES SHOULD BE TAKEN TO PREVENT THE MIGRATION OF NATIVE FINES INTO THE BACKFILL MATERIAL, WHEN REQUIRED. SEE ASTM D2321.
- FILTER FABRIC:** A GEOTEXTILE FABRIC MAY BE USED AS SPECIFIED BY THE ENGINEER TO PREVENT THE MIGRATION OF FINES FROM THE NATIVE SOIL INTO THE SELECT BACKFILL MATERIAL.
- FOUNDATION:** WHERE THE TRENCH BOTTOM IS UNSTABLE, THE CONTRACTOR SHALL EXCAVATE TO A DEPTH REQUIRED BY THE ENGINEER AND REPLACE WITH SUITABLE MATERIAL AS SPECIFIED BY THE ENGINEER. AS AN ALTERNATIVE AND AT THE DISCRETION OF THE DESIGN ENGINEER, THE TRENCH BOTTOM MAY BE STABILIZED USING A GEOTEXTILE MATERIAL.
- BEDDING:** SUITABLE MATERIAL SHALL BE CLASS I OR II. THE CONTRACTOR SHALL PROVIDE DOCUMENTATION FOR MATERIAL SPECIFICATION TO ENGINEER, UNLESS OTHERWISE NOTED BY THE ENGINEER. MINIMUM BEDDING THICKNESS SHALL BE 4" (100mm) FOR 4"-24" (100mm-600mm), 6" (150mm) FOR 30"-60" (750mm-900mm).
- INITIAL BACKFILL:** SUITABLE MATERIAL SHALL BE CLASS I OR II IN THE PIPE ZONE EXTENDING NOT LESS THAN 6" ABOVE CROWN OF PIPE. THE CONTRACTOR SHALL PROVIDE DOCUMENTATION FOR MATERIAL SPECIFICATION TO ENGINEER. MATERIAL SHALL BE INSTALLED AS REQUIRED IN ASTM D2321, LATEST EDITION.
- COVER:** MINIMUM COVER OVER ALL RETENTION/DETENTION SYSTEMS IN NON-TRAFFIC APPLICATIONS (GRASS OR LANDSCAPE AREAS) IS 12" FROM TOP OF PIPE TO GROUND SURFACE. ADDITIONAL COVER MAY BE REQUIRED TO PREVENT FLOATATION. FOR TRAFFIC APPLICATIONS, MINIMUM COVER IS 12" UP TO 36" DIAMETER PIPE AND 24" OF COVER FOR 42"-60" DIAMETER PIPE. MEASURED FROM TOP OF PIPE TO BOTTOM OF FLEXIBLE PAVEMENT OR TO TOP OF RIGID PAVEMENT. MAXIMUM FILL HEIGHT LIMITED TO 8-FT OVER FITTINGS FOR STANDARD INSTALLATIONS. CONTACT A SALES REPRESENTATIVE WHEN MAXIMUM FILL HEIGHTS EXCEED 8-FT FOR INSTALLATION CONSIDERATIONS.

© 2009 ADS, INC.



CLASS I OR II MATERIAL PER ASTM D2321, LATEST EDITION, COMPACTED IN MAX. 8" LOOSE LIFTS TO 95% MIN. OF MAX. SPD

* LOAD BEARING CONCRETE COLLAR AS SPECIFIED BY DESIGN ENGINEER (WHERE REQUIRED)

TRAFFIC INSTALLATION

UNDISTURBED EARTH

CLASS I OR II MATERIAL PER ASTM D2321, LATEST EDITION, COMPACTED IN MAX. 8" LOOSE LIFTS TO 95% MIN. OF MAX. SPD

BEDDING (CLASS I OR II MATERIAL) = 4" MIN. FOR 12" - 24" HDPE PIPE = 6" MIN. FOR 30" - 60" HDPE PIPE

SECTION A-A

TRAFFIC INSTALLATION

UNDISTURBED EARTH

CLASS I OR II MATERIAL PER ASTM D2321, LATEST EDITION, COMPACTED IN MAX. 8" LOOSE LIFTS TO 95% MIN. OF MAX. SPD

BEDDING (CLASS I OR II MATERIAL) = 4" MIN. FOR 12" - 24" HDPE PIPE = 6" MIN. FOR 30" - 60" HDPE PIPE

SECTION B-B

* LOAD BEARING CONCRETE COLLAR SHALL BE CONSTRUCTED IN TRAFFIC AREAS SUCH THAT THE LIVE LOAD IS TRANSMITTED TO THE SURROUNDING SOIL AND NOT DIRECTLY TO THE RISER.

ADS RETENTION/DETENTION PIPE SYSTEM SPECIFICATION

SCOPE

THIS SPECIFICATION DESCRIBES ADS RETENTION/DETENTION PIPE SYSTEMS FOR USE IN NON-PRESSURE GRAVITY-FLOW STORM WATER COLLECTION SYSTEMS UTILIZING A CONTINUOUS OUTFALL STRUCTURE.

PIPE REQUIREMENTS

ADS RETENTION/DETENTION SYSTEMS MAY UTILIZE ANY OF THE VARIOUS PIPE PRODUCTS BELOW:

- N-12 ST IB PIPE (PER AASHTO) SHALL MEET AASHTO M234, TYPE S OR ASTM F2306
- N-12 ST IB PIPE (PER ASTM F2648) SHALL MEET ASTM F2648
- N-12 MEGA GREEN ST IB SHALL MEET ASTM F2648
- N-12 WT IB PIPE (PER AASHTO) SHALL MEET AASHTO M234, TYPE S OR ASTM F2306
- N-12 WT IB PIPE (PER ASTM F2648) SHALL MEET ASTM F2648
- N-12 MEGA GREEN WT IB SHALL MEET ASTM F2648

ALL PRODUCTS SHALL HAVE A SMOOTH INTERIOR AND ANNULAR EXTERIOR CORRUGATIONS. ALL ST IB PIPE PRODUCTS ARE AVAILABLE AS PERFORATED OR NON-PERFORATED. WT IB PIPE PRODUCTS ARE ONLY AVAILABLE AS NON-PERFORATED. PRODUCT-SPECIFIC PIPE SPECIFICATIONS ARE AVAILABLE IN THE DRAINAGE HANDBOOK SECTION 1 SPECIFICATIONS

JOINT PERFORMANCE

PLAIN END SOIL-TIGHT (ST IB): ST IB PIPE SHALL BE JOINED USING A BELL & SPIGOT JOINT. THE BELL & SPIGOT JOINT SHALL MEET THE SOIL-TIGHT REQUIREMENTS OF ASTM F2306 AND GASKETS SHALL MEET THE REQUIREMENTS OF ASTM F477.

PLAIN END PIPE & FITTINGS CONNECTIONS SHALL BE JOINED WITH COUPLING BANDS COVERING AT LEAST TWO FULL CORRUGATIONS ON EACH END OF THE PIPE. GASKETED SOIL-TIGHT COUPLING BAND CONNECTIONS SHALL INCORPORATE A CLOSED-CELL SYNTHETIC EXPANDED RUBBER GASKET MEETING THE REQUIREMENTS OF ASTM D1056 GRADE 2A2. GASKETS, WHEN APPLICABLE, SHALL BE INSTALLED BY THE PIPE MANUFACTURER.

WATERTIGHT (WT IB): WT IB PIPE SHALL BE JOINED USING A BELL & SPIGOT JOINT. THE JOINT SHALL BE WATERTIGHT ACCORDING TO THE REQUIREMENTS OF ASTM D3212. GASKETS SHALL MEET THE REQUIREMENTS OF ASTM F477. 12" THROUGH 60" INCH (300 TO 1500MM) DIAMETERS SHALL HAVE A BELL REINFORCED WITH A POLYMER COMPOSITE BAND. THE BELL TOLERANCE DEVICE SHALL BE INSTALLED BY THE MANUFACTURER.

PIPE & FITTING CONNECTIONS SHALL BE WITH A BELL & SPIGOT CONNECTION UTILIZING A SPUN-ON OR WELDED BELL AND VALLEY OR SADDLE. GASKET. THE JOINT SHALL MEET THE WATERTIGHT REQUIREMENTS OF ASTM D3212, AND GASKETS SHALL MEET THE REQUIREMENTS OF ASTM F477.

DETENTION SYSTEMS ARE SUBJECT TO GREATER LEAKAGE THAN TYPICAL SINGLE RUN STORM SEWER APPLICATIONS AND THEREFORE ARE NOT APPROPRIATE FOR APPLICATIONS REQUIRING LONG-TERM FLUID CONTAINMENT OR HYDROSTATIC PRESSURE. FOR ADDITIONAL DETAILS REFER TO TECHNICAL NOTE 7.01 RAINWATER HARVESTING WITH HDPE CISTERNS.

FITTINGS

FITTINGS SHALL CONFORM TO ASTM F2306 AND MEET JOINT PERFORMANCE INDICATED ABOVE FOR FITTINGS CONNECTIONS. CUSTOM FITTINGS ARE AVAILABLE AND MAY REQUIRE SPECIAL INSTALLATION CRITERION.

INSTALLATION

INSTALLATION SHALL BE IN ACCORDANCE WITH ASTM D2321 AND ADS RECOMMENDED INSTALLATION GUIDELINES, WITH THE EXCEPTION THAT MINIMUM COVER IN NON-TRAFFIC AREAS FOR 12" THROUGH 60" INCH (300 TO 1500MM) DIAMETERS SHALL BE ONE FOOT (0.3M).

MINIMUM COVER IN TRAFFIC AREAS FOR 12" THROUGH 36" INCH (300 TO 900MM) DIAMETERS SHALL BE ONE FOOT (0.3M) AND FOR 42" THROUGH 60" INCH (1050 TO 1500MM) DIAMETERS, THE MINIMUM COVER SHALL BE 2 FT (0.6M). BACKFILL SHALL CONSIST OF CLASS I MATERIAL ONLY. MINIMUM COVER HEIGHTS DO NOT ACCOUNT FOR PIPE BUOYANCY. REFER TO ADS TECHNICAL NOTE 5.05 HDPE PIPE FLOTATION FOR BUOYANCY DESIGN CONSIDERATIONS.

COVER OVER SYSTEM USING STANDARD BACKFILL IS 8-FT (2.4M); CONTACT A REPRESENTATIVE WHEN MAXIMUM FILL HEIGHT MAY BE EXCEEDED. ADDITIONAL INSTALLATION REQUIREMENTS ARE PROVIDED IN THE DRAINAGE HANDBOOK SECTION 6 RETENTION/DETENTION.

NOTES:



- ALL ELEVATIONS, DIMENSIONS AND LOCATIONS OF RISERS, INLETS AND OUTLETS, SHALL BE VERIFIED BY THE ENGINEER PRIOR TO RELEASING FOR FABRICATION.
- IN SITUATIONS WHERE A FINE-GRAINED BACKFILL MATERIAL IS USED ADJACENT TO THE PIPE SYSTEM, AND ESPECIALLY INVOLVING DRAINAGE AND WATER CONDITIONS, CONSIDERATION SHOULD BE GIVEN TO THE USE OF GASKETED PIPE JOINTS. AT THE VERY LEAST THE PIPE JOINTS SHOULD BE WRAPPED IN A SUITABLE, NON-WOVEN GEOTEXTILE FABRIC TO PREVENT INFILTRATION OF FINES INTO THE PIPE SYSTEM.
- CONSIDERATION FOR CONSTRUCTION EQUIPMENT LOADS MUST BE TAKEN INTO ACCOUNT.
- ALL PIPE DIMENSIONS ARE SUBJECT TO MANUFACTURER'S TOLERANCES.
- ALL RISERS TO BE FIELD EXTENDED OR TRIMMED TO FINAL GRADE.

THE PROCEEDING DETAILS WERE GENERATED USING ADS DESIGN PRO®, A SOFTWARE PROGRAM DEVELOPED BY ADVANCED DRAINAGE SYSTEMS, INC. ("ADS"). THESE DRAWINGS ARE INTENDED TO DEPICT THE ADS COMPONENTS AS REQUESTED BY THE USER. ADS HAS NOT PERFORMED ANY ENGINEERING OR DESIGN SERVICES FOR THIS PROJECT, NOR HAS ADS INDEPENDENTLY VERIFIED THE INFORMATION SUPPLIED. THE INSTALLATION DETAILS PROVIDED HEREIN ARE GENERAL RECOMMENDATIONS AND ARE NOT SPECIFIC FOR THIS PROJECT. THE DESIGN ENGINEER SHALL REVIEW THESE DETAILS PRIOR TO CONSTRUCTION. IT IS THE DESIGN ENGINEER'S RESPONSIBILITY TO ENSURE THE DETAILS PROVIDED HEREIN MEETS OR EXCEEDS THE APPLICABLE NATIONAL, STATE, OR LOCAL REQUIREMENTS AND TO ENSURE THAT THE DETAILS PROVIDED HEREIN ARE ACCEPTABLE FOR THIS PROJECT.

THE UNDERSIGNED HERBY APPROVES THE ATTACHEMENTS.


CUSTOMER DATE

36" TRIPLE MANIFOLD TEE W/24" RISER, W/8" CLEANOUT




ITEM # 1
QTY : 1
3653ANC_1

36" SINGLE MANIFOLD TEE





ITEM # 2
QTY : 2
3651AN

36" X 90 DEGREE MANIFOLD BEND





ITEM # 3
QTY : 1
3698AN

36" TRIPLE MANIFOLD TEE W/8" CLEANOUT





ITEM # 4
QTY : 1
3653ANC_2

36" X 90 DEGREE MANIFOLD BEND W/24" RISER





ITEM # 5
QTY : 1
3698ANC_1

36" X 90 DEGREE MANIFOLD BEND W/12" STUB




ITEM # 9
QTY : 1
3698ANC_2

36" X 90 DEGREE MANIFOLD BEND W/12" STUB




ITEM # 10
QTY : 1
3698ANC_3

36" PIPE STICK : SOIL TIGHT (FIELD CUT)




ITEM # 6
QTY : 6
Stick 1

36" PIPE STICK : SOIL TIGHT



ITEM # 7
QTY : 6
36850020IB

36" PIPE STICK : SOIL TIGHT (FIELD CUT)



ITEM # 8
QTY : 6
Stick 2



PROJECT # 15-18

Site Design Consultants

Civil Engineers • Land Planners
251-F Underhill Avenue, Yorktown Heights, NY 10598
(914) 962-4488 • Fax: (914) 962-7386
www.sitedesignconsultants.com

Engineer:

Joseph C. Ritina, P.E.
NYS Lic. No. 64431

Revisions:

SCALE: NTS

DRAWN BY: TK

DATE: 9/25/15

CISTERN DETAILS

SITE PLAN
PREPARED FOR


PARTH KNOLLS LLC.

87 HAWKES AVENUE

Westchester County, NY

Sheet

C-508



LOCATION MAP
NOT TO SCALE



Buffer to be restored, grass, vines and invasive species to be removed, and area re-planted

Wetland to be restored, vines and non-native species to be removed

Buffer to be restored, vines and non-native species to be removed

Buffer to be restored, grass removed and area re-planted

Buffer to be expanded, grass removed and area re-planted

Buffer to be restored, vines, non-native species, concrete and asphalt to be removed

Buffer to be restored, grass removed and area re-planted

Proposed removal of shallow sediments and re-seeding with wetland seed mix

Proposed forebay to capture incoming sediments before they reach the watercourse and pond

PROPOSED DECK (TYP.)

PROPOSED PATIO (TYP.)

PROPOSED SPLIT RAIL FENCE (TYP.)


PROPOSED BUILDING #1
F.F. ELEVATION = 315.0
PARKING ELEVATION = 305.0

PROPOSED BUILDING #2
F.F. ELEVATION = 317.2
PARKING ELEVATION = 307.2

PROPOSED MAIN ENTRANCE/EXIT
PROPOSED SIGN LOCATION

- Limits of existing watercourse
- Limits of existing town regulated wetland
- Limits of permanent buffer disturbance
- Limits of wetland restoration area
- Limits of buffer restoration and enhancement

- PROPERTY LINE / RIGHT OF WAY
- PROPOSED CURB
- EDGE OF WETLAND
- 100' WETLAND BUFFER



SAFE DIG
Before You Dig, Drill or Blast!


Plant Species Choices for Mitigation Area				
Map Symbol	Quantity	Scientific Name	Common Name	Size
Trees				
Aru	11	Acer rubrum	Red maple	5' - 6'
Ns	6	Nyssa sylvatica	Black tupelo	5' - 6'
Qp	7	Quercus palustris	Pin oak	5' - 6'
Po	4	Platanus occidentalis	Sycamore	5' - 6'
Shrubs				
AC	21	Amelanchier canadensis	Shadblow	3' - 4'
CSe	21	Cornus sericea	Redosier dogwood	3' - 4'
Iv	36	Ilex verticillata	Winterberry holly	3' - 4'
SD	12	Salix discolor	Pussy willow	3' - 4'
ASe	12	Alnus serrulata	Speckled alder	4' - 5'
VC	33	Vaccinium corymbosum	Highbush blueberry	4' - 5'
VD	31	Viburnum dentatum	Arrowwood	4' - 5'



Buffer mitigation plan prepared by
Steve Marino, PWS, of Tim Miller Associates, Inc.
Revision date: January 21, 2016

NOTE:
1. THIS IS NOT A SURVEY. ALL SURVEY INFORMATION SHOWN ON THIS PLAN HAS BEEN TAKEN FROM SURVEY MAP PREPARED BY JOSEPH R. LINK, DATED 03/07/15, LAST REVISED 06/08/15. THE ENGINEER ASSUMES NO RESPONSIBILITY FOR ITS ACCURACY.

NOTE: UNAUTHORIZED ALTERATIONS OR ADDITIONS TO THIS DRAWING IS A VIOLATION OF SECTION 7209 (2) OF THE NEW YORK STATE EDUCATION LAW.



PROJECT # 15-18

Site Design Consultants

Civil Engineers • Land Planners
251-F Underhill Avenue, Yorktown Heights, NY 10598
(914) 962-4488 • Fax: (914) 962-7386
www.sitedesignconsultants.com

Engineer:

Joseph C. Rima, P.E.
NYS Lic. No. 64431

Revisions:		Comments:	
No.	Date	No.	Date
1	1/9/15	1	1/9/15
2	12/7/15	2	12/7/15
3	12/7/15	3	12/7/15

SCALE: 1" = 30'	DRAWN BY: TK	DATE: 9/25/15
--------------------	-----------------	------------------

WETLAND
BUFFER
MITIGATION

SITE PLAN
PREPARED FOR
PARTH KNOLLS LLC.

87 HAWKES AVENUE
Town of Ossining
Westchester County, NY

Sheet

M-101

Wetland Buffer Mitigation Narrative and Specification
Parth Knolls
Hawkes Avenue, Town of Ossining, NY
January 21, 2016

Project Description

The applicant proposes the development of 53 rental units in conformance with the existing zoning. Some of the activities that are necessary for this development will occur within the 100 foot regulated setback to wetlands and 50 foot setback to watercourses. No filling or other disturbance to wetlands or watercourses is proposed. Existing site wetlands are associated with two watercourses that enter the site.

Mitigation Proposal

The applicant is proposing a three-tier approach to mitigating the encroachments into federal wetlands.

Buffer Enhancement. The existing buffer has been historically disturbed for activities associated with the former residential/office use. Existing concrete paths, non-native edges and maintained lawn areas, dominate the buffer on the east side of the western watercourse, and on the north side of watercourse/pond at the south end of the site. It is proposed to remove existing concrete and asphalt, remove non-native shrubs and other vegetation, and cease the mowing of lawns within these areas.

Buffer Restoration. A total of 28 new trees and 166 new shrubs will be planted within the buffer areas to enhance and restore the buffer to a more natural condition. The plant list includes all native species commonly found in wetland and transitional areas in the Hudson Valley. As noted above, regular mowing will cease and seed mixes suitable for buffer and transitional areas will be applied, with one annual mowing occur in the fall to occur in these areas.

Wetland Restoration. The small fringing wetlands associated wit the watercourses are dominated by invasive plant species, including porcelainberry, oriental bittersweet, multiflora rose and others. It is proposed to actively remove these species by hand in those areas where the plants are most dominant. Wetland seed mix especially selected for riparian corridors will then be used in these areas.

Along the watercourse at the southern end of the site, sediment that has accumulated over the years after passing under the Hawkes Avenue culvert will be removed by machine and used as fill elsewhere on site. The newly exposed substrate will be hayed and seeded with wetland seed mix and planted with shrubs as shown on the accompanying plans.

Forebay Creation. In order to prevent future sediment deposition in the watercourse and wetland, a new "forebay" feature will be excavated in the buffer just downstream of the Hawkes Avenue culvert, in a location that is currently maintained as lawn. This shallow depressional areas is expected to allow sediment entering the system to settle out in a location that is more easily accessed and maintained.

Use of Porous Pavement and Creation of Nature Trails. In some portions of the buffer that are currently maintained as lawn, future disturbance needed to create the necessary number of parking spaces is unavoidable. In these areas the parking spaces will be made up of porous pavement in order to continue the groundwater recharge and filtering function of the buffer areas.

Nature trails are proposed from the proposed playground and pool areas to a wooden foot bridge across the restored stream channel to provide access to the natural areas on the western side of the stream. Wooden benches will be placed along the trail for rest or observation.

Planting Details

Plant choices for the wetland buffer were made according to existing site conditions and locally common species. All planting will proceed by hand. Materials will be brought to the site in good condition (see below) and then placed in central drop locations. The materials will then be hand-carried to their planting locations and in turn, planted by hand. Only rounded, shallow planting shovels will be used in this effort.

Criteria for selecting plant material will include (1) the plant's ability to withstand the expected light and saturation conditions; (2) its demonstrated survival on this site and other nearby sites; (3) the plant must be native and non-invasive; and (4) whether the plant material is available at nurseries in the same region as the site. The location of the trees and shrubs are coordinated with the proposed Landscape Plan (Sheet L-1) and the existing tree survey.

Planting will be done in spring or early summer (between April 1 and July 1). Shrubs may also be planted in the late summer to early fall (September 1 to October 30). In all cases, a hole will be dug twice as deep as the root ball. The only shovels allowed are rounded, shallow spades. The hole will then be backfilled with a thin layer (two to four inches) of rich, organic topsoil, the plant placed inside, the hole backfilled to the top and then gently tamped down.

Container-grown plant material delivered to the job site will be inspected to assure moist soil/root masses. Any dry and light weight plants will not be accepted. If not planted immediately the container will be stored out of the sun and wind and kept moist (i.e., a means of watering will be provided and watering will occur daily). When removed from the containers, the plants will be the size of the specified container. If in leaf, the plants will appear healthy with no spots, leaf damage, discoloration, insects or fungus. If not in leaf, the buds will be firm and free of damage, discoloration, insects or fungus. Containers will be a minimum of quart size for shrubs and gallon size for trees. Plants not having an abundance of well developed terminal buds on the leaders and branches will be rejected. The stems and branches of all plants will be turgid and the cambium healthy or the plants rejected. Seeding within wetland areas should not be completed when there is more than two inches of standing water, or in areas that are likely to be flooded. Seeds should be broadcast by hand or knapsack seeder using the proper seeding rate (3.5 pounds per acre), and carefully proportioning seed for the entire area. Cover with a light layer of straw mulch following seeding.


Monitoring and Maintenance

At least one pre-construction meeting will occur between the chosen grading and/or planting contractor/subcontractor and the site environmental systems planner prior to beginning construction on site. The construction monitor will have experience in wetland construction and a Bachelor of Science degree in Natural and/or Physical Resources.

Monitoring and maintenance efforts for the mitigation plantings will take place over a three year period following construction. This will include bi-weekly visits for the first growing season, and then twice a year for the next two years, with additional inspections as required depending on conditions. The applicant's environmental monitor will conduct a survey of the site and site conditions will be noted and adjusted as necessary. An annual report will be provided to the Town of Ossining at the end of the growing season for each of the three years. These reports will include the following information:

1. All plant species, along with their estimated relative frequency and percent cover, shall be identified.
2. Vegetation cover maps, at a scale of one inch equals 30 or larger, shall be prepared for each growing season.
3. Photographs showing all representative areas of the mitigation site shall be taken at least once each year during the period between 1 June and 15 August.

Plantings will meet or exceed and 85 percent survival rate by the end of the second growing season. If this goal is not met, the site will be re-evaluated, and re-grading and/or replanting will be completed as necessary. Invasive species (i.e., oriental bittersweet, multiflora rose, etc.) will not constitute more than 10 percent of the vegetative community. If this goal is exceeded, measures will be taken to eradicate the invasive species.



Plant Species Choices for Mitigation Area				
Map Symbol	Quantity	Scientific Name	Common Name	Size
Trees				
Ar	11	Acer rubrum	Red maple	5' - 6'
Ns	6	Nyssa sylvatica	Black tupelo	5' - 6'
Op	7	Quercus palustris	Pin oak	5' - 6'
Ps	4	Platanus occidentalis	Sycamore	5' - 6'
Shrubs				
AC	21	Amelanchier canadensis	Shadblow	3' - 4'
CSe	21	Cornus sericea	Redosier dogwood	3' - 4'
Iv	36	Ilex verticillata	Winterberry holly	3' - 4'
SD	12	Salix discolor	Pussy willow	3' - 4'
ASE	12	Anus serrulata	Speckled alder	4' - 5'
VC	33	Vaccinium corymbosum	Highbush blueberry	4' - 5'
VD	31	Viburnum dentatum	Arrowwood	4' - 5'


The proposed seed mix (Specialized Wetland Mix for Shaded OBL-FACW Areas (ERNMX - 137 or equivalent) includes the following species:

- 25% Fox Sedge, PA Ecotype (Carex vulpinoidea, PA Ecotype)
- 20% Virginia Wild Rye, PA Ecotype (Elymus virginicus, PA Ecotype)
- 14% Nodding Sedge, PA Ecotype (Carex gynandra, PA Ecotype)
- 8% Eastern Bur Reed (Sparganium americanum)
- 7% Blunt Broom Sedge, PA Ecotype (Carex scoparia, PA Ecotype)
- 5% Lurid (Shallow) Sedge, PA Ecotype (Carex lurida, PA Ecotype)
- 3% Bailey's Sedge, PA Ecotype (Carex baileyi, PA Ecotype)
- 3% Hop Sedge, PA Ecotype (Carex lupulina, PA Ecotype)
- 3% Bladder (Star) Sedge, PA Ecotype (Carex intumescens, PA Ecotype)
- 3% Squarrose Sedge, VA Ecotype (Carex squarrosa, VA Ecotype)
- 2% Swamp Dock, PA Ecotype (Rumex verticillatus, PA Ecotype)
- 2% Cosmos (Bristly) Sedge, PA Ecotype (Carex comosa, PA Ecotype)
- 2% Sensitive Fern (Onoclea sensibilis)
- 2% Many Leaved Bulrush, PA Ecotype (Scirpus polyphyllus, PA Ecotype)
- 1% Woolgrass, PA Ecotype (Scirpus cyperinus, PA Ecotype)

Total: 100%

NOTE:
1. THIS IS NOT A SURVEY. ALL SURVEY INFORMATION SHOWN ON THIS PLAN HAS BEEN TAKEN FROM SURVEY MAP PREPARED BY JOSEPH R. LINK, DATED 03/07/15, LAST REVISED 06/08/15. THE ENGINEER ASSUMES NO RESPONSIBILITY FOR ITS ACCURACY.

NOTE: UNAUTHORIZED ALTERATIONS OR ADDITIONS TO THIS DRAWING IS A VIOLATION OF SECTION 7209 (2) OF THE NEW YORK STATE EDUCATION LAW.



PROJECT # 15-18

Site Design Consultants

Civil Engineers • Land Planners
251-F Underhill Avenue, Yorktown Heights, NY 10598
(914) 962-4488 - Fax: (914) 962-7386
www.sitedesignconsultants.com

Engineer:
Joseph C. Rima, P.E.
NYS Lic. No. 64431

Revisions:		No.	Date	Comments
1	1/9/15	1	1/9/15	Town Comments
2	12/7/15	2	12/7/15	Town Comments
3	12/7/15	3	12/7/15	Town Comments

SCALE: 1" = 30'
DRAWN BY: TK
DATE: 9/25/15

BUFFER MITIGATION NOTES

SITE PLAN PREPARED FOR
PARTH KNOLLS LLC.
87 HAWKES AVENUE
Town of Ossining
Westchester County, NY


Sheet
M-102




Buffer mitigation plan prepared by
Steve Marino, PWS, of Tim Miller Associates, Inc.
Revision date: January 21, 2016

LEGEND



- PROPERTY LINE / RIGHT OF WAY
- == PROPOSED CURB
- - - - - EDGE OF WETLAND
- - - - - 100' WETLAND BUFFER



SAFE DIG
Before You Dig, Drill or Blast!
CALL US TODAY! (914) 962-4488 or (914) 962-7386
NY Industrial Code Rule T23 requires no less than ten working days notice, but not more than ten days notice.
www.gis@timillera.com



Parth Knolls Plant List 12-2-18				
Abb.	Botanical Name	Common Name	Size	Quan.
Deciduous Trees				
AC	Aesculus carnea	Red Horsechestnut	2-2.5" cal., 14-16" ht.	4
AS	Acer saccharum	Sugar Maple	2-2.5" cal., 14-16" ht.	5
LS	Liquidambar styraciflua	Sweetgum	2-2.5" cal., 14-16" ht.	2
MS	Magnolia sebaniana	Saucer Magnolia	2-2.5" cal., 14-16" ht.	1
PA	Platanus acerifolia	London Planetree	2-2.5" cal., 14-16" ht.	2
OR	Quercus rubra	Red Oak	2-2.5" cal., 14-16" ht.	8
Evergreen Trees				
O	Ilex opaca	American Holly	8-10' ht.	1
PG	Picea alauca	White Spruce	8-10' ht.	6
PS	Pinus strobus	White Pine	10-12' ht.	8
TP	Thuja plicata	Grand Arborvitae	8-10' ht.	9
Minor Deciduous Trees				
GLA	Cornus florida alba	White Dogwood	7-8' ht.	4
CFR	Cornus florida rubra	Pink Dogwood	7-8' ht.	2
MS	Magnolia stellata	Star Magnolia	7-8' ht.	2
OA	Ostrya virginiana	Sourwood	8-10' ht.	4
PT	Prunus thunderscloud	Thunderscloud Plum	7-8' ht.	5
PY	Prunus yedoensis	Yoshino Cherry	7-8' ht.	5
Hedge				
LO	Ilex glabra	Hollyberry	2.5-3' ht.	42
Notes				
1. All plants to be healthy, full and typical of the species, and shall meet the American Standards for Nursery Stock, latest edition. Much plant beds and the base of woody plants with 1.5-2" shredded cedar bark.				
All plants shall be planted in recognized spring and fall planting periods unless specific approval otherwise is given by the project Landscape Architect.				
2. All areas not covered with impervious surfaces to be planted with lawn grass in the following ratio by species: 90% Perennial Rye, 25% Bluegrass and 25% Creeping Fescue. 95% coverage to be guaranteed.				
3. If quantities indicated on the plant list differ from those on the plan, the plan quantities shall be used.				
4. All plants to be warranted by the contractor to be healthy and in good physical condition for one year or two full growing seasons after planting. Contractor shall maintain the site in a safe condition at all times, and shall clear the site of debris on completion of work. Post construction the owner shall maintain the site in a safe condition.				
5. Soil for all lawn areas to be a minimum of 6" depth of loamy topsoil approved by the project Landscape Architect.				
For shrubs and tree pits topsoil to be used in backfilling to the extents shown on the details.				




Notes:

1. All base data by others. No representation or warranty is express or implied as to accuracy of same.
2. This Landscape Plan is for illustration of plant material purposes only. Please refer to Engineer or Surveyor drawings for all other site plan and site features information.
3. All environmental concerns subject to local, state and/ or federal jurisdiction must be reviewed and approved by appropriate agencies.
4. Developer/ builder is responsible for maintaining a safe site during construction and until future owners take possession of the site, or portions thereof, at which time the new owners will take full responsibility for maintaining a safe site through proper maintenance, modification and/ or replacement of plant material as necessary.

4640 SERIES
Knuckle Mount
White LED Accent Light

SPECIFICATIONS	
LED	4 x 10W/1000lm
IP66	IP66
Warranty	5 Year

DESCRIPTION
The 4640 knuckle mount accent light is uniquely designed with rugged sealed die-cast aluminum construction and an offset swivel for balance. A wide range of photometric performances are available with internal and/or external glare control.



Stephen Lopez Landscape Architect	Tim Miller Associates, Inc. 10 North Street, Cold Spring, NY 10516 (845) 265-4400, Fax: 265-4418	
	Landscape Plan for development of Parth Knolls, LLC 87 Hawkes Avenue Town of Ossining, Westchester County, NY Date: December 7, 2015 Rev. 3-1-16	Sheet L-1