



SITE DATA: OWNER/DEVELOPER:

OWNER/DEVELOPER:

PARTH KNOLLS LLC.

500 EXECUTIVE BLVD. #203

OSSINING, NY, 10562

PROJECT LOCATION:

87 HAWKES AVE.

OSSINING, NY, 10562

EXISTING TOWN ZONING:

MF-I, MULTIFAMILY-INN

PROPOSED USE:

MF-I, MULTIFAMILY-INN

TOWN TAX MAP DATA:

SECTION 80.20, BLOCK 1, LOT 15

SITE AREA:

SEWAGE FACILITIES:


PUBLIC SEWERS

PUBLIC WATER FACILITIES

DRAWING INDEX:

DRAWING INDEX.	
SHEET NUMBER	DRAWING TITLE
T-1	TITLE SHEET
T-2	TITLE SHEET 2
C-101	SITE PLAN
C-102	EXISTING CONDITIONS PLAN
C-103	E&SC PLAN
C-104	UTILITY PLAN
C-105	WATERMAIN LOOP PLAN
C-106	GRADING PLAN
C-107	SIGHT DISTANCE PLAN
C-108	TREE PLAN
C-109	FIRE ACCESS PLAN
C-110	ENVIRONMENTAL CONSTRAINTS MAP
C-111	OPEN SPACE AND RECREATION PLAN
C-112	LIGHTING PLAN
C-301	UTILITY PROFILES
C-302	PROFILES
G-1	NOTES
G-2	E&SC NOTES
C-501	E&SC DETAILS
C-502	SITE DETAILS
C-503	WATERMAIN DETAILS
C-504	SANITARY SEWER DETAILS
C-505	DRAINAGE DETAILS
C-506	STORMWATER MANAGEMENT DETAILS
C-507	DOWNSTREAM DEFENDER DETAILS
C-508	CISTERN DETAILS
M-101	WETLAND BUFFER MITIGATION PLAN
M-102	BUFFER MITIGATION NOTES
L-101	LANDSCAPE PLAN
A-100	ZONING & CODE ANALYSIS
A-100A	SCHEMATIC BUILDING LAYOUT AND TABULATIONS
A-101	PROPOSED BUILDING #1 - BASEMENT FLOOR PLAN
A-102	PROPOSED BUILDING #1 - FIRST FLOOR PLAN
A-103	PROPOSED BUILDING #1 - SECOND FLOOR PLAN
A-104	PROPOSED BUILDING #1 - UPPER LEVEL FLOOR PLAN
A-105	PROPOSED BUILDING #1 - ROOF PLAN
A-106	PROPOSED BUILDING #1 - FRONT AND REAR ELEVATIONS
A-107	PROPOSED BUILDING #1 - LEFT AND RIGHT SIDE ELEVATIONS
A-201	PROPOSED BUILDING #2 - BASEMENT FLOOR PLAN
A-202	PROPOSED BUILDING #2 - FIRST FLOOR PLAN
A-203	PROPOSED BUILDING #2 - SECOND FLOOR PLAN
A-204	PROPOSED BUILDING #2 - UPPER LEVEL FLOOR PLAN
A-205	PROPOSED BUILDING #2 - ROOF PLAN
A-206	PROPOSED BUILDING #2 - FRONT AND REAR ELEVATIONS
A-200 A-207	PROPOSED BUILDING #2 - LEFT AND RIGHT SIDE ELEVATIONS
A ZOI	1 NOT COLD BUILDING #2 LET 1 AND MOTH SIDE ELEVATIONS

PARTH KNOLLS LLC.



CIVIL ENGINEER:
SITE DESIGN CONSULTANTS
251-F UNDERHILL AVENUE
YORKTOWN HEIGHTS, NY 10598
P: 914 962 4488

F: 914 962 7386 jriina@sitedesignconsultants.com

SURVEYOR:

LINK LAND SURVEYORS
21 CLARK PLACE, SUITE 1B
MAHOPAC, NY 10541
P: 845-628-5857
F: 845-621-0013
www.linklandsurveyors.com

ENVIRONMENTAL CONSULTANT: TIM MILLER ASSOCIATES INC.


10 NORTH STREET COLD SPRING, NY 10516 P: 845-265-4400


TRAFFIC CONSULTANT:

TIM MILLER ASSOCIATES INC. 10 NORTH STREET COLD SPRING, NY 10516 P: 845-265-4400

ARCHITECT:

ARQ.HT, LLC. 100 EXECUTIVE BLVD #205 OSSINING, NY 10562 P: 914-944-3377





ZONING SCHEDULE:

ZONING DISTRICT:	MF-I,	MULTI FAMILY RESI	DENTIAL
DIMENSIONAL REGULATIONS:	REQUIRED	PROVIDED	VARIANCE REQUIRED
MINIMUM SIZE OF LOT:			
MINIMUM LOT AREA: MINIMUM LOT WIDTH: MINIMUM LOT DEPTH:	40,000 SF. 150 FT. 150 FT.	240,751 SF. 522 FT. 414 FT.	NONE NONE NONE
MINIMUM YARD DIMENSIONS: PRINCIPAL BUILDING:			
FRONT YARD SETBACK: REAR YARD SETBACK: ONE SIDE YARD SETBACK: COMBINED SIDE YARD SETBACK:	50 FT. 40 FT. 50 FT. 100 FT.	68 FT. 201 FT. 50 FT. 100 FT.	NONE NONE NONE NONE
MAXIMUM % OF LOT TO BE OCCUPIED: LOT COVERAGE:	66% x 240,751 SF = 158,895 SF	73,894 SF	NONE
BUILDING COVERAGE:	20% x 240,751 SF = 48,151 SF	32,767 SF	NONE
MAXIMUM HEIGHT:			
PRINCIPAL BUILDING - FEET: PRINCIPAL BUILDING - STORIES:	35 FEET 2 1/2	30 FEET 2 1/2	NONE NONE

ZONING REGULATION NOTES:

1. AT LEAST 1/3 OF THE NET SITE AREA SHALL BE DEVOTED TO PERMANENT OPEN SPACE AND/OR FOR SITES SUITABLE FOR RECREATION AS REQUIRED BY NOTE 2. UNDEVELOPED PERMANENT OPEN SPACE SHALL BE PROVIDED AND GUARANTEED AT THE RATE OF 1,500 SQUARE FEET PER BEDROOM.

2. THERE SHALL BE PROVIDED ON THE SAME LOT A SUITABLY EQUIPPED AND LANDSCAPED CHILDREN'S PLAY AREA WITH A MINIMUM OF 400 SQUARE FEET FOR EACH DWELLING UNIT.

3. BUILDING COVERAGE SHALL BE NO MORE THAN 20% OF LOT AREA. 20% x 240,751 SF = 48,151 SF PARKING SCHEDULE

PARKING REQUIRED: Two (2) spaces per dwelling unit pursuant to Zoning Section 200-29. Dwelling, Multifamily

Proposed Dwelling units. 53 apa	ertments time (2) equals	106 spaces
Indoor Parking	Breakdown	Total Parking
Building No. 1	Standard 25 Handicap 1 Total <u>26</u>	26
Building No. 2	Standard 30 Handicap 1 Total <u>31</u>	31
Outdoor Parking	Breakdown	
	Standard 55 Handicap 3 Total 58	58
Total Parking Provided		<u>115</u>

NOTES:
1. PARKING REGULATION IN CONFORMANCE WITH CHAPTERS 200-29 A(1),(2),(3)(a), C, D(1),(2)

<u>Article VI.</u> Section 200.33 Affordable Housing {BMR} Section 200.34 Required 10% of the number of Dwelling units More than 5, but fewer than 10 acres Maximum permitted Density Bonus Calculation Dwelling 41 Apartm 41 1/2 of the units received must be BMR Density Bonus (x) 30% Density Bonus Number of Dwelling units Rounded Number of Dwelling units 12 Total number of units with density Bonus 1/2 of the Bonus Units received must be BMR 6
BMR units will be broken down as follows: 1 2 bedroom unit General Description of Project 5 1 bedroom units Number of Multifamily Units Non-BMR BMR Units | Total Units | Bedrooms Unit Ratio

 One (1) B/R
 31
 9
 40
 40
 75%

 Two (2) B/R
 10
 3
 13
 26
 25%

 Total Dwelling Units
 41
 12
 53
 66
 100%

 <u>Section 200.29</u> Parking & loading 2 for each dwelling unit plus 0.5 for each bedroom more than 2 bedrooms Regular Apts BMR Apts Parking Dwelling Units 41 12 Parking per Dwelling Unit (x) 2 (x) 2

Total Parking spaces required 82 24 106 Building Height Max Stories 2 1/2 Feet 35' Colonial

DISTANCE BETWEEN BLDGS. (#200-16C(1) (B))
BUILDING HEIGHT X 2 = 30' X2= 60' PROVIDED 60.4'

BULK REGULATIONS (#200-22)

THE TOTAL NUMBER OF APARTMENTS ALLOWED PER SECTION 200-22; **BULK REGULATIONS** 1. REQUIRED SQ FT PER DWELLING UNIT. 4,000 SF PLUS 1,500 SQ FT PER BEDROOM. ONE (1) BEDROOM APARTMENTS 5,500 TWO (2) BEDROOM APARTMENTS 7,000 CALCULATION:

ONE (1) BEDROOM APARTMENTS 5,500SF X 31 = 170,500 SF 31 TWO (2) BEDROOM APARTMENTS 7,000 SF X 10= <u>70,000</u> SF 10 TOTAL APARTMENTS


TOTAL SF AREA REQUIRED 240,000 SF TOTAL PROVIDED-SITE SF AREA: 240,751 SF

No. No. No. Sq. Fl.Area Simplex Duplex Simplex Unit 1 8/R 1 8/R 2 No. No. No. No. Sq. Fl.Area Simplex Unit 1 8/R 1 8/R 1 No. N			ble Housing								ļ
No fewer than 10% of the total number of Units Shall be BMR Units Number of BMR Units Provided							h this Sect	ion			
Number of BMR Units Required 5.3	Section	200-33					c Shall ba	DMD Hai			
			!			ibei oi Onii		DIVIN UIII	.5		
More Ana 5 acres, but fewer than, 10 30% Bonus							5.3				
Section	<u>Section</u>	<u>200-34</u>									
The BMR units shall be no less than 00% of the size of self marker rate units and shall be reached by derivation. Further, the BMR units shall provide a mix of unit types in the same proportion in consideration of consideration of consideration of consideration of methods. The presidence of the size of the consideration of the BMR Units are: The Gross Units of the BMR Units are: The Gross Units of the SMR Units are: The Gross Units of the size of the size of the size of the consideration of the BMR Units are: The Gross Units of the SMR Units are: The Gross Units of the size of the	Sootion	200.25	More than 5	acres, but fo	ewer than 1	10	30% Bonu	JS			
See Street TT			The BMR ur	nits shall he	no less tha	n 80% of th	ne size of s	aid marke	et rate	units	
See Sheet T The Breakdown of the BMR Units are:											
The Development of the BMR Units are:			of unit types	in the same	proportion						
or cablustion of One (1) Bedroom Units (3) Simplex 0 in control from Units (1) From Units (1) From (2) Bedroom Units (1) Simplex Unit (1) From (2) Bedroom Units (1) Simplex Unit (1) From (2) Bedroom Units (1) Simplex Unit (1) From (2) Bedroom Units (1) Simplex Units (1) From (2) Bedroom Units (1) From (2) Bedroom (1) From (2) Bedroom (2) B								6			
Tenus Units							(Linite	5			ļ
Part Knolls Apartment Tabulation See location in schedule below See							COINS				
Building Floor Apartment Liveble One DR No. BR No. N		· · · · · · · · · · · · · · · · · · ·					lule below	- 1			
Building Floor Apartment Liveble One DR No. BR No. N											
No. No. No. Ser Flares Simplex Duplex Simplex Unit 18/R 18/R 18/R 2					0 . 0/0	0		D14D	10:		
Dec											Sim
One 1st ft 102		-				•	Omplex	Offic	_	1 0/1	2 0,
Den											
Dec 1st R. 105 1.089 1.089 1.375 1 1 1 1 1 1 1 1 1	One	1st fl.		•					1		
Den	One	1st fl.							1		
One 1st fl. 107 1,081 1,081 BMR 1 One 1st fl. 110 1,081 1,064 1,268 8 One 1st fl. 110 1,268 1,054 1,263 8 Two 1st fl. 111 1,268 3 1,263 1 Two 1st fl. 112 933 933 1,263 1 Two 1st fl. 115 1,459 1,016 1,459 Two 1st fl. 116 1,459 1,459 Two 1st fl. 117 1,034 1,216 Two 1st fl. 117 1,034 1,216 Two 1st fl. 118 1,200 1,200 Two 1st fl. 121 1,121 1,121 1,211 Two 1st fl. 122 1,119 1,119 1,149 Two 1st fl. 122 1,149 1,119 1,149 1,149									1		
Done		<u> </u>			l		1,375				
One 1st ft. 1109 1.054 1.054 1.054 1.054 1.218		1			1 '		es numero de la como	DMD	1 .		and de mass
One 1st fl. 110 1.218 1.216	(1000年4月15日 11日 11日	Hardidaliği ildə də ildə ildə ildə ildə ildə ildə	ar garaga kanalah kanalah dan basa dari basa da kanalah da 📗	otta Hanajaid Didalaatika niimidik	1,00/) 1 05/			BIVIK	1		
Two 1st ft 111					1,004		1 218		1		
Two	3.10		'''	1,210			1,210		8		
Two	Two	1st fl.	111	1,263			1,263				\vdash
Two 1stft 115	Two	1st fl.	112	933	933	•			1		
Two 1st fl. 115 1.459 1.			1 1				a papacayona ka akaa			side	she
Two	(4021-21421/1165-4)/1145-22/17114/KZ	The land of the property of the party of						BMR			
Two 1st fl. 117			L				1,459	ļ			ļ
Two											
Two			1		1,034		1 216		1		ļ
Two			1								
Two					927		1,200		1		
Two			I								
Cone 2nd fi 201									-		
One 2nd fi 201	Two	1st fl.	123	846	846			BMR			
One 2nd fil 202 1,119 1,145									16	0	
One 2nd fi 203			;		rdven renskhandera rak		ndarumentsternteranz		OSI:RADINETIUS	1 ####################################	a setsouta
Page 1, Bal. forward page 2	til and self-artists to describe a commercial residual	 very life and to be a large down a. 	Separation of the profession reality estativities			1,1119		BMK			edheli
Building						2 220			16	-	
No. No. No. Sq Ft Area Simplex Duplex Simplex Unit 1 B/R 1 B/R 2 Balances forward from page 1 28,475 16,308 2,238 9,929 16 2 2 2 1,087 0 0 0 2 2 1,087 0 0 0 2 2 1 1,087 0 0 0 2 2 1 1 0 0 0 0 0 0 0 0								DMD		t .	Sim
Balances forward from page 1 28,475 16,308 2,238 9,929 16 2 One 2nd fi 204 1,087 1,087 1 1 One 2nd fi 205 1,276 1,276 1,276 1 1 One 2nd fi 206 1,264 1,264 1,264 1 One 2nd fi 208 3,49 3,49 5,000 1 One 2nd fi 209 1,109 1,109 1,109 1 One 2nd fi 210 1,081 1,081 1 1 One 2nd fi 210 1,081 1,081 1,081 1 1 One 2nd fi 210 1,109 1,109 1 1,109 1 1 One 2nd fi 211 1,109 1,109 1 1,09 1 1 One 2nd fi 212 1,193 1,193 1,043 1 1 One 2nd fi 213 1,043 1,043 1,043 1 1 One 2nd fi 214 1,110 1,110 1 1 1 Two 2nd fi 215 1,264 1,205 1,205		1	L								
One 2nd fi 204 1,087 1,087 1,276 1 1 1 1 1 1 1 1 1			: 1			•					
One 2nd fi 206											
One 2nd fi 207 1,087 1,087 1,097 1,097 1,097 1,109	One		205			1,276				1	
One	One		206			1,264				1	
One 2nd fi 209 1,109 1,109 1,109 1 One 2nd fi 210 1,081 1,081 1,099 1 One 2nd fi 211 1,109 1,109 1 One 2nd fi 212 1,193 1,103 1 One 2nd fi 213 1,043 1,043 1 One 2nd fi 214 1,110 1,110 1 Two 2nd fi 215 1,264 1,204 1,264 Two 2nd fi 216 1,204 1,204 1,264 Two 2nd fi 218 950 950 1 1 Two 2nd fi 219 1,255 1,209 BMR 1 Two 2nd fi 220 1,038 1038 1,255 1 Two 2nd fi 221 1,202 1,255 1 1 Two 2nd fi 222 1,184 1,		1				Table March 2007 Concessional Control	25-1-9-10-27-28-40-2777-28-20-2		1	besseriestron	T. COLORES
One	CHANGE CONTRACTOR AND	120010000111000001010101010101	SAL WAS CONTRACTOR CON		849			BMR	1		
One 2nd fi 211					4.004	1,109				1	ļ
One 2nd fl 212					1,081	1 100			1	1	
One 2nd fl 213					1 193				1		
One 2nd fi 214					1,100				 	1	
Two 2nd fl 215 1,264 1,264 1,264 1,264 Two 2nd fl 216 1,209 1,209 1,209 1,209 1,255 1,255 1 1,255 1 1,264 1,270 1,		<u> </u>			1,110				1	•	
Two 2nd fi 216										7	
Two							1,264				
Two 2nd fi 218 950 950 1, 255 1, 255 1, 255 1 1, 255 1 1, 255 1 1, 255 1 1, 255 1 1, 202 1, 204 fi 220 1, 38 1038 1, 38 1038 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1		,	1 1		THE RESERVE OF THE STREET		SHIPTONGAGGGGGGGGGGG		Official programmers		aliavos
Two 2nd fl 219 1,255	CATCOLT OF SERVICE SERVICES (1)	a de la come de la com	distribution de la constitue de la constitución de la constitución de la constitue de la const	(中国统治) (() () () () () () () () () () () () (and the land of the contract o	#BloGWISHIZGURADA		BMR		SHARRING COLUMNS	
Two 2nd fi 220 1,038 1038 1,202 1,202 1,202 1,202 1,202 1,202 1,202 1,202 1,202 1,202 1,202 1,202 1,202 1,202 1,202 1,202 1,203 1,2038 1,039 1,0							1055		1		
Two			1 1				1,200		1		-
Two			1						 		
Two 2nd fl 223			J								1
Two 2nd fl 225 1,102 1,375 1,375 1 Two 2nd fl 226 1,375 1,250 1,375 1 Two 2nd fl 227 1,250 1,250 1,250 1 Two 2nd fl 228 1,250 1250 1 Two 2nd fl 229 1,196 1,196 1,138 1,138 1 Two 2nd fl 230 1,138 1,138 1,138 1 Total Square Foot Areas 59,523 26,991 16,469 16,063 26 14 Break down of Apartment Type 26 Apts 14 Apts 13 Apts Average Sq ft size by Apartment Type 1,038 sf 1,176 sf 1,236 sf 1,236 sf 2 Section 200.35.A BMR Units must be no less than 80% of size of said market rate units 830 sf 941 sf 989 sf 2 Section 200.35.B Section 200.35.B Section 200.22 Section 200.35 ft 675 sf 750 sf 2 Minimum gross Floor Area 675 sf 675 sf 750 sf 5 Section 200-22 Section 200.22 Section 200.35 ft 700 sf 7	Two	2nd fl	223	1,038	1,038				1		
Two 2nd fil 226 1,375 1,250 1,375 1 Two 2nd fil 227 1,250 1,250 1,250 1 Two 2nd fil 228 1,250 1250 1,196 1 Two 2nd fil 229 1,196 1,138 1,138 1 Total Square Foot Areas 59,523 26,991 16,469 16,063 26 14 Break down of Apartment Type 26 Apts 14 Apts 13 Apts Average Sq ft size by Apartment Type 37,038 fil 1,176 sf 1,236 sf 38 BMR Units must be no less than 80% of size of said market rate units 830 sf 941 sf 989 sf 38 Minimum gross Floor Area 675 sf 675 sf 750 sf 38 Section 200.35.B		<u> </u>				1,185				1	
Two 2nd fil 227 1,250 1,250 1,250 1 Two 2nd fil 228 1,250 1250 1,196 1 Two 2nd fil 229 1,196 1,196 1,138 1 Two 2nd fil 230 1,138 1,138 1,138 1 Total Square Foot Areas 59,523 26,991 16,469 16,063 26 14 Break down of Apartment Type 26 Apts 14 Apts 13 Apts Average Sq ft size by Apartment Type 31,038 sf 1,176 sf 1,236 sf 326 sid market rate units 328 size of said market rate units 328 size of said market rate units 328 size of Said market rate units 329 size of Said									ļ	ļ	<u> </u>
Two 2nd fl 228 1,250 1250 1 1 Two 2nd fl 229 1,196 1,196 1,138 Total Square Foot Areas 59,523 26,991 16,469 16,063 26 14 Break down of Apartment Type 26 Apts 14 Apts 13 Apts Average Sq ft size by Apartment Type 1,038 sf 1,176 sf 1,236 sf 26 BMR Units must be no less than 80% of size of said market rate units 830 sf 941 sf 989 sf 26 Section 200.35.B Minimum gross Floor Area 675 sf 675 sf 750 sf 200 sf 200-22 Minimum requirements. 700 sf per for 1 or more bedrooms 700 sf 700 sf 700 sf 700 sf 200 sf 200 sld market 200 sl		1				4 050	1,375			-	
Two 2nd fl 229 1,196 1,196 1,196 1,198 1 Two 2nd fl 230 1,138 1,138 1,138 1,138 1 Total Square Foot Areas 59,523 26,991 16,469 16,063 26 14 2 Break down of Apartment Type 26 Apts 14 Apts 13 Apts 2 Average Sq ft size by Apartment Type 1,038 sf 1,176 sf 1,236 sf 2 BMR Units must be no less than 80% of 200,35.A 200,35.B 200						1			1	 	
Two							-		<u> </u>	1	
Total Square Foot Areas 59,523 26,991 16,469 16,063 26 14						1,,,,,,	1,138			 	
Average Sq ft size by Apartment Type 1,038 sf 1,176 sf 1,236 sf		A				16,469			26	14	
Average Sq ft size by Apartment Type 1,038 sf 1,176 sf 1,236 sf							<u> </u>				
### BMR Units must be no less than 80% of size of said market rate units	<u> </u>	-	• •	t Type	1,038 sf	1,176 sf	1,236 sf				
Size of said market rate units 830 sf 941 sf 989 sf											
Section 200.35.B	3MR Unite			1 80% of							
Minimum gross Floor Area 675 sf 675 sf 750 sf					830 sf	941 sf	989 sf				
Section 200-22	size of sai				C75 6		750		ļ		
Minimum requirements. 700 sf 700 sf 700 sf Provided BMR Units Bldg. # 1	size of sai Section		or Area		6/5 sf	6/5 sf	/50 sf			 	ļ
Too sf T	size of sai Section Minimum (-			<u> </u>	-	-				
Bidg. # 1 1 st Fl Apt No.108 1,007 sf 1 B/R Simplex Bidg. # 1 2nd Fl Apt No.202 1,119 sf 1 B/R Duplex Bidg. # 1 2nd Fl Apt No. 208 849 sf 1 B/R Simplex Bidg. # 2 1 st Fl Apt No.123 846 sf 1 B/R Simplex	size of sai Section Minimum Section	200-22	200 - C	DOF 5 4 -		1		1			1
Bidg. # 1 1 st Fi Apt No.108 1,007 sf 1 B/R Simplex Bidg. # 1 2nd Fl. Apt No.202 1,119 sf 1 B/R Duplex Bidg. # 1 2nd Fl Apt No. 208 849 sf 1 B/R Simplex Bidg. # 2 1 st Fl Apt No.123 846 sf 1 B/R Simplex	size of sai Section Minimum Section Minimum	200-22 requireme	ents. 700 sf	per for 1 or	700 ef	700 ef	700 cf				
Bidg. # 1 2nd Fl. Apt No.202 1,119 sf 1 B/R Duplex Bidg. # 1 2nd Fl. Apt No. 208 849 sf 1 B/R Simplex Bidg. # 2 1 st Fl. Apt No.123 846 sf 1 B/R Simplex	size of sai Section Minimum s Section Minimum more bedr	200-22 requirement rooms		per for 1 or	700 sf	700 sf	700 sf	Brook de	own of	BMP	Inita
Bldg. # 1 2nd Fl Apt No. 208 849 sf 1 B/R Simplex Bldg. # 2 1st Fl Apt No.123 846 sf 1 B/R Simplex	size of sai Section Minimum Section Minimum more bedr	200-22 requirement ooms BMR Un	<u>its</u>	per for 1 or			700 sf			BMRL	<u>Jnits</u>
Bldg. # 2 1st Fl Apt No.123 846 sf 1 B/R Simplex	size of sai Section Minimum s Section Minimum more bedre Provided Bldg. # 1	200-22 requirement rooms BMR Un 1st Fl	its Apt No.108	per for 1 or				1 B/R Sir	nplex	BMR	<u>Jnits</u>
***	size of sai Section Minimum Section Minimum more bedr Provided Bldg. # 1 Bldg. # 1 Bldg. # 1	200-22 requirement ooms BMR Un 1st Fl 2nd Fl. 2nd Fl	its Apt No.108 Apt No.202		1,007 sf	1,119 sf		1 B/R Sir 1 B/R Du	nplex plex	BMR L	<u>Jnits</u>
	size of sai Section Minimum Section Minimum more bedr Provided Bldg. # 1 Bldg. # 1 Bldg. # 1 Bldg. # 2	200-22 requirements ooms BMR Un 1st Fl 2nd Fl. 2nd Fl 1st Fl	its Apt No.108 Apt No.202 Apt No. 208 Apt No.123		1,007 sf 849 sf	1,119 sf		1 B/R Sir 1 B/R Du 1 B/R Sir 1 B/R Sir	nplex iplex nplex nplex	BMRL	<u>Jnits</u>
7.Parth Knolls BMR Units-Rev.1.2.29.16 Page 2	ze of sai ection inimum ection inimum ore bedr rovided dg. # 1 dg. # 1 dg. # 2 dg. # 2 dg. # 2	requirements BMR Un 1st Fl 2nd Fl. 2nd Fl 1st Fl 1st Fl 1st Fl 2nd Fl.	its Apt No.108 Apt No.202 Apt No. 208 Apt No.123 Apt No.114 Apt No. 227		1,007 sf 849 sf	1,119 sf	1,053 sf	1 B/R Sir 1 B/R Du 1 B/R Sir 1 B/R Sir	nplex plex nplex nplex nplex	BMRL	<u>Jnit</u>


87.Parth Knolls BMR Units-Rev.1.2.29.16 Page 2





KNOL






































GENERAL NOTES:

- 1. THE ENGINEER WHOSE SEAL APPEARS HEREON HAS NOT BEEN RETAINED FOR SUPERVISION OF CONSTRUCTION, SUBSEQUENTLY, HE IS NOT RESPONSIBLE FOR CONSTRUCTION AND THEREFORE ASSUMES NO RESPONSIBILITY FOR CONSTRUCTION PRACTICES, PROCEDURES, AND RESULTS **THEREFROM**
- 2. THE ENGINEER SHALL NOT BE HELD RESPONSIBLE OR HELD ACCOUNTABLE FOR THE INTEGRITY OF ANY
- STRUCTURES CONSTRUCTED OR UNDER CONSTRUCTION PRIOR TO THE APPROVAL OF THE PLANS. THE TOWN ENGINEER'S OFFICE AND WATER DISTRICT OFFICE IS TO BE NOTIFIED 24 HOURS BEFORE
- COMMENCING SITE CONSTRUCTION OR WATER MAIN CONNECTION. 4. ALL WORK IS TO BE IN ACCORDANCE WITH THE TOWN CODE OF PRACTICE AND SPECIFICATIONS.
- ALL CONDITIONS, LOCATIONS, AND DIMENSIONS SHALL BE FIELD VERIFIED AND THE ENGINEER SHALL BE IMMEDIATELY NOTIFIED OF ANY DISCREPANCIES
- 6. ALL CHANGES MADE TO THE PLANS SHALL BE APPROVED BY THE ENGINEER WHOSE SEALAPPEARS ON THESE DRAWINGS. ANY SUCH CHANGES SHALL BE FILED AS AMENDMENTS TO THE ORIGINAL BUILDING
- 7. ALL WRITTEN DIMENSIONS ON THE DRAWINGS SHALL TAKE PRECEDENCE OVER ANY SCALED
- 8. IT IS THE CONTRACTOR'S RESPONSIBILITY TO CALL IN A "CODE 53" PRIOR TO CONSTRUCTION FOR UNDERGROUND UTILITY LOCATIONS. 9. SUBSTRUCTURES AND THEIR ENCROACHMENTS BELOW GRADE,
- 9. ANY PROPOSED ELECTRIC AND/OR TELEPHONE SERVICE LINES ARE TO BE PLACED UNDERGROUND. 10. THE DESIGN ENGINEER DISCLAIMS ANY LIABILITY FOR DAMAGE OR LOSS INCURRED DURING OR AFTER
- 11. ALL CONDITIONS, LOCATIONS AND DIMENSIONS SHALL BE FIELD VERIFIED BY THE CONTRACTOR AND THE OWNER/ENGINEER NOTIFIED IN WRITING OF ANY DISCREPANCIES PRIOR TO THE START OF WORK. THE OWNER/ENGINEER WILL EVALUATE THE SITUATION AND MODIFY THE PLAN AS NECESSARY.

CONTRACTOR RESPONSIBILITIES:

- 1. ALL WORK ON THE PROJECT SHALL BE PERFORMED IN A WORKMAN LIKE MANNER AND SHALL BE IN ACCORDANCE WITH THE STANDARDS OF THE INDUSTRY. THE OWNER WILL BE THE SOLE JUDGE OF THE ACCEPTABILITY OF THE WORK. MATERIALS AND WORK DEEMED UNACCEPTABLE WILL BE REMOVED AND REDONE AT THE SOLE COST AND RESPONSIBILITY OF THE CONTRACTOR.
- 2. THE CONTRACTOR SHALL BE RESPONSIBLE TO PROTECT HIS WORK AND WILL BE HELD RESPONSIBLE FOR CONSEQUENTIAL DAMAGES DUE TO HIS ACTIVITIES. THE CONTRACTOR SHALL BE RESPONSIBLE TO THE OWNER FOR THE ACTS AND OMISSIONS OF HIS EMPLOYEE, AND THEIR AGENTS AND EMPLOYEES, AND ANY OTHER PERSONS PERFORMING ANY THE WORK UNDER A SEPARATE CONTRACT WITH THE CONTRACTOR.
- 3. IT IS THE CONTRACTOR'S RESPONSIBILITY TO PROPERLY SHORE EXISTING UTILITIES IF REQUIRED BY
- 4. IT SHALL BE THE CONTRACTOR'S RESPONSIBILITY TO NOTIFY THE THE BUILDING INSPECTOR IN ADVANCE OF HIS WORK OR AS THE INSPECTOR DEEMS APPROPRIATE.
- 5. ALL CONDITIONS, LOCATIONS AND DIMENSIONS SHALL BE FIELD VERIFIED BY THE CONTRACTOR AND THE OWNER/ENGINEER NOTIFIED IN WRITING OF ANY DISCREPANCIES PRIOR TO THE START OF WORK. THE
- OWNER/ENGINEER WILL EVALUATE THE SITUATION AND MODIFY THE PLAN AS NECESSARY. 6. ALL CHANGES MADE TO THIS PLAN SHALL BE APPROVED BY THE ENGINEER WHOSE SEAL APPEARS ON THESE DRAWINGS. ANY UNAUTHORIZED ALTERATION OR ADDITIONS TO THIS DRAWING IS A VIOLATION OF SECTION 7209 (2) OF THE NEW YORK STATE EDUCATION LAW.
- 7. THE CONTRACTOR SHALL SUPERVISE AND DIRECT THE WORK USING HIS BEST SKILL AND ATTENTION. HE SHALL BE SOLELY RESPONSIBLE FOR ALL CONSTRUCTION MEANS, METHODS,
- TECHNIQUES, SEQUENCES, AND PROCEDURES AND FOR COORDINATING ALL PORTIONS OF THE WORK UNDER THIS CONTRACT.
- 8. THE CONTRACTOR SHALL BE RESPONSIBLE TO THE OWNER FOR THE ACTS AND OMISSIONS OF HIS EMPLOYEES, SUBCONTRACTORS, AND THEIR AGENTS AND EMPLOYEES, AND ANY OTHER PERSONS PERFORMING ANY OF THE WORK UNDER A CONTRACT WITH THE CONTRACTOR.
- 9. THE CONTRACTOR SHALL VERIFY ALL SUBSTRUCTURES ENCOUNTERED DURING CONSTRUCTION.
- 10. THE CONTRACTOR SHALL SECURE & PAY FOR A BUILDERS RISK POLICY TO COVER THE PERIOD OF CONSTRUCTION. THE ENGINEER & OWNER SHALL BE NAMED AS ADDITIONAL INSURED. ALL CONTRACTORS EMPLOYED AT THE SITE SHALL BE COVERED BY WORKMAN'S COMPENSATION.

GENERAL CONSTRUCTION NOTES:

- 1. BENCH MARKS USING U.S.G.S. DATUM SHALL BE OF SUCH ELEVATION THAT THE GROUND WILL SLOPE AWAY FROM IT IN ALL DIRECTIONS.
- 2. CONSTRUCTION ACTIVITY SHALL BE LIMITED FROM 8:00 A.M. TO 6 P.M., AND NO CONSTRUCTION ACTIVITY SHALL OCCUR ON SUNDAYS OR LEGAL NEW YORK STATE HOLIDAYS. WHERE BLASTING IS NECESSARY, IT SHALL OCCUR FROM MONDAY THROUGH FRIDAY BETWEEN THE HOURS OF 8:00 A.M. AND 6:00 P.M. NO BLASTING SHALL OCCUR ON HOLIDAYS, SATURDAY OR SUNDAY, ALL BLASTING SHALL ALSO BE COMPLETED IN ACCORDANCE WITH THE TOWN OF OSSINING AND NEW YORK STATE BLASTING ORDINANCES.
- ANY SOIL THAT IS UNSUITABLE FOR DEVELOPMENT OF BUILDINGS OR ROADWAYS SHALL BE REMOVED FROM AREAS TO BE DEVELOPED AND SHALL BE DISPOSED OF WITHIN THE SITE IN NEW EMBANKMENTS WHERE STRUCTURAL LOADING, I.E. A BUILDING OR ROADWAY, WILL NOT TAKE PLACE. WHEN CONSTRUCTION IS PROPOSED TO OCCUR IN SPECIFIC AREAS WHERE SOILS ARE OF QUESTIONABLE SUITABILITY, THE APPLICANT SHALL PROVIDE SOILS ENGINEERING REPORTS AS REQUIRED BY THE PLANNING BOARD ENGINEER. PRIOR TO THE CONSTRUCTION OF ROADWAYS AND, AS REQUIRED BY THE BUILDING INSPECTOR, PRIOR TO THE ISSUANCE OF A BUILDING PERMIT.
- 4. NO TOPSOIL SHALL BE REMOVED FROM THE SITE.
- 5. ROCK CUT STABILITY IS TO BE FIELD VERIFIED BY GEOTECHNICAL ENGINEER AND SHALL BE MODIFIED IF REQUIRED.
- 6. NO CRUSHING/PROCESSING IS PERMITTED ON THE SITE WITHOUT PRIOR APPROVAL BY THE TOWN OF OSSINING

GENERAL STORM DRAINAGE & UTILITY NOTES

- 1. ALL UTILITIES, INCLUDING ELECTRIC LINES, TELEPHONE, WATER, SANITARY SEWER LINES, AND STORM SEWER LINES SHALL BE LOCATED UNDERGROUND AND SHALL BE INSTALLED IN ACCORDANCE WITH THE REQUIREMENTS OF THE TOWN OF OSSINING AND THE UTILITY COMPANIES HAVING JURISDICTION.
- 2. LOCATION OF GAS AND WATER VALVES, ELECTRIC AND TELEPHONE POLES ARE TO BE DETERMINED BY PROPER AUTHORITIES AND APPROVED. AS TO LOCATION. BY THE TOWN ENGINEER.
- 3. EACH BUILDING CONSTRUCTED HEREON SHALL BE OF SUCH AN ELEVATION THAT THE GROUND WILL SLOPE AWAY FROM IT IN ALL DIRECTIONS. IN THE EVENT THAT THIS IS NOT FEASIBLE, THE CONTRACTOR SHALL INSTALL TYPICAL YARD DRAINS AS REQUIRED AND CONNECT THEM TO THE STORM DRAINAGE SYSTEM OR AS DIRECTED BY THE PROJECT ENGINEER.
- 1. ROOF LEADERS AND FOOTING DRAINS SHALL EMPTY INTO THE STORM DRAINAGE SYSTEM OR DISCHARGE DIRECTLY TO STORMWATER MANAGEMENT SYSTEMS IF GRADES PERMIT, AND CONNECTION TO THE STORM SYSTEM IS NOT FEASIBLE, FOOTING DRAINS ONLY MAY DISCHARGE TO DAYLIGHT AT THE REAR OF BUILDINGS. FOOTING DRAINS SHALL EXTEND A MINIMUM OF 30 FT. FROM THE REAR FACE OF THE BUILDING WHEN POSSIBLE. UNDER NO CIRCUMSTANCES SHALL THE DISCHARGE OF GROUND WATER OR STORM WATER, EITHER BY GRAVITY OR BY PUMPING, BE DISCHARGED TO ANY SANITARY SEWER SYSTEM.
- 5. ANY REVISIONS AND/OR ADDITIONS TO THE ROAD STORM DRAINAGE SYSTEMS CURRENTLY SHOWN ON THE PLANS WHICH ARE DEEMED NECESSARY DURING CONSTRUCTION MUST BE MADE BY THE CONTRACTOR AS REQUIRED BY THE TOWN AND SHALL BE SHOWN ON THE AS-BUILT DRAWINGS.
- 6. STORM DRAIN PIPING TO BE HIGH DENSITY POLYETHYLENE AS SHOWN ON THE CONSTRUCTION DRAWINGS. MINIMUM COVER TO BE 2' UNLESS OTHERWISE NOTED.
- 7. INTERCEPTOR DRAINS ARE TO BE INSTALLED WHERE REQUIRED BY THE TOWN OR PROJECT ENGINEER DURING ROAD CONSTRUCTION.
- 8. ALL EXISTING UNDERGROUND DRAINS ENCOUNTERED DURING CONSTRUCTION OF PROPOSED ROADS ARE TO BE CONNECTED TO PROPOSED DRAINAGE IMPROVEMENTS. CONNECTIONS TO BE APPROVED BY THE TOWN ENGINEER
- 9. PRIOR TO FINAL APPROVAL AND OPERATION OF DRAINAGE SYSTEM, CONTRACTOR SHALL CLEAR ALL ACCUMULATED SEDIMENT AND/OR DEBRIS FROM DRAINAGE STRUCTURES, MANHOLES, CULVERTS, OUTLETS AND DRAIN INLETS. ENGINEER SHALL BE NOTIFIED FOR FINAL INSPECTION.

TE: UNAUTHORIZED ALTERATIONS OR ADDITIONS TO THIS DRAWING IS A VIOLATION OF SECTION 7209 (2) OF THE NEW YORK STATE EDUCATION LAW

- 10. ALL STRUCTURES SHALL BE SET ONE INCH BELOW PAVEMENT.
- 11. STREET OPENING PERMIT FROM THE TOWN OF OSSINING D.P.W. MAY BE REQUIRED FOR INSTALLATIONS IN PUBLIC ROADS.

WALL NOTES:

GEOTECHINICAL ENGINEER.

- 1. EXCAVATION IN GENERAL SHALL CONFORM TO THE LINES AND GRADES SHOWN ON THE CONTRACT DRAWINGS.
- 2. THE ENGINEER SHALL BE NOTIFIED OF UNSUITABLE SUB-GRADE SOILS PRIOR TO PLACEMENT
- 3. WALLS TO BE CONSTRUCTED ON VIRGIN IN-SITU SOIL SHALL HAVE A MINIMUM ALLOWABLE BEARING CAPACITY OF 2 TSF. ALL OTHER CONDITIONS SHALL BE APPROVED BY THE
- 4. TO INSURE A PROPER BEARING SURFACE, THE WALL SHALL BE CONSTRUCTED ON NATURAL IN-SITU SOIL, THE CONTRACTOR SHALL STRIP ALL TOP SOIL. THE AREA SHALL THEN BE COMPACTED USING SUITABLE COMPACTION EQUIPMENT. A MINIMUM OF 3 PASSES SHALL BE MADE.
- 6. SOILS USED AS BACKFILL SHALL CONSIST OF CLEAN DRY SOIL. THE MATERIAL SHALL BE GRANULAR AND FREE OF ORGANIC OR OTHER DELETERIOUS MATERIAL. IN GENERAL THE SOIL SHALL BE NON-PLASTIC WITH A PLASTICITY INDEX LESS THAN 5 AND SHALL CONFORM TO THE AASHTO SOIL CLASSIFICATION SYSTEM FOR AN "A-1-A" SOIL . HOWEVER THE MAXIMUM SIZE SHALL BE 6". IN GENERAL ALL FILL SHALL BE APPROVED BY THE ENGINEER PRIOR TO IT'S USE. WET MATERIAL OR UNSUITABLE MATERIAL SHOULD NOT BE USED.
- 7. BACKFILL SHALL BE PLACED AND COMPACTED IN A MAXIMUM 12" LIFTS.

5. WALLS SHALL NOT BE CONSTRUCTED ON WET OR FROZEN GROUND.

- 8. ALL BOULDER RETAINING WALLS SHALL HAVE A GEOTEXTILE FABRIC BACKING FOR THE FULL HIEGHT OF THE WALL AS MANUFACTURED BY MIRAFI OR APPROVED EQUAL.
- 9. IF GROUNDWATER IS ENCOUNTERED, THE ENGINEER SHALL BE NOTIFIED IMMEDIATELY TO DETERMINE IF THE ADDITION OF AN UNDERDRAIN MAY BE REQUIRED.
- 10. THE CONTRACTOR SHALL NOT USE LARGE OR HEAVY CONSTRICTION EQUIPMENT WITHIN 5' OF THE RETAINING WALLS OR NEW FOUNDATION WALLS. HAND OPERATED COMPACTING
- EQUIPMENT SHALL BE USED WITHIN 5' OF THE WALL FACE. 11. ALTERNATE WALL DESIGNS MUST BE SEALED BY A NEW YORK STATE LICENSED PROFESSIONAL
- ENGINEER THE MINIMUM FACTORS OF SAFETY FOR SLIDING AND OVERTURNING SHALL BE 2.0. 12. ALTERNATE WALL DESIGNS MUST BE SEALED BY A NEW YORK STATE LICENSED PROFESSIONAL

ENGINEER THE MINIMUM FACTORS OF SAFETY FOR SLIDING AND OVERTURNING SHALL BE 2.0.

WATERMAIN NOTES

DISTRIBUTION SYSTEM - WATERMAIN

THE CONTRACTOR SHALL PERFORM THE NECESSARY EXCAVATION, BACKFILLING, CLEARING, GRUBBING, SHEETING, SHORING, DO ALL SHAPING OF TRENCHES, PUMPING AND BAILING, LAYING AND JOINING OF ALL PIPES, PROTECT AND SUPPORT EXISTING STRUCTURES AND REPAIR THEM, IF DAMAGED, AND ALL ELSE NECESSARY TO COMPLETE THE WORK.

THE CONTRACTOR SHALL FURNISH ALL MATERIALS, EQUIPMENT, LABOR, AND TOOLS NECESSARY TO COMPLETE THE WORK IN A SAFE, NEAT, AND WORKMANLIKE MANNER.

B. SITE AND ACCESS CLEARING (WITHIN EASEMENTS)

THE CONTRACTOR SHALL CONFINE ALL CLEARING OPERATIONS TO WITHIN THE IMMEDIATE AREAS THAT ARE ESSENTIAL FOR CONSTRUCTION OF THE WORK.

C. STOCKPILING OF SUITABLE BACKFILL MATERIAL

THE CONTRACTOR SHALL BE PREPARED WHEN EXCAVATING THE TRENCH TO SEPARATE SUITABLE BACKFILL MATERIAL FROM UNSUITABLE MATERIAL FOR USE AS BACKFILL ADJACENT

D. PROTECTION OF EXISTING STRUCTURES AND UTILITIES

SPECIAL PRECAUTIONS SHALL BE TAKEN BY THE CONTRACTOR TO PROTECT OVERHEAD POWER LINES, WATERMAINS, GAS MAINS, ELECTRIC AND TELEPHONE CONDUITS, STORM AND SANITARY SEWERS, CULVERTS, BUILDINGS AND OTHER EXISTING STRUCTURES IN AND NEAR THE EXCAVATION. IN ALL CASES, WHETHER UNDERGROUND STRUCTURES HAVE OR HAVE NOT BEEN DELINEATED, THE TOWN ENGINEER, WATER SUPERINTENDENT, OR AUTHORIZED REPRESENTATIVE ACCEPTS NO RESPONSIBILITY FOR THEIR LOCATION. 'UNDERGROUND UTILITIES" LOCATES EXISTING UNDERGROUND UTILITIES FREE OF CHARGE. THE PHONE NUMBER IS 1-800-245-2828.

GUTTERS, SEWERS, DRAINS AND DITCHES SHALL BE KEPT OPEN AT ALL TIMES FOR SURFACE DRAINAGE NO DAMMING OR PONDING OF WATER IN GUTTERS OR OTHER WATERWAYS WILL BE PERMITTED EXCEPT WHERE STREAM CROSSINGS ARE NECESSARY AND THEN ONLY TO AN EXTENT WHICH THE TOWN ENGINEER, WATER SUPERINTENDENT, OR AUTHORIZED REPRESENTATIVE SHALL CONSIDER NECESSARY THE CONTRACTOR SHALL NOT DIRECT ANY FLOW OF WATER ACROSS OR OVER PAVEMENTS EXCEPT THROUGH APPROVED PIPES OR PROPERLY CONSTRUCTED TROUGHS OF SUCH SIZES AND LENGTHS AS MAY BE REQUIRED, AND PLACE THE SAME AS DIRECTED. THE GRADING IN THE VICINITY OF TRENCHES SHALL BE CONTROLLED SO THAT THE GROUND SURFACE IS PROPERLY PITCHED TO PREVENT WATER RUNNING IN THE TRENCHING. THE CONTRACTOR SHALL NOT COMMENCE OPERATIONS INVOLVING ANY PUBLIC UTILITY BEFORE HAVING GIVEN WRITTEN NOTICE TO THE COMPANY OR OWNER, OR ITS AGENTS, AND SHALL COOPERATE WITH THE COMPANY'S OR OWNER'S FORCES IN PROTECTING AND PREVENTING DAMAGE TO THE PROPERTY.

THE CONTRACTOR WILL, AT HIS OWN EXPENSE, BE RESPONSIBLE FOR DIRECT OR INDIRECT DAMAGE THAT MAY BE DONE TO ANY UTILITY OR STRUCTURE IN THE PROSECUTION OF HIS WORK. THE LIABILITY OF THE CONTRACTOR IS ABSOLUTE AND IS NOT DEPENDENT UPON ANY QUESTIONS OF NEGLIGENCE ON HIS PART OR ON THE PART OF HIS AGENT, OR EMPLOYEES, AND THE NEGLECT OF THE TOWN ENGINEER, WATER SUPERINTENDENT, OR AUTHORIZED REPRESENTATIVE TO DIRECT THE CONTRACTOR TO TAKE ANY PARTICULAR PRECAUTION OR TO REFRAIN FROM DOING SUCH DAMAGE.

SHOULD THE POSITION OF ANY PIPE, CONDUIT, POLE OR OTHER STRUCTURES, ABOVE OR BELOW THE GROUND, BE SUCH AS TO REQUIRE ITS REMOVAL, REALIGNMENT, OR CHANGE DUE TO WORK TO BE DONE, REALIGNMENT OR CHANGE WILL BE DONE BY OR UNDER SUPERVISION OF THE OWNER OF THE OBSTRUCTIONS. THE CONTRACTOR SHALL UNCOVER AND SUSTAIN THE STRUCTURES, AFTER SUCH

THE CONTACTOR SHALL NOT INTERFERE WITH ANY PERSONS, OR WITH THE OWNER IN PROTECTING, REMOVING, CHANGING OR REPLACING THEIR PIPES, CONDUITS, POLES OR OTHER STRUCTURES; BUT HE SHALL SUFFER SAID PERSONS OR THE OWNER TO TAKE ALL SUCH MEASURES AS THEY MAY DEEM NECESSARY OR ADVISABLE FOR THE PURPOSE AFORESAID, AND THE CONTRACTOR SHALL THEREBY BE IN NO WAY RELIEVED OF ANY OF HIS RESPONSIBILITIES.

THE CONTRACTOR SHALL MAKE ALL NECESSARY ARRANGEMENTS WITH THE OWNER OF THE RESPECTIVE UTILITY PRIOR TO RELOCATION OR INTERRUPTION OF SERVICE. ALL WORK NECESSARY FOR THE RELOCATION SHALL BE PERFORMED BY THE CONTRACTOR, OR BY THE OWNER AT THE OWNER'S OPTION, AND TO THE SATISFACTION OF THE OWNER. WHERE SERVICE IS INTERRUPTED, THE CONTRACTOR SHALL COOPERATE IN RESTORING SERVICE PROMPTLY. ALL CHARGES FOR DAMAGES DONE TO UTILITIES SHALL BE PAID BY THE CONTRACTOR.

E. CONSTRUCTION OF ROAD RIGHT-OF-WAY

CONSTRUCTION IN THE ROAD RIGHT-OF-WAY SHALL AT ALL TIMES BE PERFORMED WITH MINIMUM DISTURBANCE TO TRAFFIC WITH SUFFICIENT BARRICADES AND DIRECTION. DETOURS CAN BE INSTITUTED WITH APPROVAL OF THE TOWN ENGINEER, WATER SUPERINTENDENT, OR AUTHORIZED REPRESENTATIVE, OR STATE, COUNTY, OR LOCAL AUTHORITIES. PAVEMENT SHALL BE CUT PRIOR TO REMOVAL. HOLES AND SETTLEMENTS IN THE TRENCHES SHALL BE IMMEDIATELY FILLED TO THE ORIGINAL GRADE ELEVATION WITH THE SPECIFIED MATERIALS.

F. EXCAVATION AND PREPARATION OF TRENCH

THE CONTRACTOR SHALL PROCEED WITH CAUTION IN THE EXCAVATION AND PREPARATION OF THE TRENCH SO THAT THE EXACT LOCATION OF UNDERGROUND STRUCTURES, BOTH KNOWN, AND UNKNOWN, MAY BE DETERMINED. THE TRENCH SHALL BE EXCAVATED SO THAT THE PIPE. CAN BE LAID TO THE ALIGNMENT AND DEPTH REQUIRED. MINIMUM DEPTH OF COVER FROM SURFACE OF GROUND TO TOP OF PIPE BARREL SHALL BE FOUR FEET (4'). NO TRENCH SHALL BE EXCAVATED MORE THAN FIVE HUNDRED LINEAL FEET (500 LF) IN ADVANCE OF PIPE LAYING UNLESS AUTHORIZED BY THE TOWN ENGINEER, WATER SUPERINTENDENT, OR AUTHORIZED REPRESENTATIVE. THE TRENCH SHALL BE SO BRACED AND DRAINED THAT THE WORKMEN MAY WORK THEREIN SAFELY AND EFFICIENTLY. IT IS ESSENTIAL THAT THE DISCHARGE OF THE TRENCH DEWATERING PUMPS BE CONDUCTED TO NATURAL DRAINAGE CHANNELS OR DRAINS. AS IN ACCORDANCE WITH OSHA REQUIREMENTS.

THE WIDTH OF THE TRENCH SHALL BE OF ADEQUATE SIZE TO PERMIT THE PIPE TO BE LAID AND JOINTED PROPERLY, BUT SHALL NOT EXCEED THE SUM OF TWENTY-FOUR INCHES(24") PLUS THE PIPE OUTSIDE DIAMETER, AND THE BACKFILL TO BE PLACED AND COMPACTED AS SPECIFIED.


LEDGE ROCK, BOULDERS AND LARGE STONES SHALL BE REMOVED TO PROVIDE A CLEARANCE OF AT LEAST SIX INCHES (6") BELOW AND ON EACH SIDE OF ALL PIPES AND FITTINGS.

THE TRENCH SHALL BE EXCAVATED TO THE DEPTH REQUIRED SO AS TO PROVIDE A UNIFORM AND CONTINUOUS BEARING AND SUPPORT FOR THE PIPE ON SOLID AND UNDISTURBED GROUND AT EVERY POINT. WHERE THE BOTTOM OF THE TRENCH AT A SUBGRADE IS FOUND TO BE UNSTABLE, OR TO INCLUDE ASHES, CINDERS, ALL TYPES OF REFUSE, VEGETABLE OR OTHER ORGANIC MATERIAL OR LARGE PICES OF FRAGMENTS OR INORGANIC MATERIAL WHICH IN THE JUDGEMENT OF THE TOWN ENGINEER, WATER SUPERINTENDENT, OR AUTHORIZED REPRESENTATIVE SHOULD BE REMOVED, THE CONTRACTOR SHALL EXCAVATE AND REMOVE SUCH UNSUITABLE MATERIAL TO THE WIDTH AND DEPTH ORDERED BY THE TOWN ENGINEER, WATER SUPERINTENDENT, OR AUTHORIZED REPRESENTATIVE.

ANY PART OF THE BOTTOM OF THE TRENCH EXCAVATED BELOW THE SPECIFIED GRADE SHALL BE CORRECTED WITH APPROVED BEDDING MATERIAL, SUCH AS THOROUGHLY COMPACTED CRUSHED STONE, GRAVEL, OR CONCRETE AS DIRECTED BY THE TOWN ENGINEER, WATER SUPERINTENDENT, OR AUTHORIZED REPRESENTATIVE. THE FINISHED SUBGRADE SHALL BE PREPARED ACCURATELY BY MEANS OF HAND TOOLS.

GENERAL WATER MAIN NOTES:

- ALL PROPOSED WATERMAIN MATERIALS, CONSTRUCTION AND INSTALLATION SHALL CONFORM TO ALL APPLICABLE RULES AND REGULATIONS OF THE TOWN OF OSSINING WATER DEPARTMENT AND THE WESTCHESTER COUNTY HEALTH DEPARTMENT STANDARDS AND SPECIFICATIONS.
- 2. THE RECORDS OF THE TOWN OF OSSINING INDICATE THAT THERE IS ADEQUATE WATER PRESSURE AND CAPACITY AS REQURIED TO SERVE THIS PROJECT.
- 3. ALL BACKFLOW PREVENTION DEVICES ASSOCIATED WITH THE FIRE AND DOMESTIC SERVICES FOR EACH OF THE PROPOSED OFFICE SPACES IN THE TYPE "B" UNITS SHALL BE LOCATED INTERNAL TO THE BUILDING AND SHALL REQUIRE SEPARATE APPROVAL BY THE WESTCHESTER COUNTY DEPARTMENT OF HEALTH.
- 4. ALL FIRE AND DOMESTIC SERVICE CONNECTIONS FROM THE PROPOSED WATER MAIN SHALL BE INSTALLED WITH WET TAPS AFTER THE CONTRACTOR HAS INSTALLED THE MAIN AND IT HAS BEEN APPROVED BY THE TOWN OF OSSINING WATER DEPARTMENT AND THE
- WESTCHESTER COUNTY DEPARTMENT OF HEALTH. 5. THE CONTRACTOR IS ADVISED THAT BEFORE HE CONNECTS TO THE EXISTING WATER SYSTEM, HE MUST ADVISE AND COORDINATE HIS OPERATIONS WITH THE TOWN OF OSSINING WATER DEPARTMENT'S SUPERINTENDENT. MEANS AND METHODS USED TO CONNECT TO THE EXISTING SERVICE SHALL BE APPROVED BY THE TOWN AND SHALL INCLUDE BUT NOT BE LIMITED TO WET TAPS OR OTHERWISE.
- 6. THE CONTRACTOR IS TO MAINTAIN CONSTANT FLOW AND PRESSURE IN ALL WATER MAINS AT ALL TIMES. IF THE NEED SHOULD ARISE THAT WATER SERVICE IS TO BE INTERRUPTED FOR A SHORT PERIOD, IT MUST BE COORDINATED WITH AND APPROVED BY THE ENGINEER AND THE TOWN OF OSSINING SUPERINTENDENT OF WATER.
- 7. WATER MAINS CROSSING HOUSE SEWERS, STORM SEWERS OR SANITARY SEWERS SHALL BE LAID TO PROVIDE A VERTICAL SEPARATION OF A MINIMUM OF 18" BETWEEN THE BOTTOM OF WATER MAIN AND TOP OF SEWER.
- 8. WATER MAINS PASSING UNDER HOUSE SEWERS, IN ADDITION, SHALL BE PROTECTED BY PROVIDING A VERTICAL SEPARATION OF 18" MINIMUM FROM THE BOTTOM OF THE SEWER TO THE TOP OF THE WATER MAIN AND ADEQUATE STRUCTURAL SUPPORT FOR THE SEWER TO PREVENT EXCESSIVE DEFLECTION OF THE JOINTS AND THE SEWER SETTLING AND BREAKING THE WATER MAIN. IN ADDITION THE LENGTH OF WATER PIPE IS TO BE CENTERED AT THE POINT OF CROSSING SO THAT THE JOINTS WILL BE EQUIDISTANT AND AS FAR AS POSSIBLE FROM THE SEWER. NO WATER MAIN SHALL PASS THROUGH OR COME IN CONTACT WITH ANY PART OF A SEWER OR SEWER MANHOLE.
- 9. THE COVER OVER THE TOP OF THE WATER MAIN SHALL BE A MINIMUM OF 4 FEET TO A MAXIMUM OF 5.5 FT.
- 10. WATER MAINS SHALL BE CLASS 54 DUCTILE IRON PIPES (DIP) TYTON JOINT TYPE AND FITTINGS SHALL BE FACTORY CEMENT LINED CLASS 54. ALL FITTINGS SHALL HAVE MECHANICAL JOINTS AND SHALL BE PRESSURE RATED AT 250 PSI. ALL NECESSARY JOINT MATERIALS SHALL BE FURNISHED. WATER MAINS SHALL BE INSTALLED IN ACCORDANCE WITH AWWA STANDARDS, LATEST REVISION.
- 11. ALL GATE VALVES SHALL BE MUELLER RESILIENT WEDGE (TURN LEFT OPEN) TYPE AND SHALL MEET AWWA STANDARDS, LATEST REVISION.
- 12. ALL SERVICE CONNECTIONS AND SMALL DIAMETER EXTENSIONS SHALL CONFORM TO AWWA C-151.
- 13. RETAINER GLANDS AND CONCRETE THRUST BLOCKS OR RODS SHALL BE USED AT ALL LOCATIONS WHERE RESTRAINTS EXIST.
- 14. INSTALLATION AND TESTING OF THE WATER MAIN SHALL BE INSPECTED BY THE WESTCHESTER COUNTY DEPARTMENT OF HEALTH. THE CONTRACTOR SHALL PROVIDE THE HEALTH DEPARTMENT A MINIMUM 48 HOURS NOTICE PRIOR TO ANY PRESSURE/LEAKAGE TESTS AND/OR DISINFECTION AND BACTERIOLOGICAL TESTS PERFORMED ON THE PROPOSED WATER MAIN. THE RESULTS OF THE ABOVE TESTS MUST BE ACCEPTED BY THE WCHD PRIOR TO USE OF THE MAIN.
- 15. ASBUILT DRAWINGS SHALL SHOW DIMENSIONS BETWEEN ALL VALVE TURNING NUTS AND FINISH GRADE.
- 16. INSTALLATION, DISINFECTION AND TESTING TO BE WITNESSED AND CERTIFIED BY A
- LICENSED PROFESSIONAL ENGINEER OR TOWN OF OSSINING ENGINEER 17. ALL HYDRANTS AND VALVES SHALL BE AS MANUFACTURED BY THE MUELLER COMPANY.
- 18. THE FINAL LOCATIONS OF FIRE HYDRANTS AND SIAMESE CONNECTIONS SHALL BE DETERMINED BY AND COORDINATED WITH THE TOWN OF OSSINING FIRE DEPARTMENT
- 19. IF, DURING CONSTRUCTION, IT IS FOUND THAT THE REQUIRED SEPARATION OF WATER MAINS, SANITARY SEWERS, STORM SEWERS, AND BUILDING SEWERS CANNOT BE MET, THE DEVELOPER OR HIS AUTHORIZED REPRESENTATIVE SHALL CONTACT THE WESTCHESTER COUNTY DEPARTMENT OF HEALTH. APPROVAL BY THE WCHD IS REQUIRED PRIOR TO ANY FIELD CHANGES THAT WILL AFFECT MINIMUM WATER/SEWER SEPARATION DISTANCES.
- 20. ALL TYPES OF INSTALLED PIPE SHALL BE PRESSURE TESTED AND LEAKAGE TESTED IN ACCORDANCE WITH THE LATEST EDITION OF AWWA STANDARD C-600.
- 21. ALL NEW, CLEANED OR REPAIRED WATER MAINS SHALL BE DISINFECTED AND BACTERIOLOGICAL TESTING PERFORMED IN ACCORDANCE WITH THE LATEST EDITION OF AWWA STANDARD C-651-05 (EXCEPT FOR SECTION 4.4.2 WHICH IS NOT APPROVABLE). THE SPECIFICATIONS INCLUDE DETAILED PROCEDURES FOR THE ADEQUATE FLUSHING, DISINFECTION, AND MICRO- BIOLOGICAL TESTING OF ALL WATER MAINS.
- 22. ROAD OPENINGS SHALL BE DONE IN ACCORDANCE WITH CONDITIONS OF PERMIT, AND COORDINATED WITH THE TOWN OF OSSINING.



Construction Sequence

Recommended Sequence of Construction

Use of erosion and sediment control structures and practices are important for maintaining site stability under runoff and during daily construction activities. The Construction Sequence should be staged with erosion and sediment controls, as follows, with all controls in place and implemented prior to respective infrastructure construction. As construction proceeds, the controls should be monitored, maintained and replaced as needed. Additional controls may be required as needed to address unforeseen situations.

Refer to The Construction Drawings for all plans and details which relate to the Construction Sequence. This Sequence should be followed in conjunction with all Plans, Notes, and the Stormwater Pollution Prevention Plan. Prior to the commencement of work, the Owner and General Contractor shall read and understand the Sequence for Construction. The Sequence shall be discussed at the time of the Pre-construction Meeting.

During construction of the project, the Contractor is responsible to coordinate all required inspections with various agencies and the Project Engineer.

Construction Sequence

General Sequence: The general sequence applies to the start of all Phases of the project. The requirements in such shall be applied as appropriate in that phase and shall be assumed in place prior to the start of the work outlined in the sequence for each Phase.

- 1. Prior to the beginning of any site work the major features of the construction must be field staked by a licensed surveyor. These include the building, limits of disturbance, utility lines, and Stormwater practices.
- 2. Prior to the start of the project, an on-site pre-construction meeting will be held. This will be attended by the Project Owner, the Operator responsible for complying with the approved construction drawings including the Erosion and Sediment Control (E&SC) Plan and Details, the Design Engineer, the Engineer responsible for E&SC monitoring during construction, Town representatives from the Engineering Department and Code Enforcement.
- 3. Cut and clear trees within the phase limits as necessary for the areas to be disturbed. Install tree protective measure at marked locations on E&SC Plan.
- 4. Install all temporary erosion control measures as shown on the Erosion and Sediment Control Plan for the project's immediate disturbance areas. This shall include, but not limited to silt fence, stabilized construction entrances, diversion swales, sediment traps, construction fence, etc. This sequence must be followed to insure proper implementation of the Erosion and Sediment Control Plan (E&SC) and Stormwater Pollution
- 5. Timbered trees and woodchips shall be temporarily stored in the stockpile and/or staging area if necessary before being removed off-site. Woodchips may be used for mulch to stabilize disturbed areas. Woodchip mulch shall be applied at a minimum rate of 500 lbs. per 1000 SF (2" thick minimum).
- 6. Remove existing vegetative cover, cut and clear trees, grub, remove stumps and other surface features in the limit of construction only. Any disturbance that results from tree clearing and grubbing shall be immediately stabilized with woodchips mulch, hydro-mulch, or straw and seed. Timbered trees, wood chips, and stumps shall be removed off-site unless otherwise directed. As stated woodchips may be stockpiled for use as stabilizing ground cover. Demolish and/or remove existing features, i.e.: fence, concrete slab, asphalt etc., and dispose of or stockpile as required by the Owner. All construction debris shall be properly disposed of in accordance with all Federal, State, and Local requirements.

Standard Sequence Notes for Phases I & II

8. A licensed surveyor must define the building locations.

Prevention Plan (SWPPP).

- 7. Begin rough grading the building pads for the Buildings. Begin moving the fill towards the location designated for each phase. Cut and fill of a certain phase shall meet the next phase boundary at a maximum slope of 2V:1H. For previous phases where grading is complete match to finish grade elevations. All compaction requirements shall be met within the fill sections. (This work shall include the commencement of the retaining walls around the proposed building construction.) Upon completion of the grading, temporary seed or hydro-mulch the embankment and install erosion control blankets as shown on the Plans along the northern perimeter of the fill section. During building and site construction, maintain and re-establish as required, erosion control and stabilization measures as required by the Site Plan and Details. Areas which are to remain undisturbed for more than seven (7) days shall be stabilized with temporary seeding or mulch.
- 9. Install or check condition of all temporary Erosion Control Measures as shown on the Erosion and Sediment Control Plan.
- 10. Begin preparation of the building site and excavation of the building foundation as well as construction of all retaining walls. Areas in which final grade is achieved shall be immediately stabilized with permanent vegetative cover. Permanent slopes of 3:1 or greater shall receive erosion
- 11. Begin construction of the foundation. Upon completion and after proper curing time is achieved, backfill the foundation and bring site to rough grade. Areas which are to remain undisturbed for more than seven (7) days shall be stabilized with temporary seeding or mulch.

The following phases are the general order for construction of the project and may be modified after approved by the supervising Engineer. The phasing is meant to minimize the amount of open disturbance. Under no circumstances shall multiple phases amounting to five (5) acres or greater be disturbed during the same period of time. In the event greater disturbance is necessary outside of the Phase lines shown on the Erosion and Sediment Control Plan, the Contractor shall coordinate with the Engineer of Record, and Municipality for an on-site meeting to discuss the alternative approach to the construction.

Phase I: Construction of Building 1 - The intent of this Phase is to complete the construction of Building 1, the driveways for the parking area in front of the building, the parking garage, the parking area in the rear of the building, and the landscape and hardscape included in the Phase limits shown on the Erosion and Sediment Control Plan. Additionally, any proposed drainage measures shown within the phase limits shall be put in place, but not connected until the final stabilization of Phase 2.

- 1. The Surveyor shall stake-out the proposed driveway centerlines, limits of cut and fill and the location of the temporary sediment traps.
- 2. Implement the General Sequence Notes 1 through 6 where applicable prior to continuing this Phase.
- 3. Once the tree removal operation is complete strip the topsoil within the Phase I boundary and place excavated topsoil within the identified stockpile locations. Any soils so deemed by the Design or Monitoring Engineer shall be stockpiled for future use as landscaped area topsoil. Contractor shall take every precaution feasible to reduce the amount of disturbed/exposed soils during construction.
- 4. Construct and install temporary sediment traps along the proposed access drive and rear parking area. Install the temporary filtered outlet pipe. Any disturbed area that will not be further disturbed within seven (7) days shall be immediately stabilized with woodchips, hydro-mulch, or straw and seed.
- 5. Prior to starting the work install all erosion and sediment controls including the installation of the stabilized construction entrance and sediment
- 6. Begin the removal of the existing driveway. Material shall be properly disposed of.
- 7. Begin rough grading of driveways within phase limits and adjacent areas. Slops in excess of 3H:1V shall not be left exposed and must be
- 8. Begin excavation of the building foundation for the Building and adjacent areas.

Refer to Notes 7 through 12 under the General Sequence.

- 9. Cut material shall first be moved to the fill locations required to complete the access drive and staging area and bring the area up to final grades. Excess material to be used toward infilling in Phase II shall be stockpiled. Blasted rock that is not suitable to remain on site shall be hauled away and properly disposed of. An area has been provided for the stockpiling of removed soil and rock which is to be removed from the site as well as a cueing area for trucks awaiting loading.
- 10. Proceed with the construction of Building 1. This includes the building structure itself, retaining walls, and rough grades. At any point during this begin installation of the utilities including the water and sewer connections, drainage and power utilities.
- 11. Stake-out the location of utilities and utility structures within this Phase. Temporarily relocate the staging area at the western end of the site. Begin installation of subsurface infiltration and detention chambers within Phase I limits.
- 12. When the subsurface units are installed, the upstream drainage structure shall be blocked so as to not allow sediment laden water from reaching the subsurface chambers.
- 13. Backfill as installation is complete and stabilize the area. If trenches are to be left open, place excavated material on the up-slope sides of the
- trench and protect and stabilize if it is to remain open for an extended period of seven (7) days or more. 14. Upon completion of the subsurface chambers, begin installation of proposed bypass and outlet structures. Install storm sewer piping, catch basins and manholes, working downstream to upstream. During the installation of catch basins, install inlet protection and water bar as per
- E&SC Plan to assure that sediment laden water will not enter the storm system. Once the final grade above the system is achieved, put into place the final topsoil cover, seed mix, and erosion control blanket, or hydro-mulch. Refer to the Landscape Plan for the seed mix requirements. 15. Once the infiltrator system has been installed, grade and install the base course for the driveways and parking areas. Re-establish the staging area for the construction site trailer and parking.

Note: No stormwater is permitted to enter the infiltration system from the upstream conveyance system and shall be blocked until the completion and stabilization of all Phases tributary to the basin. An area shall be considered to have achieved final stabilization when it has a minimum uniform 80% perennial vegetative cover or other permanent non-vegetative cover with a density sufficient to resist accelerated surface erosion and subsurface characteristics sufficient to resist sliding and other movements.

- 16. Complete construction of the building and remaining retaining walls within Phase limits.
- 17. Stake out and install curbing as per Plan. Once curbing is completed around catch basins, re-install inlet protection within catch basins. As curbing is complete, backfill with topsoil. Areas that are filled with topsoil are to be raked, seeded, and hay mulched.
- 18. Upon completion of the majority of the infrastructure in that phase, install pavement binder course to the thickness and elevation as per the Construction Plans
- 19. As each Phase is at the completion stage install final asphalt surface.
- 20. Install hardscape such as patios, walks steps etc., and final vegetation including sod and landscaping. Refer to Landscape Plans for location and identification of ground cover and plantings. Clear site of debris and all unwanted materials. Disposal shall be in accordance with all Federal, State, and Local requirements.
- 21. During the Final Phase of building construction, finish grade, topsoil, rake, and seed all areas as required. Where required or recommended, hydro-mulch or install erosion control blankets.
- 22. Upon completion of this Phase, the Contractor shall be required to stabilize disturbed soils in the event the disturbed area will remain not worked for greater than seven (7) days, at the direction of the Engineer of Record or permitting entity Inspector, and when significant precipitation is in the immediate forecast. All disturbed areas shall be temporarily stabilized with hydro-mulch or where appropriate woodchips. It is recommended that any grading that is at the finish stage will receive no further disturbance and that permanent stabilization such as topsoil, seed, mulching or blankets as per the Plan be installed. The next Phase cannot commence until these steps have been completed.

Phase II: Construction of Building 2 - The intent of this Phase is to complete the construction of Building 2, the main access driveway and parking for the building, the pool and recreation area located behind the building and the landscape and hardscape included in the Phase limits shown on the Erosion and Sediment Control Plan. Additionally, the any proposed drainage measures shown within the phase limits shall be put in place, but not connected until the final stabilization of Phase II.

- 1. The Surveyor shall stake-out the proposed building, drive and parking access, pool and recreation area, limits of cut and fill, and the location of
- the temporary sediment traps. 2. Strip topsoil within the Phase II boundary and place excavated topsoil within the identified stockpile locations. Any soils so deemed by the Design or Monitoring Engineer shall be stockpiled for future use as landscaped area topsoil. Contractor shall take every precaution feasible to
- reduce the amount of disturbed/exposed soils during construction. 3. Begin excavation for the building foundation for the building and adjacent areas. Refer to Notes 7 through 12 under the General Sequence.
- 4. Begin rough grading main access driveway and parking area for building 2. Connections to building 1 driveway shall be made at subgrade
- 5. Cut material shall first be moved to the fill locations required to complete and bring the areas up to final grades. Excess material to be removed from the site.
- 6. Stake-out the location of utilities and utility structures within this Phase. Install storm sewer piping, catch basins and manholes, working downstream to upstream. During the installation of catch basins, install inlet protection and water bar as per E&SC Plan to assure that sediment-laden water will not enter the storm system. Make connections to other phase utilities as necessary.
- 7. Complete construction of the building and remaining retaining walls within Phase limits. Utilities must be installed and completed before the construction of the retaining walls.
- 8. Stake out and install curbing as per Plan. Once curbing is completed around catch basins, re-install inlet protection within catch basins. As curbing is complete, backfill with topsoil. Areas that are filled with topsoil are to be raked, seeded, and hay mulched. 9. Upon completion of the majority of the infrastructure in that phase, install pavement binder course to the thickness and elevation as per the

sediment and debris. They can then be unblocked to allow for flow of collected surface runoff.

- 11. Install hardscape such as patios, walks steps etc., and final vegetation including sod and landscaping. Refer to Landscape Plans for location and identification of ground cover and plantings. Clear site of debris and all unwanted materials. Disposal shall be in accordance with all Federal, State, and Local requirements.
- 12. During the Final Phase of building construction, once final grade is achieved, place final topsoil cover, begin placement of seed mix and erosion control blanket, or hydro-mulch. Refer to the Landscape Plan for the seed mix requirements.

Final Site Stabilization and Completion of New Construction:

10. As the Phase is at the completion stage install final asphalt surface.

- 13. Upon completion of all Phases, the site shall be inspected by the Supervising Engineer and Town Inspector to determine completion of all work and permanent stabilization of the site.
- 14. Any areas deemed incomplete or not properly stabilized shall be done so to the satisfaction to the Supervising Engineer and Town Inspector. 15. Once the site is deemed adequately stable the temporary erosion and sediment control measures can be removed including the sediment traps. The area where the sediment trap was located shall be filled, top soiled, seeded and mulched in accordance with the specifications within this plan. At that time if deemed appropriate drainage structures upstream from the subsurface stormwater management systems shall be cleaned of

Contact information during and after construction:

Anthony Beldotti APB. Management 500 Executive Blvd. #203 Ossining, NY 10562 914-762-7898

GENERAL EROSION CONTROL NOTES:

- 1. CONTRACTOR SHALL BE RESPONSIBLE FOR COMPLIANCE WITH ALL SEDIMENT AND EROSION CONTROL PRACTICES. THE SEDIMENT AND EROSION CONTROL PRACTICES ARE TO BE INSTALLED PRIOR TO ANY MAJOR SOIL DISTURBANCES, AND MAINTAINED UNTIL PERMANENT PROTECTION IS ESTABLISHED. ROAD SURFACE FLOWS FROM THE SITE SHOULD BE DISSIPATED WITH TRACKING PAD OR APPROPRIATE MEASURES DURING ADJACENT ROAD SHOULDER REGRADING. CONTRACTOR IS RESPONSIBLE FOR THE INSTALLATION AND MAINTENANCE OF ALL SOIL EROSION AND SEDIMENTATION CONTROL DEVICES THROUGHOUT THE COURSE OF CONSTRUCTION.
- 2. CATCH BASIN INLET PROTECTION MUST BE INSTALLED AND OPERATING AT ALL TIMES UNTIL TRIBUTARY AREAS HAVE BEEN STABILIZED. WHEN POSSIBLE FLOWS SHOULD BE STABILIZED BEFORE REACHING INLET PROTECTION STRUCTURE. TIMELY MAINTENANCE OF SEDIMENT CONTROL STRUCTURES IS THE RESPONSIBILITY OF THE CONTRACTOR.
- 3. ALL STRUCTURES SHALL BE MAINTAINED IN GOOD WORKING ORDER AT ALL TIMES. THE SEDIMENT LEVEL IN ALL SEDIMENT TRAPS SHALL BE CLOSELY MONITORED AND SEDIMENT REMOVED PROMPTLY WHEN MAXIMUM LEVELS ARE REACHED OR AS ORDERED BY THE ENGINEER. ALL SEDIMENT CONTROL STRUCTURES SHALL BE INSPECTED ON A REGULAR BASIS, AND AFTER EACH HEAVY RAIN TO INSURE PROPER OPERATION AS DESIGNED. AN INSPECTION SCHEDULE SHALL BE SET FORTH PRIOR TO THE START OF CONSTRUCTION.
- 4. THE LOCATIONS AND THE INSTALLATION TIMES OF THE SEDIMENT CAPTURING STANDARDS SHALL BE AS SPECIFIED IN THESE PLANS. AS ORDERED BY THE ENGINEER, AND IN ACCORDANCE WITH THE LATEST EDITION OF THE "NEW YORK STANDARDS AND SPECIFICATIONS FOR EROSION AND SEDIMENT CONTROL" (NYSSESC)
- 5. ALL TOPSOIL SHALL BE PLACED IN A STABILIZED STOCKPILE FOR REUSE ON THE SITE. ALL STOCKPILE MATERIAL REQUIRED FOR FINAL GRADING AND
- STORED ON SITE SHALL BE TEMPORARILY SEEDED AND MULCHED WITHIN 7 DAYS. REFER TO SOIL STOCKPILE DETAILS. 6. ANY DISTURBED AREAS THAT WILL BE LEFT EXPOSED MORE THAN 7 DAYS AND NOT SUBJECT TO CONSTRUCTION TRAFFIC. SHALL IMMEDIATELY RECEIVE TEMPORARY SEEDING. MULCH SHALL BE USED IF THE SEASON PREVENTS THE ESTABLISHMENT OF A TEMPORARY COVER. DISTURBED
- AREAS SHALL NOT BE LIMED AND FERTILIZED PRIOR TO TEMPORARY SEEDING. 7. ALL DISTURBED AREAS WITHIN 500 FEET OF AN INHABITED DWELLING SHALL BE WETTED AS NECESSARY TO PROVIDE DUST CONTROL.
- NECESSARY DURING THE COURSE OF THE PROJECT
- 9. SEDIMENT AND EROSION CONTROL STRUCTURES SHALL BE REMOVED AND THE AREA STABILIZED WHEN THE DRAINAGE AREA HAS BEEN PROPERLY

8. THE CONTRACTOR SHALL KEEP THE ROADWAYS WITHIN THE PROJECT CLEAR OF SOIL AND DEBRIS AND IS RESPONSIBLE FOR ANY STREET CLEANING

- STABILIZED BY PERMANENT MEASURES.
- 10. ALL SEDIMENT AND EROSION CONTROL MEASURES SHALL BE INSTALLED IN ACCORDANCE WITH CURRENT EDITION OF NYSSESC.
- 11. ALL REGRADED AREAS MUST BE STABILIZED APPROPRIATELY PRIOR TO ANY ROCK BLASTING, CUTTING, AND/OR FILLING OF SOILS. SPECIAL CARE
- SHOULD BE TAKEN DURING CONSTRUCTION TO INSURE STABILITY DURING MAINTENANCE AND INTEGRITY OF CONTROL STRUCTURES. 12. ANY SLOPES GRADED AT 3:1 OR GREATER SHALL BE STABILIZED WITH EROSION BLANKETS TO BE STAKED INTO PLACE IN ACCORDANCE WITH THE MANUFACTURES REQUIREMENTS. EROSION BLANKETS MAY ALSO BE REQUIRED AT THE DISCRETION OF TOWN OFFICIALS OR PROJECT ENGINEER.
- WHEN STABILIZED BLANKET IS UTILIZED FOR CHANNEL STABILIZATION, PLACE ALL OF THE VOLUME OF SEED MIX PRIOR TO LAYING NET, OR AS RECOMMENDED BY THE MANUFACTURER. 13. TO PREVENT HEAVY CONSTRUCTION EQUIPMENT AND TRUCKS FROM TRACKING SOIL OFF-SITE, CONSTRUCT A PERVIOUS CRUSHED STONE PAD.
- LOCATE AND CONSTRUCT PADS AS DETAILED IN THESE PLANS. 14. CONTRACTOR IS RESPONSIBLE FOR CONTROLLING DUST BY SPRINKLING EXPOSED SOIL AREAS PERIODICALLY WITH WATER AS REQUIRED.
- CONTRACTOR TO SUPPLY ALL EQUIPMENT AND WATER.
- 15. CONTRACTOR SHALL BE RESPONSIBLE FOR CONSTRUCTION INSPECTIONS AS PER NYSDEC GP-0-15-002 AND TOWN OF OSSINING CODE.

MAINTENANCE OF TEMPORARY EROSION AND SEDIMENT CONTROL STRUCTURES:

- N.Y.S.D.E.C. GP-0-15-002 EXPOSURE RESTRICTIONS STATES THAT ANY EXPOSED EARTHWORK SHALL BE STABILIZED IN ACCORDANCE WITH THE GUIDELINES OF THIS PLAN. 1. TREES AND VEGETATION SHALL BE PROTECTED AT ALL TIMES AS SHOWN ON THE DETAIL DRAWING AND AS DIRECTED BY THE ENGINEER.
- 2. CARE SHOULD BE TAKEN SO AS NOT TO CHANNEL CONCENTRATED RUNOFF THROUGH THE AREAS OF CONSTRUCTION ACTIVITY ON THE SITE. 3. FILL AND SITE DISTURBANCES SHOULD NOT BE CREATED WHICH CAUSES WATER TO POND OFF SITE OR ON ADJACENT PROPERTIES.
- 4. RUNOFF FROM LAND DISTURBANCES SHALL NOT BE DISCHARGED OR HAVE THE POTENTIAL TO DISCHARGE OFF SITE WITHOUT FIRST BEING INTERCEPTED BY A CONTROL STRUCTURE, SUCH AS A SEDIMENT TRAP OR SILT FENCE. SEDIMENT SHALL BE REMOVED BEFORE EXCEEDING 50% OF THE RETENTION STRUCTURE'S CAPACITY.
- 5. FOR FINISHED GRADING, ADEQUATE GRADE SHALL BE PROVIDED SO THAT WATER WILL NOT POND ON LAWNS FOR MORE THAN 24 HOURS AFTER RAINFALL, EXCEPT IN SWALE FLOW AREAS WHICH MAY DRAIN FOR AS LONG AS 48 HOURS AFTER RAINFALL.
- 6. ALL SWALES AND OTHER AREAS OF CONCENTRATED FLOW SHALL BE PROPERLY STABILIZED WITH TEMPORARY CONTROL MEASURES TO PREVENT EROSION AND SEDIMENT TRAVEL. SURFACE FLOWS OVER CUT AND FILL AREAS SHALL BE STABILIZED AT ALL TIMES.
- 7. ALL SITES SHALL BE STABILIZED WITH EROSION CONTROL MATERIALS WITHIN 7 DAYS OF FINAL GRADING.
- 8. TEMPORARY SEDIMENT TRAPPING DEVICES SHALL BE REMOVED FROM THE SITE WITHIN 30 DAYS OF FINAL STABILIZATION.

MAINTENANCE SCHEDULE:

	DAILY	WEEKLY	MONTHLY	AFTER RAINFALL	NECESSARY TO MAINTAIN FUNCTION	AFTER APPROVAL OF INSPECTOR
SILT FENCE			INSP.	INSP.	CLEAN/ REPLACE	REMOVE
WHEEL CLEANER	CLEAN				REPLACE	REMOVE
INLET PROTECTION		INSP.	INSP.	CLEAN	REPLACE	REMOVE

MAINTENANCE OF PERMANENT CONTROL STRUCTURES DURING CONSTRUCTION

The stormwater management system and outlet structure shall be inspected on a regular basis and after every rainfall event. Sediment build up shall be removed from the inlet protection regularly to insure detention capacity and proper drainage. Outlet structure shall be free of obstructions. All piping and drain inlets shall be free of obstruction. Any sediment build up shall be removed.

MAINTENANCE OF CONTROLS AFTER CONSTRUCTION:

Controls (including respective outlet structures) should be inspected periodically for the first few months after construction and on an annual basis thereafter. They should also be inspected after major storm events. DEBRIS AND LITTER REMOVAL

Twice a year, inspect outlet structure and drain inlets for accumulated debris. Also, remove any accumulations during each mowing operation. STRUCTURAL REPAIR/REPLACEMENT

Outlet structure must be inspected twice a year for evidence of structural damage and repaired immediately.

Unstable areas tributary to the basin shall immediately be stabilized with vegetation or other appropriate erosion control measures. SEDIMENT REMOVAL

Sediment should be removed after it has reached a maximum depth of five inches above the stormwater management system floor.

TOPSOIL:

Existing topsoil will be removed and stored in piles sufficiently as to avoid mixing with other excavation. Stockpiles shall be surrounded by erosion control as outlined on these plans. The furnishing of new topsoil shall be of a better or equal to the following criteria (SS713.01 NYSDOT):

- 1. The pH of the material shall be 5.5 to 7.6.
- 2. The organic content shall not be less than 2% or more than 70%.

3.	Gradation:	SIEVE SIZE	<u>% PASSING BY WGT.</u>
		2 INCH	100
		1 INCH	85 TO 100
		1/4 INCH	65 TO 100
		NO. 200 MESH	20 TO 80

PERMANENT VEGETATIVE COVER

- 1. Site preparation: 1.1. Install erosion control measures.
- 1.2. Scarify compacted soil areas.
- Lime as required to ph 6.5.
- 1.4. Fertilize with 10-6-4 4 lbs/1,000 S.F.
- Incorporate amendments into soil with disc harrow. 2. Seed mixtures for use on swales and cut and fill areas.

<u>MIXTURE</u>		<u>LBS./ACRE</u>
ALT. A	KENTUCKY BLUE GRASS	20
	CREEPING RED FESCUE	28
	RYE GRASS OR REDTOP	5
ALT. B	CREEPING RED FESCUE	20
	REDTOP	2

- 3. SEEDING
- 3.1. Prepare seed bed by raking to remove stones, twigs, roots and other foreign material.

TALL FESCUE/SMOOTH BLOOMGRASS 20

- 3.2. Apply soil amendments and integrate into soil.
- 3.3. Apply seed uniformly by cyclone seeder culti-packer or hydro-seeder at rate indicated.
- 3.4. Stabilize seeded areas in drainage swales. 3.5. Irrigate to fully saturate soil layer, but not to dislodge planting soil.
- 3.6. Seed between April 1st and May 15th or August 15th and October 15th. 3.7. Seeding may occur May 15th and August 15th if adequate irrigation is provided.

TEMPORARY VEGETATIVE COVER: SITE PREPARATION:

- Install erosion control measures.
- 2. Scarify areas of compacted soil.
- 3. Fertilize with 10-10-10 at 400/acre.

4. Lime as required to ph 6.5.

SEED SPECIES:	
<u>MIXTURE</u>	LBS./ACRE
Rapidly germinating annual ryegrass	20
(or approved equal)	
Perennial ryegrass	20
Cereal oats	36

Same as permanent vegetative cover

OWNER / OPERATOR CERTIFICATION

"I certify under penalty of law that this document and all attachments were prepared under my direction or supervision in accordance with a system designed to assure that qualified personnel properly gathered and evaluated the information submitted. Based on my inquiry of the person or persons who manage the system, or those persons directly responsible for gathering the information, the information submitted is, to the best of my knowledge and belief, true, accurate, and complete. Further, I hereby certify that the SWPPP meets all Federal, State, and local erosion and sediment control requirements. I am aware that false statements made herein are punishable as a Class A misdemeanor pursuant to Section 210.45 of the

Penal Law."		
Name (please print):		
Title:		
Date:	_	
Address:		
Phone:		
E-mail:		
Signature:		


CONTRACTOR CERTIFICATION STATEMENT

Certification Statement - All contractors and subcontractors as identified in a SWPPP, by the Owner or Operator, in accordance with Part III.A.5 of the SPDES General Permit for Stormwater Runoff from Construction Activity, GP-0-15-002, dated January 12, 2015, Page 10 of 40, shall sign a copy of the following Certification Statement before undertaking any construction activity at the Site identified in the SWPPP:

"I hereby certify that I understand and agree to comply with the terms and conditions of the SWPPP and agree to implement any corrective actions identified by the Qualified Inspector during a site inspection. I also understand that the Owner or Operator must comply with the terms and conditions of the New York State Pollutant Discharge Elimination System ("SPDES") General Permit for Stormwater Discharge from Construction Activities and that it is unlawful for any person to cause or contribute to a violation of water quality standards. Furthermore, I understand that certifying false, incorrect or inaccurate information is a violation of the referenced permit and the laws of the State of New York and could subject me to criminal, civil and/or administrative proceedings."

Individual Contractor:	
Name and Title (please print):	
Signature of Contractor:	
Company / Contracting Firm:	
Name of Company:	
Address of Company:	
Telephone Number / Cell Number:	
Site Information:	
Address of Site:	
Todav's Date:	


onsultants sign





S

G-2

H







-1/4 CUBIC YARD OF CRUSHED


OR APPROVED EQUAL

STONE UNDER DRAIN OPENING TYPE "K" COPPER PIPE (SEE PLAN FOR SIZE)

AS PER TOWN SPECIFICATIONS

- CORPORATION STOP MUELLER H-15000

WATER SERVICE CONNECTION DETAIL



P.S.I. CONCRETE (MIN.).


Retainer glands, concrete thrust blocks and tie rods shall be used at all locations where restraints are required.

2. If groundwater is encountered within 7 feet of grade, hydrant drain holes shall be plugged. When the drains are plugged the barrels must be pumped dry after use during freezing weather. Where hydrant drains are not plugged, a gravel pocket or dry well shall be provided unless the natural soils will provide adequate drainage. Hydrant drains shall not be connected to or located within 10 feet of sanitary sewers or storm drains. 3. If hydrant is within 10 feet of sewers, hydrant drain holes shall be plugged.

4. Hydrant shall be painted with two coats of Electro- Farrothane, plastic finish, No. 44 red paint.

. All gate valves shall be Mueller AWWA standard.

FIRE HYDRANT DETAIL W-3



shall be pressure tested to assure water tightness prior to backfilling.

NOTES:


1. Any deviation from the required minimum separations shall be subject to a review and approval by the Westchester County Department of Health prior to construction

2. HORIZONTAL SEPARATION NOTES: A Water mains shall be laid at least ten (10) feet horizontally, as measured from edge to edge, from any existing or proposed sewer or drain lines. Should local conditions prevent a lateral separation of ten feet, a water main may be laid closer than ten feet to a sewer if (1) it is laid in a separate trench, or if (2) it is laid in the same trench with the water main located at one side on a bench of undisturbed earth and if in either case the elevation of the crown of the sewer or drain is at least 18 inches below the bottom of the water main B When it is impossible to obtain proper horizontal separation, as stipulated above, the sewer or drain shall be constructed of materials and with joints equivalent to the standards for the water main and

3. VERTICAL SEPARATION NOTES: A Normal conditions: whenever a water main must cross over or under a sewer or drain, the pipes shall be laid to provide a vertical separation between them of at least 18 inches, as measured from the bottom of the higher pipe to the crown of the lower pipe. B Unusual conditions: when conditions prevent a vertical separation of 18 inches, the sewer shall be constructed of materials and with joints equivalent to the water main standards and shall be pressure tested to assure water tightness prior to backfilling.

C Water main crossing over sewers: Vertical separation of 18 inches must be provided;

ii. Adequate structural support must be provided for the sewer to prevent excessive deflection of joints and settling;
iii. Full length of water pipe must be centered at the point of crossing, no joints will be permitted at the point of crossing;



	90	80	32	32	39.5
16	45	48	28	30	19.7
16	22.5	30	22	26	10.0
	11.25	20	18	12	3.8
	90	56	26	20	15.0
	45	38	22	10	7.7
12	22.5	20	20	12	3.6
	11.25	18	18	12	3.0
	90	48	22	16	8.9
	45	28	20	12	4.0
10	22.5	18	18	12	2.7
	11.25	16	16	12	2.2
	90	34	20	12	4.4
_	45	20	18	12	2.5
8	22.5	14	14	12	1.6
	11.25				(3)
	90	24	16	12	2.5
•	45	14	14	12	1.5
6	22.5	12	12	12	1.2
	11.25				(3)

BLOCK DIMENSIONS

VOLUME


1. Min. 2,500 psi concrete to be used. 2. Block dimensions are minimum and are based upon soil bearing pressure of 2,000 psf and water pressure of 150 psi. Where soil bearing is less or water pressure is greater, a


special design will be required. 3. All bolts shall be covered with burlap before pouring concrete. 4. Bend to be set against disturbed earth, backfill to be firmly tamped, or block to be furnished as directed by the engineer.

SEPARATION OF WATER MAINS, SANITARY SEWERS OR STORM SEWERS W-7

3. All bolts shall be covered with burlap before pouring concrete.

THRUST BLOCKING FOR HORIZONTAL BENDS







THRUST BLOCKING FOR TEES W-6

DET

C-503





Sile Design Consultants

Civil Engineers • Land Planners

Civil Engineers • Land Planners

51-F Underhill Avenue, Yorktown Heights, NY 1059
(914) 962-4488 • Fax: (914) 962-7386

www.sitedesignconsultants.com

SCALE:

NTS

No. Date Comments:

1 11/9/15 Town Comments
2 12/7/15 Town Comments
3 1/25/16 Town Comments
4 3/7/16 Town Comments
5 4/8/16 Town Comments
5 4/8/16 Town Comments
NYS Lic. N

NYS Lic. N


SANITARY SEWER DETAILS


S AVENUE

Westchester County, NY

SITE PLAN
PREPARED FOR
PARTH KNOLLS LLC
87 HAWKES AVENUE

C-504





MEN

C-506

	PARTS LIST	
ITEM	DESCRIPTION	SIZE
1	PRECAST MANHOLE (BY HYDRO)	48"
2	MANHOLE LID, FRAME AND COVER	30"
3	INLET PIPE (BY ADS/OTHERS)	12"
4	OUTLET PIPE (BY ADS/OTHERS)	12"
4A	REDUCER/ EXPANDER (NOT SHOWN FOR DETAIL)	18"X12"
5	PIPE COUPLING (BY ADS/OTHERS)	
6	LEDGER ANGLE	
7	SUPPORT FRAME]
8	DIP PLATE]
9	CENTER SHAFT & CONE]
10	BENCHING SKIRT	1

MATERIALS & LABOR TO ACHIEVE

FINAL GRADE (BY OTHERS)

CAPACITIES

1. PEAK TREATMENT FLOW: 3.0 CFS (85 L/S) 2. SEDIMENT STORAGE CAPACITY: 0.70 YD3 (0.54 m3) OIL STORAGE CAPACITY: 70 GALLONS (265 LITERS)

ADDITIONAL DESIGN INFORMATION

1. THE OUTLET PIPE STUB IS A ROTO-MOLDED PRODUCT WITH AN I.D. OF 12" THAT CANNOT BE MODIFIED. TO AVOID THE USE OF

A REDUCER OR EXPANDER ON THE OUTLET A 12" OUTLET PIPE SHOULD BE USED IF POSSIBLE. 2. ONLY SMALLER INLET PIPES MAY BE USED. THE INLET PIPE INVERT SHOULD BE PLACED ONE INLET PIPE DIAMETER BELOW

THE OUTLET PIPE INVERT. THE I.D. OF THE INLET PIPE SHOULD BE PLACED TANGENT TO THE I.D. OF THE MANHOLE. HEADLOSS AT 3.0 CFS WITH A 12" INLET: 8" (203 mm). HEADLOSS WILL INCREASE WITH SMALLER INLET PIPES. 3. SEDIMENT SHALL BE STORED IN A ZONE THAT IS ISOLATED FROM THE MAIN FLOW PATH AND PROTECTED FROM

RE-ENTRAINMENT BY THE BENCHING SKIRT.

Hydro International Stormwater
THE DOWNSTREAM DEFENDER ® AND FIRST DEFENSE ® ARE DESIGNED, MANUFACTURED AND SUPPLIED BY HYDRO INTERNATIONAL PLC, AND ALL TRADEMARKS ARE THE PROPERTY OF HYDRO INTERNATIONAL PLC.

THIS DRAWING HAS BEEN PREPARED BASED ON INFORMATION PROVIDED TO ADS UNDER THE DIRECTION OF THE DESIGN ENGINEER OR OTHER PROJECT REPRESENTATIVE. THE DESIGN ENGINEER SHALL REVIEW THIS DRAWING PRIOR TO CONSTRUCTION. IT IS THE ULTIMATE RESPONSIBILITY OF THE DESIGN ENGINEER TO ENSURE THAT THE PRODUCT(S) DEPICTED AND ALL ASSOCIATED DETAILS MEET V: 8	SIGNED	DATE	ADVANCED DRAIN
	DIRECTION OF THE DESIGN ENGINEER OR OT SHALL REVIEW THIS DRAWING PRIOR TO CON DESIGN ENGINEER TO ENSURE THAT THE PR	THER PROJECT REPRESENTATIVE. THE DESIGN ENGINEER NSTRUCTION. IT IS THE ULTIMATE RESPONSIBILITY OF THE ODUCT(S) DEPICTED AND ALL ASSOCIATED DETAILS MEET	TECHNIC 70 INWOOD ROCKY H V: 888 F: 866

	ADVANCED DRAINAGE SYSTEMS, INC.	
	TECHNICAL SERVICES	DATE:
ER THE	70 INWOOD ROAD, SUITE 3 ROCKY HILL, CT 06067 V: 888-892-2694	DRAW
:E1	F: 866-328-8401	CHECK

.		87 4' ONLINE [HAWKES DD - DETA			NY
S	DATE:	05-27-2015	PROJECT:	917	772	
E 3 7	DRAWN:	DWC	SCALE:	1/4	" = 1'	
	CHECKED:	MRJ	PAGE:	2	OF	3
			•			

87 HAWKES AVE - NY

1/4" = 1'

3 OF 3


PROJECT: 91772

SCALE:

PAGE:

4' ONLINE DD - PLAN VIEW

05-27-2015



_	APPROVED BY:
Hydro International stormwater	SIGNED
THE DOWNSTREAM DEFENDER ® AND FIRST	THIS DRAWING HAS BEEN PREPARED BA

	SIGNED DATE	ADVANCED DRAINAGE SYSTEMS, INC.	4	4' ONL
_		TECHNICAL SERVICES	DATE:	05-27-2
	THIS DRAWING HAS BEEN PREPARED BASED ON INFORMATION PROVIDED TO ADS UNDER THE DIRECTION OF THE DESIGN ENGINEER OR OTHER PROJECT REPRESENTATIVE. THE DESIGN ENGINEER SHALL REVIEW THIS DRAWING PRIOR TO CONSTRUCTION. IT IS THE ULTIMATE RESPONSIBILITY OF THE	70 INWOOD ROAD, SUITE 3 ROCKY HILL, CT 06067 V: 888-892-2694	DRAWN:	DWC
	DESIGN ENGINEER TO ENSURE THAT THE PRODUCT(S) DEPICTED AND ALL ASSOCIATED DETAILS MEET ALL APPLICABLE LAWS, REGULATIONS, AND PROJECT REQUIREMENTS.	F: 866-328-8401	CHECKED:	MRJ

NOTE: UNAUTHORIZED ALTERATIONS OR ADDITIONS TO THIS DRAWING IS A VIOLATION OF SECTION 7209 (2) OF THE NEW YORK STATE EDUCATION LAW

Downstream Defender® Operation and Maintenance Manual

Operation

Introduction

The Downstream Defender® operates on simple fluid hydraulics. It is self-activating, has no moving parts, no external power requirement and is manufactured from durable non-corrosive components. No manual procedures are required to operate the unit and maintenance is limited to monitoring accumulations of stored pollutants and periodic clean-outs. The Downstream Defender® has been designed to allow for easy and safe access for inspection/monitoring and clean-out procedures. Entry into the unit or removal of the internal components is not necessary for maintenance, thus safety concerns related to confined-spaceentry are avoided.

Pollutant Capture and Retention

The internal components of the Downstream Defender® have Overview volumes so that separator performance is not reduced as pollutants Defender® vessel remains wet between storm events. Oil and floatables are stored on the water surface in the outer annulus separate from the sediment storage volume in the sump of the unit providing the option for separate oil disposal, and accessories such as adsorbant pads. Since the oil/floatables and sediment storage volumes are isolated from the active separation region, the potential for re-suspension and washout of stored pollutants between clean-outs is minimized.

Wet Sump

The sump of the Downstream Defender® retains a standing water




Fig.2 Pollutant storage volumes of the Downstream Defender®.

Tel: (207) 756-6200 Fax: (207) 756-6212 Web: www.hydro-int.com

level between storm events. The water in the sump prevents stored sediment from solidifying in the base of the unit. (The clean-out procedure becomes more difficult and labor intensive if the system allows fine sediment to dry-out and consolidate. Dried sediment must be manually removed by maintenance crews. This

is a labor intensive operation in a hazardous environment.)

Blockage Protection

The Downstream Defender® has large clear openings and no internal restrictions or weirs, minimizing the risk of blockage and hydraulic losses. In addition to increasing the system headloss, orifices and internal weirs can increase the risk of blockage within

Maintenance

removing a wide range of pollutants from stormwater runoff. accumulate between clean-outs (Fig.2). The Downstream Periodic removal of these captured pollutants is essential to the continuous, long-term functioning of the Downstream Defender®. The Downstream Defender® will capture and retain sediment and oil until the sediment and oil storage volumes are full to capacity. When sediment and oil storage capacities are reached, the Downstream Defender® will no longer be able to store removed sediment and oil. Maximum pollutant storage capacities are provided in Table 1.

> Hydro International recommends that maintenance crews watch the Downstream Defender® maintenance training video at www.hydro-int.com/us/products/downstream-defender. Maintenance providers are also encouraged to participate in Hydro International's Maintenance Contractor Certification Program (see



Fig.3 Watch the Downstream Defender® instructional maintenance video at www.hydro-int.com/us/products/downstream-defender.

Hydro International (Stormwater), 94 Hutchins Drive, Portland ME 04102

Page | 5 Downstream Defender® Operation and Maintenance Manual

The Downstream Defender® allows for easy and safe inspection, Inspection Procedures monitoring and clean-out procedures. A commercially or Inspection is a simple process that does not involve entry into the municipally owned sump-vac is used to remove captured sediment Downstream Defender®. Maintenance crews should be familiar and floatables. Access ports are located in the top of the manhole. with the Downstream Defender® and its components prior to On the 6-ft (1.8m), 8-ft (2.4m), 10-ft (3.0m) and 12-ft (3.7m) units, inspection the floatables access port is above the outlet pipe between the concrete manhole wall and the dip plate. The sediment removal access ports for all Downstream Defender® models are located • It is important to inspect your Downstream Defender® every

directly over the hollow center shaft.

removal.

Maintenance events may include Inspection, Oil & Floatables Removal, and Sediment Removal. Maintenance events do not require entry into the Downstream Defender®, nor do they require the internal components of the Downstream Defender® to be removed. In the case of inspection and floatables removal, a vactor truck is not required. However, a vactor truck is required if the maintenance event is to include oil removal and/or sediment

Determining Your Maintenance Schedule

The frequency of cleanout is determined in the field after installation. During the first year of operation, the unit should be inspected every six months to determine the rate of sediment and floatables accumulation. A simple probe such as a Sludge Judge® can be used to determine the level of accumulated solids stored in the sump. This information can be recorded in the maintenance • Sediment probe (such as a Sludge Judge®) log (see page 9) to establish a routine maintenance schedule.

The vactor procedure, including both sediment and oil/floatables removal, for a 6-ft (1.8m) Downstream Defender® typically takes Downstream Defender® Maintenance Log less than 30 minutes and removes a combined water/oil volume of about 500 gallons (1900 liters).

Table 1. Downstream Defender® Pollutant Storage Capacities and Max. Cleanout Depths.

Unit Di	iameter	Total Oil	Storage		ean-out epth	Total Se Stor		Sedir Clean-ou			uid Volume noved
(ft)	(m)	(gal)	(L)	(in)	(cm)	(yd³)	(m³)	(in)	(cm)	(gal)	(L)
4	1.2	70	265	<16	<41	0.70	0.53	<18	<45	384	1,454
6	1.8	216	818	<23	<58	2.10	1.61	<24	<61	1,239	4,690
8	2.4	540	2,044	<33	<84	4.65	3.56	<30	<76	2,884	10,917
10	3.0	1,050	3,975	<42	<107	8.70	6.65	<36	<91	5,546	20,994
12	3.7	1,770	6,700	<49	<125	14.70	11.24	<42	<107	9,460	35,810

1. Refer to Dowmstream Defender® Clean-out Detail (Fig.2) for measurement of depths.

2. Oil accumulation is typically less than sediment, however, removal of oil and sediment during the same service is recommended. **3.** Remove floatables first, then remove sediment storage volume.

4. Sediment removal is not required unless sediment depths exceed 75% of maximum clean-out depths stated in Table 1.



Downstream Defender® Operation and Maintenance Manual









Inspection Procedures 1. Set up any necessary safety equipment around the access port or grate of the Downstream Defender® as stipulated by local ordinances. Safety equipment should notify passing

- pedestrian and road traffic that work is being done. 2. Remove the lids to the manhole (Fig. 4). NOTE: The 4-ft (1.2m) Downstream Defender® will only have one lid.
- 3. Without entering the vessel, look down into the chamber to inspect the inside. Make note of any irregularities. See Fig.7 and 8 for typical inspection views.
- 4. Without entering the vessel, use the pole with the skimmer net to remove floatables and loose debris from the outer annulus
- 5. Using a sediment probe such as a Sludge Judge[®], measure the depth of sediment that has collected in the sump of the vessel (Fig.5).
- 6. On the Maintenance Log (see page 9), record the date, unit location, estimated volume of floatables and gross debris removed, and the depth of sediment measured. Also note any apparent irregularities such as damaged components or blockages.





7. Securely replace the grate or lid.

8. Take down safety equipment.

9. Notify Hydro International of any irregularities noted during inspection.

Floatables and Sediment Cleanout Floatables cleanout is typically done in conjunction with sediment removal. A commercially or municipally owned sump-vac is used to remove captured sediment and floatables (Fig.6).

Floatables and loose debris can also be netted with a skimmer and pole. The access port located at the top of the manhole provides unobstructed access for a vactor hose and skimmer pole to be lowered to the base of the sump.

Scheduling

- Floatables and sump cleanout are typically conducted once a year during any season.
- If sediment depths are greater than 75% of maximum cleanout depths stated in Table 1, sediment removal is required.
- Floatables and sump cleanout should occur as soon as possible following a spill in the contributing drainage area.



Fig.8 View of outer annulus of floatables and oil collection zone.

Hydro International (Stormwater), 94 Hutchins Drive, Portland ME 04102 Tel: (207) 756-6200 Fax: (207) 756-6212 Web: www.hydro-int.com

Safety Equipment (traffic cones, etc)

- Crow bar or other tool to remove grate or lid
- Pole with skimmer or net (if only floatables are being removed)
- Sediment probe (such as a Sludge Judge®) Vactor truck (6-inch/150mm diameter flexible hose
- recommended)
- Downstream Defender® Maintenance Log

Floatables and Sediment Clean Out Procedures

- 1. Set up any necessary safety equipment around the access port or grate of the Downstream Defender® as stipulated by local ordinances. Safety equipment should notify passing pedestrian and road traffic that work is being done.
- 2. Remove the lids to the manhole NOTE: The 4-ft (1.2m) Downstream Defender® will only have one lid.
- 3. Without entering the vessel, look down into the chamber to inspect the inside. Make note of any irregularities.
- 4. Using the Floatables Port for access, remove oil and floatables stored on the surface of the water with the vactor hose or the skimmer net (Fig.9, top).
- 5. Using a sediment probe such as a Sludge Judge®, measure the depth of sediment that has collected in the sump of the vessel and record it in the Maintenance Log (Pg.9).
- Once all floatables have been removed, drop the vactor hose to the base of the sump via the Central Access Port. Vactor out the sediment and gross debris off the sump floor (Fig.6 and 9).

Downstream Defender® Operation and Maintenance Manual

- 7. Retract the vactor hose from the vessel.
- **8.** On the Maintenance Log provided by Hydro International, record the date, unit location, estimated volume of floatables and gross debris removed, and the depth of sediment measured. Also note any apparent irregularities such as

six months during the first year of operation to determine your

Typically, inspection may be conducted during any season

Sediment removal is not required unless sediment depths

Safety Equipment and Personal Protective Equipment

Crow bar or other tool to remove grate or lid

exceed 75% of maximum clean-out depths stated in Table 1

site-specific rate of pollutant accumulation

Recommended Equipment

Pole with skimmer or net

(traffic cones, work gloves, etc.)

Trash bag for removed floatables

damaged components or blockages.




Fig.9 Floatables and sediment are removed with a vactor hose


Maintenance at a Glance


Inspection	- Regularly during first year of installation - Every 6 months after the first year of installation
Oil and Floatables Removal	- Once per year, with sediment removal - Following a spill in the drainage area
Sediment Removal	- Once per year or as needed - Following a spill in the drainage area






X NDE] HE







* MAXIMUM FILL HEIGHTS OVER MANIFOLD FITTINGS. CONTACT MANUFACTURER'S REPRESENTATIVE FOR INSTALLATION CONSIDERATIONS WHEN COVER EXCEEDS 8-FT.

NOTE: UNAUTHORIZED ALTERATIONS OR ADDITIONS TO THIS DRAWING IS A VIOLATION OF SECTION 7209 (2) OF THE NEW YORK STATE EDUCATION LAW.

**60" SYSTEMS REQUIRE CLASS I BACKFILL AROUND ALL FITTINGS.

NOTES:

- 1. ALL REFERENCES TO CLASS I OR II MATERIAL ARE PER ASTM D2321 "STANDARD PRACTICE FOR UNDERGROUND INSTALLATION OF THERMOPLASTIC PIPE FOR SEWERS AND OTHER GRAVITY FLOW APPLICATIONS", LATEST EDITION.
- 2. ALL RETENTION AND DETENTION SYSTEMS SHALL BE INSTALLED IN ACCORDANCE WITH ASTM D2321, LATEST EDITION AND THE MANUFACTURER'S PUBLISHED INSTALLATION GUIDELINES.
- 3. MEASURES SHOULD BE TAKEN TO PREVENT THE MIGRATION OF NATIVE FINES INTO THE BACKFILL MATERIAL, WHEN REQUIRED. SEE ASTM D2321.
- 4. FILTER FABRIC: A GEOTEXTILE FABRIC MAY BE USED AS SPECIFIED Y THE ENGINEER TO PREVENT THE MIGRATION OF FINES FROM THE NATIVE SOIL INTO THE SELECT BACKFILL MATERIAL.
- 5. FOUNDATION: WHERE THE TRENCH BOTTOM IS UNSTABLE. THE CONTRACTOR SHALL EXCAVATE TO A DEPTH REQUIRED BY THE ENGINEER AND REPLACE WITH SUITABLE MATERIAL AS SPECIFIED BY THE ENGINEER. AS AN ALTERNATIVE AND AT THE DISCRETION OF THE DESIGN ENGINEER, THE TRENCH BOTTOM MAY BE STABILIZED USING A GEOTEXTILE MATERIAL.
- 6. BEDDING: SUITABLE MATERIAL SHALL BE CLASS I OR II. THE CONTRACTOR SHALL PROVIDE DOCUMENTATION FOR MATERIAL SPECIFICATION TO ENGINEER. UNLESS OTHERWISE NOTED BY THE ENGINEER, MINIMUM BEDDING THICKNESS SHALL BE 4" (100mm) FOR 4"-24" (100mm-600mm); 6" (150mm) FOR 30"-60" (750mm-900mm).
- 7. <u>INITIAL BACKFILL:</u> SUITABLE MATERIAL SHALL BE CLASS I OR II IN THE PIPE ZONE EXTENDING NOT LESS THAN 6" ABOVE CROWN OF PIPE. THE CONTRACTOR SHALL PROVIDE DOCUMENTATION FOR MATERIAL SPECIFICATION TO ENGINEER. MATERIAL SHALL BE INSTALLED AS REQUIRED IN ASTM D2321, LATEST EDITION.
- 8. COVER: MINIMUM COVER OVER ALL RETENTION/DETENTION SYSTEMS IN NON-TRAFFIC APPLICATIONS (GRASS OR LANDSCAPE AREAS) IS 12" FROM TOP OF PIPE TO GROUND SURFACE. ADDITIONAL COVER MAY BE REQUIRED TO PREVENT FLOATATION. FOR TRAFFIC APPLICATIONS, MINIMUM COVER IS 12" UPTO 36" DIAMETER PIPE AND 24" OF COVER FOR 42" - 60" DIAMETER PIPE, MEASURED FROM TOP OF PIPE TO BOTTOM OF FLEXIBLE PAVEMENT OR TO TOP OF RIGID PAVEMENT. MAXIMUM FILL HEIGHT LIMITED TO 8-FT OVER FITTINGS FOR STANDARD INSTALLATIONS. CONTACT A SALES REPRESENTATIVE WHEN MAXIMUM FILL HEIGHTS EXCEED 8-FT FOR INSTALLATION

ADS RETENTION/DETENTION PIPE SYSTEM SPECIFICATION

THIS SPECIFICATION DESCRIBES ADS RETENTION/DETENTION PIPE SYSTEMS FOR USE IN NON-PRESSURE GRAVITY-FLOW STORM WATER COLLECTION SYSTEMS UTILIZING A CONTINUOUS OUTFALL STRUCTURE.

- PIPE REQUIREMENTS ADS RETENTION/DETENTION SYSTEMS MAY UTILIZE ANY OF THE VARIOUS PIPE PRODUCTS BELOW:
- N-12 ST IB PIPE (PER AASHTO) SHALL MEET AASHTO M294, TYPE S OR ASTM F2306 N-12 ST IB PIPE (PER ASTM F2648) SHALL MEET ASTM F2648
- N-12 MEGA GREEN ST IB SHALL MEET ASTM F2648 N-12 WT IB PIPE (PER AASHTO) SHALL MEET AASHTO M294, TYPE S OR ASTM F2306
- N-12 WT IB PIPE (PER ASTM F2648) SHALL MEET ASTM F2648
- N-12 MEGA GREEN WT IB SHALL MEET ASTM F2648
- ALL PRODUCTS SHALL HAVE A SMOOTH INTERIOR AND ANNULAR EXTERIOR CORRUGATIONS. ALL ST IB PIPE PRODUCTS ARE AVAILABLE AS PERFORATED OR NON-PERFORATED. WT IB PIPE PRODUCTS ARE ONLY AVAILABLE AS NON-PERFORATED.

PRODUCT-SPECIFIC PIPE SPECIFICATIONS ARE AVAILABLE IN THE DRAINAGE HANDBOOK SECTION 1 SPECIFICATIONS

HAVE A BELL REINFORCED WITH A

PLAIN END /SOIL-TIGHT (ST IB): ST IB PIPE SHALL BE JOINED USING A BELL & SPIGOT JOINT. THE BELL & SPIGOT JOINT SHALL MEET THE SOIL-TIGHT REQUIREMENTS OF ASTM F2306 AND

GASKETS SHALL MEET THE REQUIREMENTS OF ASTM F477. PLAIN END PIPE & FITTINGS CONNECTIONS SHALL BE JOINED WITH COUPLING BANDS COVERING AT LEAST TWO FULL CORRUGATIONS ON EACH END OF THE PIPE. GASKETED SOIL-TIGHT COUPLING BAND CONNECTIONS SHALL INCORPORATE A CLOSED-CELL SYNTHETIC

EXPANDED RUBBER GASKET MEETING THE REQUIREMENTS OF ASTM D1056 GRADE 2A2. GASKETS, WHEN APPLICABLE, SHALL BE INSTALLED BY THE PIPE MANUFACTURER. WATERTIGHT (WT IB): WT IB PIPE SHALL BE JOINED USING A BELL & SPIGOT JOINT. THE JOINT SHALL BE WATERTIGHT ACCORDING TO THE

POLYMER COMPOSITE BAND. THE BELL TOLERANCE DEVICE SHALL BE INSTALLED BY THE MANUFACTURER. PIPE & FITTING CONNECTIONS SHALL BE WITH A BELL AND SPIGOT CONNECTION UTILIZING A SPUN-ON OR WELDED BELL GASKET. THE JOINT SHALL MEET THE WATERTIGHT REQUIREMENTS OF ASTM D3212, AND GASKETS SHALL MEET THE REQUIREMENTS OF ASTM F477. DETENTION SYSTEMS ARE SUBJECT TO GREATER LEAKAGE THAN TYPICAL SINGLE RUN STORM SEWER APPLICATIONS AND THEREFORE ARE NOT APPROPRIATE FOR APPLICATIONS REQUIRING LONG-TERM FLUID CONTAINMENT OR HYDROSTATIC PRESSURE. FOR ADDITIONAL DETAILS REFER TO

GASKETS SHALL MEET THE REQUIREMENTS OF ASTM F477. 12 - THROUGH 60 - INCH (300 TO 1500MM) DIAMETERS SHALL

FITTINGS SHALL CONFORM TO ASTM F2306 AND MEET JOINT PERFORMANCE INDICATED ABOVE FOR FITTINGS CONNECTIONS. CUSTOM FITTINGS ARE AVAILABLE AND MAY REQUIRE SPECIAL INSTALLATION CRITERION.


TECHNICAL NOTE 7.01 RAINWATER HARVESTING WITH HDPE CISTERNS.

INSTALLATION SHALL BE IN ACCORDANCE WITH ASTM D2321 AND ADS RECOMMENDED INSTALLATION GUIDELINES, WITH COVER IN NON-TRAFFIC AREAS FOR 12 - THROUGH 60 - INCH (300 TO 1500MM) DIAMETERS SHALL BE ONE FOOT (0.3M). MINIMUM COVER IN TRAFFICKED AREAS FOR 12 - THROUGH 36 - INCH (300 TO 900MM) DIAMETERS SHALL BE ONE FOOT (0.3M) AND FOR 42 - THROUGH 60 -INCH (1050 TO 1500MM) DIAMETERS, THE MINIMUM COVER SHALL BE 2 FT (0.6M). BACKFILL SHALL CONSIST OF CLASS I MATERIAL ONLY. MINIMUM COVER HEIGHTS DO NOT ACCOUNT FOR PIPE BUOYANCY. REFER TO ADS TECHNICAL NOTE 5.05 HDPE PIPE FLOTATION FOR BUOYANCY DESIGN COVER OVER SYSTEM USING STANDARD BACKFILL IS 8-FT (2.4M); CONTACT A REPRESENTATIVE WHEN MAXIMUM FILL HEIGHT MAY BE EXCEEDED ADDITIONAL INSTALLATION REQUIREMENTS ARE PROVIDED IN THE DRAINAGE HANDBOOK SECTION 6

RETENTION/DETENTION.

- 1) ALL ELEVATIONS, DIMENSIONS AND LOCATIONS OF RISERS, INLETS AND OUTLETS, SHALL BE VERIFIED BY THE ENGINEER PRIOR TO RELEASING FOR FABRICATION.
- IN SITUATIONS WHERE A FINE-GRAINED BACKFILL MATERIAL IS USED ADJACENT TO THE PIPE SYSTEM, AND ESPECIALLY INVOLVING GROUND WATER CONDITIONS, CONSIDERATION SHOULD BE GIVEN TO THE USE OF GASKETED PIPE JOINTS. AT THE VERY LEAST THE PIPE JOINTS SHOULD BE WRAPPED IN A SUITABLE, NON-WOVEN GEOTEXTILE FABRIC TO PREVENT INFILTRATION OF FINES INTO THE PIPE SYSTEM.
- 3) CONSIDERATION FOR CONSTRUCTION EQUIPMENT LOADS MUST BE TAKEN INTO ACCOUNT.
- 4) ALL PIPE DIMENSIONS ARE SUBJECT TO MANUFACTURERS TOLERANCES. 5) ALL RISERS TO BE FIELD EXTENDED OR TRIMMED TO FINAL GRADE.
- THE PROCEEDING DETAILS WERE GENERATED USING ADS DESIGN PRO®, A SOFTWARE PROGRAM DEVELOPED BY ADVANCED DRAINAGE SYSTEMS, INC. ("ADS"). THESE DRAWINGS ARE INTENDED TO DEPICT THE ADS COMPONENTS AS REQUESTED BY THE USER. ADS HAS NOT PERFORMED ANY ENGINEERING OR DESIGN SERVICES FOR THIS PROJECT, NOR HAS ADS INDEPENDENTLY VERIFIED THE INFORMATION SUPPLIED. THE INSTALLATION DETAILS PROVIDED HEREIN ARE GENERAL RECOMMENDATIONS AND ARE NOT SPECIFIC FOR THIS PROJECT. THE DESIGN ENGINEER SHALL REVIEW THESE DETAILS PRIOR TO CONSTRUCTION. IT IS THE DESIGN ENGINEERS RESPONSIBILITY TO ENSURE THE DETAILS PROVIDED HEREIN MEETS OR EXCEEDS THE APPLICABLE NATIONAL, STATE, OR LOCAL REQUIREMENTS AND TO ENSURE THAT THE DETAILS PROVIDED HEREIN ARE ACCEPTABLE FOR THIS PROJECT.





* LOAD BEARING CONCRETE COLLAR SHALL BE CONSTRUCTED IN TRAFFIC AREAS SUCH THAT THE LIVE LOAD IS TRANSMITTED TO THE SURROUNDING SOIL AND NOT DIRECTLY TO THE RISER.

